

musescore

Handbook

Downloaded from musescore.org on Jan 14 2019
Released under [Creative Commons Attribution-ShareAlike](https://creativecommons.org/licenses/by-sa/4.0/)

GETTING STARTED	17
INSTALLATION	17
INSTALL ON WINDOWS	17
Install	17
Start MuseScore	20
Uninstall	20
Troubleshooting	20
External links	20
INSTALL ON MACOS	21
Install	21
Uninstall	21
Install with Apple Remote Desktop	21
External links	21
INSTALL ON LINUX	22
Applmage	22
Step 1 - Download	22
Step 2 - Give execute permission	22
Step 3 - Run it!	22
Installing the Applmage (optional)	23
Using command line options	23
Distribution Packages	23
Fedora	23
External links	23
INSTALL ON CHROMEBOOK	23
Desktop program	24
Android app (playback only)	24
External links	24
CREATE A NEW SCORE	24
Start Center	24
Create new score	25
Enter score information	25
Choose template file	25
Choose instruments (or voice parts)	26
Add instruments	27
Add Staff / Add Linked Staff	27
Change order of instruments	28
Delete an instrument	28
Choose key signature and tempo	29
Choose time signature, pickup measure, and number of measures	29
Adjustments to score after creation	30
Add/delete measures	30
Add/edit text	30
Change instrument set-up	30
Hide a staff	30
Adjust layout and formatting	30
Templates	30
System templates folder	30
User templates folder	30
See also	31
External links	31
LANGUAGE SETTINGS AND TRANSLATION UPDATES	31
Change language	31
Update translation	31
See also	32
External links	32
CHECKING FOR UPDATES	32
Automated update check	32
Check for update	33
See also	33
BASICS	33
NOTE INPUT	33
Basic note entry	34
Step 1. Select a starting position	34
Step 2. Enter Note Input mode	34
Step 3. Select a duration	34

Step 4. Enter the note or rest	34
Select a note/rest duration	34
Input devices	34
Computer keyboard	35
Enter notes/rests	35
Move notes up/down	35
Add accidentals	35
Chords	35
Keyboard shortcuts	36
Mouse	36
MIDI keyboard	36
Virtual Piano Keyboard	37
Input modes	37
Coloring of notes outside an instrument's range	37
Small notes/small noteheads	38
Change notes or rests already entered	38
Change duration	38
Change pitch	38
Change rest to note and vice versa	38
Note properties	39
See also	39
External links	39
EDIT MODE	39
Enter/exit edit mode	39
Text	39
Lines	40
Notes	40
Offset notes	40
Adjust note stem length	40
Keyboard shortcuts	40
See also	41
PALETTES AND WORKSPACES	41
Workspaces	41
Single Palette Mode	41
Docking/undocking	41
Custom workspace	42
Palettes	42
Open/close palette	42
Apply symbols from a palette	42
Preset palettes (Advanced workspace)	42
Custom palettes	43
Palette menu	43
Behavior of applied text and lines	43
See also	44
INSPECTOR AND OBJECT PROPERTIES	44
Inspector	44
Inspector categories	44
Element	45
Element Group	45
Segment	45
Chord	45
Note	45
Select	45
Beam	46
Clef	46
Properties dialogs	46
Articulation properties	46
Fretboard diagram properties	46
Line properties	46
Measure properties	46
Staff properties	46
Text properties	46
Time signature properties	46
See also	47
MEASURE OPERATIONS	47
Select	47
Single measure	47
Range of measures	47
Insert	47
Insert an empty measure into the score	47
Insert multiple measures	47
Append	48
Append an empty measure to the end of a score	48
Append multiple measures to the end of a score	48
Delete	48
Delete a single measure	48
Delete a range of measures	48
Properties	48
Staves	48

Measure duration	49
Other	49
Exclude from measure count	49
Add to measure number	49
Layout stretch	49
Play Count (as of version 2.1) / Repeat count (prior to version 2.1)	49
Break multi-measure rests	49
Numbering	49
Split and join	50
Join measures	50
Split a measure	50
External links	50
VOICES	50
When to use voices	51
How to enter notes in different voices	51
Deleting and hiding rests	51
Restoring deleted rests	51
Exchange voices of notes	51
Move notes to another voice (without swapping)	51
See also	52
External links	52
COPY AND PASTE	52
Summary of commands	52
Notes	52
Copy or cut	52
Paste	53
Swap with Clipboard	53
Copy pitch of a single note only	53
Other elements	53
Copy or cut	53
Paste	53
Quick repeat	53
Duplicate	53
Selection filter	54
See also	54
External links	54
SELECTION MODES	54
Select a single object	54
Select a single note	54
Select a chord	54
Select a single measure	55
Select a continuous range of objects	55
1. Shift selection	55
2. Shift + click selection	55
Select a range of measures	55
3. Drag selection	55
4. Select All	55
5. Select section	55
Select a list of objects	56
Select all similar	56
What selections are useful for	57
See also	57
VIEWING AND NAVIGATION	57
View menu	57
Show sidebars/panels	57
Zoom in/out	57
Toolbars (display)	58
Show Status bar	58
Split display	58
Visibility options	58
Full screen	58
Page/Continuous View	58
Page View	59
Continuous View	59
Toolbars	59
Side panels	59
Navigation	60
Navigator	60
Find	60
See also	60
OPEN/SAVE/EXPORT/PRINT	61
Open	61
Save	61
Export	62
Print	62

See also	62
UNDO AND REDO	62
SHARE SCORES ONLINE	62
Create an account	62
Share a score directly from MuseScore	63
Upload a score on MuseScore.com	65
Edit a score on MuseScore.com	65
Switch to the direct method of updating an online score	65
External links	65
CONCERT PITCH	65
See also	66
External links	66
NOTATION	66
BARLINES	66
Change barline type	66
Insert barline	66
Custom barlines	67
Connect barlines	67
See also	67
CLEFS	67
Add a clef	68
Add clef to beginning of measure	68
Add mid-measure clef	68
Courtesy clefs	68
Remove a clef	68
Hide clefs	68
Display clef only in the first measure (for all staves)	68
Display clef only in the first measure (for a particular staff)	69
Hide all clefs in a particular staff	69
KEY SIGNATURES	69
Add a new key signature	69
Add new key signature to all staves	69
Add new key signature to one staff only	69
Replace an existing key signature	69
Replace key signature for all staves	69
Replace key signature for one staff only	69
Remove a key signature	70
Naturals on key signature changes	70
Key signature changes and multi-measure rests	70
Courtesy key signatures	70
Custom key signatures	71
TIME SIGNATURES	72
Add a time signature to a score	72
Delete a time signature	72
Create a time signature	72
Time signature properties	72
Change default beaming	73
Additive (composite) meters	73
Local time signatures	74
Pickup measures and cadenzas	74
Time signature changes and breaks	74
See also	74
External links	74
ACCIDENTALS	74
Add accidental	74
Change enharmonic spelling	75
Respell pitches	75
See also	75
External links	75
ARPEGGIOS AND GLISSANDI	75
Arpeggios	76
Glissandi (slides)	76
Adjust start and end points	76
Custom glissandi	76

Wind instrument articulations	76
Slide in/out	76
External links	77
ARTICULATIONS AND ORNAMENTS	77
Articulations	77
Ornaments	77
Add articulation/ornament	77
Add accidental to an ornament	77
Add fermata to a barline	78
Keyboard shortcuts	78
Adjust position	78
Articulation properties	78
See also	78
External links	78
BENDS	78
Apply a bend	78
Edit a bend	79
Adjust height	79
Adjust position	79
Custom bends	80
BEAMS	80
Beam symbols	80
Change note beaming	80
Adjust beam with the keyboard/mouse	81
Adjust beam angle	81
Adjust beam height	81
Adjust beam with the inspector	81
Adjust beam angle	81
Adjust beam height	81
Make the beam horizontal	81
Adjust feathered beams	81
Local relayout	81
Flip note beam	82
Reset Beam Mode	82
See also	82
External links	82
BRACKETS	82
Add	82
Delete	82
Change	83
Edit	83
Style	83
BREATHS AND PAUSES	83
Add symbol	83
Adjust position	83
Adjust pause length	83
GRACE NOTES	83
Create grace notes	84
Change pitch	84
Change duration	84
Manual adjustment	84
External links	84
HAIRPINS	84
Add a hairpin	84
Adjust length	85
Cresc. and dim. lines	85
Hairpin playback	86
LINES	86
Applying lines to the score	86
To apply a line to just one note	86
To apply a line across a range of notes	86
To apply a line from a note to the end of that measure	87
To apply a line across a range of measures	87
Adjust vertical position	87
Change length	87
Text lines	87

Custom lines and line properties	87
Copying lines	88
Extended ornament lines	88
External links	88
MEASURE RESTS	88
Full measure rest	88
To create one or more full measure rests	88
To create a full measure rest in a particular voice	88
Multimeasure rest	88
To display multimeasure rests	89
Break multimeasure rest	89
OCTAVE LINES	89
Apply an octave line	89
Change length	89
Custom lines	90
External links	90
SLURS	90
Add slur in note-input mode	90
Add slur outside note-input mode	90
Method 1	90
Method 2	90
Adjust slur	91
Extended slurs	91
Dotted slurs	91
See also	91
TIES	92
Tie notes together	92
Tie chords together	92
Add tied notes in note input mode	92
Add a tied chord in note input mode	92
Tied unison notes	93
Flip a tie	93
See also	93
External links	93
TREMOLO	93
TUPLETS	93
Create a triplet	94
Create a triplet in normal mode	94
Create a triplet in note input mode	94
Create other triplets	94
Custom triplets	94
Delete a triplet	95
Change display of triplets	95
Using the Inspector	95
Using the Style menu	96
External links	97
REPEATS AND JUMPS	97
Simple repeats	97
1st and 2nd endings	98
Playback	98
Repeat symbols and text	98
Jumps	98
Markers	99
Examples of jumps	99
See also	99
External links	99
VOLTAS	99
To add a volta to the score	99
To change the number of measures that a volta covers	100
Text	100
Playback	101
External links	101
TRANSPOSITION	101
Manual transposition	101
Automatic transposition	101
Transpose Chromatically	102

By Key	102
By Interval	102
Transpose Diatonically	102
Transposing instruments	102
Concert pitch	103
Change staff transposition	103
External links	103
DRUM NOTATION	103
Percussion staff types	103
Note input methods	103
MIDI keyboard	104
Piano keyboard	104
Computer keyboard	104
Mouse	104
Drum input palette	105
Edit Drumset	105
Roll	106
External links	106
TABLATURE	106
Create a new tablature staff	107
With the New Score wizard	107
With the Instruments dialog	108
By changing staff type	108
Edit string data	108
Change tuning	108
Add a string	109
Delete a string	109
Mark unfretted string "open"	109
Change number of instrument frets	110
Change tablature display	110
Combine pitched staff with tablature	110
Create a staff/tablature pair with the New Score wizard	110
Create a staff/tablature pair in an existing score	110
Create a staff/tablature pair from an existing staff	111
Enter notes in tablature	111
Using a computer keyboard	111
Historical tablature	111
Using a mouse	111
Select note duration	112
Edit notes	112
Note input mode	112
Non note input mode	112
Crosshead notes	112
Summary of keyboard commands	112
Note input mode	112
Normal mode	113
External links	113
SOUND AND PLAYBACK	113
MID-STAFF INSTRUMENT CHANGES	113
Instrument changes as of version 2.1	113
Instrument changes in version 2.0	113
Incompatibilities	114
Add an instrument change	114
See also	115
External links	115
MIXER	115
Mute and Solo	116
Dials	116
Sound	116
Mid-staff sound change (pizz., con sordino, etc.)	116
See also	116
External links	116
PLAY MODE	117
Playback commands	117
Start/stop playback	117
During playback	117
Play panel	117
Count in	118
Metronome playback	118
Loop playback	118
SOUNDFONTS AND SFZ FILES	118

SoundFonts	119
Install a SoundFont	119
Uninstall	119
SFZ	119
Install an SFZ	119
Uninstall	119
Synthesizer	120
List of downloadable soundfiles	120
GM SoundFonts	120
Orchestral soundfiles	120
Piano soundfiles	120
SF2 Pianos	120
SFZ Pianos	121
Unzipping downloaded soundfiles	121
Troubleshooting	121
See also	121
External links	122
SWING	122
Apply swing to a score section	122
Triplet in tempo marking	122
Return to straight rhythm	122
Apply swing globally	122
External links	122
SYNTHESIZER	123
Overview	123
Save/Load Synthesizer settings	123
Fluid	123
To load a soundfont	124
To reorder the soundfonts	124
To remove a soundfont	124
Zerberus	124
Volume	124
Effects	125
Zita 1 reverb	125
SC4 compressor	126
Tuning	126
See also	127
TEMPO	127
Add a tempo marking	127
Edit tempo	127
Edit tempo text	127
Overriding the tempo marking	128
Ritardando and accelerando playback	128
Fermatas	128
See also	128
DYNAMICS	128
Add a dynamic	129
Adjusting playback volume for a dynamic	129
Adjusting range for a dynamic	129
List of dynamics in palettes	129
Edit a dynamic	129
See also	129
External links	129
TEXT	129
TEXT BASICS	130
Add text	130
Format text	130
Adjust position of text objects	130
Text anchors	131
TEXT EDITING	131
Enter/exit text edit mode	131
Keyboard shortcuts	131
Symbols and special characters	131
Special character shortcuts	132
See also	133
TEXT STYLES AND PROPERTIES	133
Text Style	133

Edit style	133
Create a new text style	134
Apply options	135
Reset text to style	135
Save and load text styles	135
Text Properties	135
Edit properties	135
See also	135
STAFF AND SYSTEM TEXT	136
Staff text	136
System text	136
See also	136
External links	136
CHORD SYMBOLS	136
Enter a chord symbol	136
Keyboard Commands	137
Chord symbol syntax	137
Edit a chord symbol	137
Transpose chord symbols	137
Chord symbol text	137
Chord symbol style	137
Appearance	137
Note spelling	138
Automatic Capitalization	138
Positioning	138
Capo	138
FINGERING	138
Add fingering to a single note	139
Add fingering to several notes	139
Adjust position of fingering	139
Single fingering	139
Multiple fingering	139
Edit fingering text	139
LYRICS	139
Enter a lyrics line	139
First line	139
Subsequent lines	140
Special characters	140
Melisma	140
Elision (Lyric) slur / Synalepha	141
Edit Lyrics	142
Adjust position of lyrics	142
Copy lyrics to clipboard	142
Paste lyrics from clipboard	142
See also	143
External links	143
REHEARSAL MARKS	143
Add a rehearsal mark	143
Manual Placement	143
Automatic placement	143
Add an alphanumeric rehearsal mark	143
Add a measure-number rehearsal mark	143
Automatically resequence rehearsal marks	144
Text style	144
Search for a rehearsal mark	144
See also	144
External links	144
FORMATTING	144
LAYOUT AND FORMATTING	144
Ways to affect layout	144
Layout menu	145
Page Settings...	145
Reset	145
Increase Stretch/Decrease Stretch	145
Reset Stretch	145
Reset Beam Mode	145
Regroup Rhythms	146
Style menu	146
General: Score	146
General: Page	147
Distance to page margins	149
Distance between staves	149
Distance between systems	149

Lyrics Margins	149
Vertical frame margins	149
Last system fill threshold	149
Clefs and key signatures	149
General: Header, Footer, Numbers	150
General: System	151
General: Measure	152
General: Barlines	153
General: Notes	154
General: Clefs	155
General: Arpeggios	155
General: Beams	156
General: Slurs/Ties	157
General: Sizes	158
General: Hairpins, Volta, Ottava	159
General: Pedal, Trill	160
General: Chord Symbols, Fretboard Diagrams	161
General: Figured Bass	163
General: Articulations, Ornaments	164
General: Accidentals	165
General: Tuplets	166
Apply and OK buttons	167
Apply to all parts in one go	167
Save/Load style	167
See also	167
External links	167
GENERAL STYLE: MEASURE	168
Introduction	168
Options	169
PAGE SETTINGS	169
Page size	170
Odd/Even Page Margins	170
Scaling	170
Miscellaneous	170
First page number	171
Apply to all Parts	171
BREAKS AND SPACERS	171
Breaks	171
Add a break to a measure	171
Using a keyboard shortcut	171
Using a palette symbol	171
Add a break to a frame	172
Move a break	172
Delete breaks	172
Section break	172
Spacers	172
Add a spacer	173
Adjust a spacer	173
Delete a spacer	173
See also	173
FRAMES	173
Horizontal frame	173
Insert/append horizontal frame	173
Adjust width of horizontal frame	173
Add text or image to horizontal frame	174
Vertical frame	174
Insert/append vertical frame	174
Adjust height of vertical frame	174
Edit vertical frame properties	174
Add text or image to vertical frame	174
Insert horizontal frame in vertical frame	175
"Title" frame	175
Text frame	175
Insert/ append text frame	175
Edit text frame properties	175
Create a frame	175
Insert a frame into the score	175
Append a frame to the score	176
Delete a frame	176
Apply a break	176
See also	176
External links	176
IMAGES	176
Add image	176
Cut/copy and paste image	176
Modify image	176
See also	176
External links	177

IMAGE CAPTURE	177
Save a snapshot	177
Image capture menu	177
See also	178
External links	178
ALIGN ELEMENTS	178
Snap to grid	178
ADVANCED TOPICS	178
ACCESSIBILITY	178
Introduction	178
Initial setup	178
Finding your way around	179
The score window	179
Score reading	180
Moving forwards or backwards in time	180
Moving between notes at a given point in time	180
Filtering score reading	181
Score playback	181
Score editing	181
Customization	181
External links	181
ALBUMS	181
Create album	182
Load album	182
Print album	182
Join scores	182
Save album	182
CROSS-STAFF NOTATION	182
See also	183
External links	183
EARLY MUSIC FEATURES	183
Unbarred (or unmetred) notation	183
Example	184
Mensurstrich	184
Ambitus	185
Mensural time signatures	185
See also	186
FIGURED BASS	186
Adding a new figured bass indication	186
Text format	186
Digits	186
Accidentals	187
Combined shapes	187
Parentheses	187
Continuation lines	188
Duration	188
Editing existing figured basses	189
Style	189
Proper syntax	191
Summary of keys	191
FILE FORMATS	191
MuseScore native format	191
MuseScore format (*.mscz)	192
Uncompressed MuseScore format (*.mscx)	192
MuseScore backup file (*.mscz) or (*.mscx)	192
Graphic files (export only)	192
PDF (*.pdf)	192
PNG (*.png)	192
SVG (*.svg)	192
Audio files (export only)	193
WAV audio (*.wav)	193
MP3 (*.mp3)	193
FLAC audio (*.flac)	193
Ogg Vorbis (*.ogg)	193
Share with other music software	193
MusicXML (*.xml, *.musicxml)	194
Compressed MusicXML (*.mxl)	194

MIDI (*.mid, *.midi, *.kar)	194
MuseData (*.md) (import only)	194
Capella (*.cap, *.capx) (import only)	194
Bagpipe Music Writer (*.bww) (import only)	194
BB (*.mgu, *.sgu) (import only)	194
Overture (*.ove) (import only)	194
Guitar Pro (*.gtp, *.gp3, *.gp4, *.gp5, *.gpx) (import only)	194
See also	194
External links	194
FRETBOARD DIAGRAMS	194
Add a fretboard diagram	195
Edit fretboard diagram	195
Adjust position, size, color	196
Fretboard diagram style	196
MIDI IMPORT	196
Available operations	196
MASTER PALETTE	198
Symbols	198
Find a symbol	199
Apply a symbol	199
Connect symbols	199
See also	199
NOTE INPUT MODES	199
Step-time	200
Re-pitch	200
Rhythm	200
Real-time (automatic)	200
Real-time (manual)	201
Real-time Advance shortcut	201
See also	201
External links	201
NOTEHEADS	201
Notehead groups	201
Change notehead group	202
Change notehead type	202
Shared noteheads	202
Change offset noteheads to shared	202
Examples of notehead sharing	202
Remove duplicate fret marks	203
External links	203
PARTS	203
Set up all parts at once	203
Define specific parts	204
Delete a Part	205
Export the parts	205
Save the parts	205
Print a part	205
PLUGINS	205
Overview	206
Installation	206
Windows	206
macOS	206
Linux	206
Enable/disable plugins	206
Create/edit/run plugins	207
Plugins installed by default	208
ABC Import	208
Break Every X Measures	208
Notes -> Color Notes	208
Create Score	208
helloQml	208
Notes -> Note Names	208
Panel	209
random	209
random2	209
run	209
scorelist	209
ScoreView	209
Walk	209
See also	209

PREFERENCES	209
General	209
Canvas	210
Note input	211
Note Input	211
MIDI Remote Control	211
Score	212
I/O	212
API / Device	213
MIDI Input/Output/Output Latency	213
Jack Audio Server	213
Import	213
Export	213
Shortcuts	214
Update	215
See also	215
RECOVERED FILES	215
Behavior of saving after session recovery	215
Finding recovered files	216
See also	216
External links	216
SCORE PROPERTIES	216
Edit meta tags	216
Preexisting meta tags	217
Header/Footer	218
See also	219
STAFF PROPERTIES	219
Staff Types	220
Staff Properties: all staves	220
Staff Properties: plucked strings only	221
Advanced Style Properties	221
Change staff type	221
Standard and Percussion staff options	222
Tablature staff options	222
Tablature staff options: Fret Marks	222
Tablature staff options: Note Values	223
Preview	224
Change instrument	224
External links	224
TOOLS	224
Add / Remove system/line breaks	224
Explode	225
Implode	225
Apply implode to multiple staves	225
Apply implode to a single staff	225
Fill with slashes	226
Toggle rhythmic slash notation	226
Resequence rehearsal marks	226
Copy lyrics to clipboard	226
See also	226
NEW FEATURES IN MUESCORE 2	227
SEE ALSO	227
UPGRADE FROM MUESCORE 1.X	227
How to upgrade MuseScore	227
Opening 1.x scores in MuseScore 2	227
Relayout	228
Getting the sound from MuseScore 1.x	228
SUPPORT	228
HELPING IMPROVE TRANSLATIONS	228
Software translation	228
Website and handbook translation	228
See also	228
HOW TO ASK FOR SUPPORT OR FILE BUG REPORTS	228

External links	229
REVERT TO FACTORY SETTINGS	229
MuseScore 2.0.3 and above	229
MuseScore 2.0 through 2.0.2	229
Instructions for Windows	229
Instructions for MacOS	230
Instructions for Linux	230
See also	231
KNOWN INCOMPATIBILITIES	231
Hardware incompatibilities	231
Software incompatibilities	231
AVG Internet Security hangs MuseScore	231
Font problem on macOS	231
Font problem on Linux	231
Save As dialog empty on Linux	232
APPENDIX	232
KEYBOARD SHORTCUTS	232
Navigation	232
Note input	232
Duration	233
Voices	233
Pitch	233
Interval	233
Layout	233
Articulations	233
Text entry	234
Lyrics entry	234
Display	234
Miscellaneous	234
See also	234
KNOWN LIMITATIONS OF MUESCORE 2.X	234
Local time signatures	234
Regroup Rhythms	234
Tablature staff linked with standard staff	235
Mixer	235
Header & footer	235
COMMAND LINE OPTIONS	235
Qt Toolkit Options	236
See also	236
External links	237
GLOSSARY	237
External links	240
TABLE OF CONTENTS	240
GETTING STARTED	240
BASICS	240
NOTATION	241
SOUND AND PLAYBACK	241
TEXT	241
FORMATTING	241
ADVANCED TOPICS	242
NEW FEATURES IN MUESCORE 2.0	242

SUPPORT

243

APPENDIX

243

This handbook is for MuseScore version 2.0 and above. It is maintained by the MuseScore community. [Find out how you can help](#)

Getting started

This chapter helps you to install and run MuseScore for the first time. The chapter will also show you how to create a new .score

Installation

MuseScore exists for various different operating systems, including Windows and macOS, as well as many [Linux distributions](#) and several [BSD variants](#)


Install on Windows

Install


If you're on Windows 10, MuseScore can be installed from the Windows Store. Clicking [here](#) will open MuseScore's page in the Store app. There you will only have to click Get the app > and MuseScore will be downloaded and installed

Otherwise you can get the Windows installer from the [download](#) page of the MuseScore website. Click on the link to start the download. Your Internet browser will ask you to confirm that you want to download this file. Click Save File

When the download finishes, double-click on the file to start the installation. Windows may prompt you with a security window to confirm this before running the software. Click Run to continue, you'll then briefly see




followed by




In case you don't see this installer window but something else, it's possible that the .msi extension is not associated with .msiexec.exe. Either you can [fix the association](#), or download and use the [portable version of MuseScore](#) instead


Continuing you'll see




:If you click Cancel, here or later, you'll see




.If instead you click Next to continue, the setup wizard displays the terms of the free software license



Read the terms of the license, make sure the box next to "I accept the terms in the License Agreement" is checked, and .click Next to continue. Next the installer will ask you to confirm the location in which to install MuseScore




If you are installing a newer version of MuseScore but still want to keep the old version on your computer, then you should change the folder (note that MuseScore 2 can coexist with MuseScore 1 with no changes needed). Otherwise click .Next to continue




.Click Install to continue

Give the setup wizard a few minutes to install the necessary files and configurations. You'll see



and finally



.Click Finish to exit the installer. You may delete the installer file you downloaded

Start MuseScore

.To start MuseScore, from the menu, select Start → All Programs → MuseScore 2 → MuseScore 2

Uninstall

You can uninstall MuseScore from the menu by selecting Start → All Programs → MuseScore 2 → Uninstall MuseScore; or via Windows' Control Panel. Note that this will not remove your scores nor your MuseScore settings

Troubleshooting

On Windows XP and Vista, the installer might be blocked by the system. If you don't manage to install MuseScore, right click the downloaded file and click Properties. If there is a message *"This file came from another computer and might be blocked to help protect this computer"*, click on "Unblock", "OK" and double click on the downloaded file again

External links

- [How to install MuseScore on Windows without administrator rights](#) ↗ •
- [How to run MuseScore as Administrator on Windows](#) ↗ •

Install on macOS


Install

You will find the DMG (disk image) file on the [download](#) page of the MuseScore website. Click on the macOS link to start the download. When the download is complete, double-click the DMG file to mount the disk image



.Drag and drop the MuseScore icon to the Applications folder icon

If you are not logged in as administrator, macOS may ask for a password: click **Authenticate** and enter your password to proceed.



When the application has finished copying, eject the disk image. You can now launch MuseScore from the Applications folder, Spotlight, or Launchpad

Uninstall

.Simply delete MuseScore from Applications folder

Install with Apple Remote Desktop

You can deploy MuseScore to multiple computers with the "Copy" feature of ARD. Since MuseScore is a self-contained application you can simply copy the application to the '/Application' folder on the target machines. It is also possible to install multiple versions of the application as long as their names differ

External links

- [How to run MuseScore 2.x on Mac OS X 10.6](#)
- [How to change the language in MuseScore](#)

Install on Linux

As of MuseScore 2.0.3 you can, for the first time, get hold of a copy for Linux straight from the [download](#) page, just like Windows and Mac users. This is possible thanks to the [AppImage](#) packaging format, which runs on pretty much all Linux distributions. If you prefer, there is still the option to get it the traditional way via your [distribution's package manager](#) (but you may have to wait for it to get packaged by the relevant maintainer). Of course, you can always [build from source](#)

AppImage

The [AppImage format](#) is a new way of packaging Linux applications. AppImages are portable - they don't have to be installed - and they run on pretty much any Linux distribution. Dependencies are included in the one AppImage file

Step 1 - Download

Before you download an AppImage, you need to know your processor's architecture. These terminal commands will show

```
arch
```

or

```
uname -m
```

The output will be something like "i686", "x86_64" or "armv7"

- i686 (or similar) - 32-bit Intel/AMD processor (found on older machines)
- x86_64 (or similar) - 64-bit Intel/AMD processor (modern laptop and desktop computers, most Chromebooks)
- armv7 (or later) - ARM processor (phones & tablets, Raspberry Pi 2/3 running Ubuntu Mate, some Chromebooks, (usually 32-bit at present)

Now you can head over to the [download](#) page and find the AppImage that best matches your architecture. Once downloaded, the file will be named "MuseScore-X.Y.Z-(arch).AppImage"

Step 2 - Give execute permission

Before you can use the AppImage you need to give permission for it to be run as a program

From the Terminal

This command gives the user (u) permission to execute (x) the AppImage. It works on all Linux systems

```
cd ~/Downloads
chmod u+x MuseScore*.AppImage
```

Note: Use the "cd" command to change directory to wherever you saved the AppImage

From a File Manager

If you prefer to avoid the command line, there is usually a way give execute permission from inside a File Manager

In GNOME Files (Nautilus), simply

- 1 Right-click on the AppImage and select "Properties"
- 2 Open the "Permissions" tab
- 3 Enable the option labelled "Allow executing file as a program"

The process may be slightly different in other file managers

Step 3 - Run it

Now you should be able to run the program simply by double-clicking on it

When you downloaded the AppImage it was probably saved in your Downloads folder, but you can move somewhere else at any time (e.g. you could put it on your desktop for easy access). If you ever want to remove it then simply delete it

You can run the Applmage without installing it, but you must install it if you want it to be completely integrated with your desktop environment. This has the following benefits

- Adds the Applmage to your Applications Menu or Launcher
- (Sets the correct icons for MuseScore's files (MSCZ, MSCX) and for MusicXML files (MXL, XML
- Makes the Applmage available via your File Manager's right-click "Open with..." menu

To install it, run the Applmage from the Terminal with the "install" option see immediately below). This copies a desktop file and various icons to your computer. If you want to remove them you will need to run the "remove" option before you delete the Applmage. This does not affect any scores created with any version of MuseScore

Using command line options

Running the Applmage from the Terminal allows you to use various command line options. The Applmage has some special options in addition to MuseScore's normal command line options

:You will need to change directory (cd) to wherever the Applmage is saved your system, for example

```
cd ~/Desktop
[...MuseScore*.Applmage [option/.
```

:Or give the path to the Applmage

```
[...desktop/MuseScore*.Applmage [option/~
```

:Use the "--help" and "man" options to get more information about the available command line options

```
MuseScore*.Applmage --help # displays a complete list of command line options/.
(MuseScore*.Applmage man # displays the manual page (explains what the options do).
```

Distribution Packages

Fedora

:Import the GPG key .1

```
rpm --import http://prereleases.musescore.org/linux/Fedora/RPM-GPG-KEY-Seve
su
```

Go to the download [page](#) of the MuseScore website. Click on the link for the stable Fedora download and choose .2 the correct rpm package for your architecture

Depending on your architecture, use one of the two sets of commands to install MuseScore .3

for arch i386 ◦

```
su
yum localinstall musescore-X.Y-1.fc10.i386.rpm
```

for arch x86_64 ◦

```
su
yum localinstall musescore-X.Y-1.fc10.x86_64.rpm
```

.If you have difficulty with sound, see Fedora 11 and sound [page](#) .See also the hints for the various distributions on the download page [page](#)

External links

- How to run the MuseScore Applmage on Linux [page](#) - video
- How to change the language in MuseScore [page](#)

Install on Chromebook

MuseScore's desktop program will not work natively on Chrome OS, but there are some workaround solutions

Since Chrome OS 69, certain chromebook models are able to run Linux apps and so you can install MuseScore for Linux as provided on our [Download page](#). Feedback about the installation process and supported hardware is welcome on the [forum](#)

Via software-on-demand service such as [rollApp](#): By just visiting this website, you can run MuseScore in the browser. You can access your scores via cloud services such as Google Drive or save them to your online MuseScore account through the menu File → Save Online.... Note that currently, sound and playback does not work on [rollApp](#)

Via [Crouton](#): Involves installing a Linux based operating system which runs in parallel with Chrome OS, and then installing MuseScore on Linux

(Android app (playback only

Alternatively, it is possible to install [MuseScore's Android app](#) on recent Chromebooks. You will need to update to the latest version of Chrome OS first. See the Chromebook support documentation for help [installing Android apps on Chromebooks](#), and a [list of supported devices](#). The app only supports playback of existing scores, not score editing or creation, but you can sign-in to your MuseScore account for easy access to all your scores on MuseScore.com

External links


- [How to run MuseScore on a Chromebook](#)
- Check the installation procedure from [the comments in this thread](#)
- [How to change the language in MuseScore](#)

Create a new score

To create a new score, open the [New Score Wizard](#) (see [Create new score](#), below): this can also be accessed via the [Start Center](#)

Start Center

This is the window that displays when you open MuseScore for the very first time



:To open the Start Center (if not already visible), use any of the following options

- .Press F4
- ...From the menu bar, select View → Start Center

:From the Start Center you can

- .Open the "**Getting Started**" tutorial score
- .View thumbnails of previously-opened scores: click on a thumbnail to open it
- ... Open a score from your computer's file system: click onOpen a score
- .(Create a new score (by clicking on the icon with the plus sign
- .See the "In the spotlight" score of the day
- .Search sheet music on musecore.com ↗
- Link to mobile apps
- Link to follow MuseScore on social networks


Create new score

:To open the **New Score Wizard** when the Start Center is not open, use one of the following options

- ;Click on the New Score icon in the toolbar on the top left of the window
- ;(Use keyboard shortcut Ctrl+N (Mac: Cmd+N
-From the menu, select File → New

.**Note:** The following subheadings may differ slightly in versions prior to MuseScore 2.2


Enter score information



.Step 1: Enter score information

Enter the title, composer, or any other information as shown above, then click onNext >. This step is optional: you can also
.(add this information after the score is created (see [Vertical frame](#)

Choose template file





.Step 2: Choose template file

Here, you can choose from a range of solo, ensemble and orchestral *templates*. Any custom *templates* stored in your *user templates folder* will be displayed under the heading, '**Custom Templates**'. From version 2.2, you can use the **Search bar** (top right) to find specific templates

- Click on a template to select it. This will automatically take you to the next page of the Wizard
- **Choose key signature** (and tempo)
 - **Choose Instruments** ("template" (under "General

(Choose instruments (or voice parts)





The **Choose Instruments** window is divided into two columns

The **left column** contains a list of instruments, or voice parts to choose from. This list is categorized into instrument families, and clicking a category shows the full list of instruments in each family

The default entry is "Common instruments" but you can choose from others, including "Jazz instruments" and "Early music". There is a search box at the bottom of the instrument window: typing the name of an instrument there will search for it in "All instruments"

The **right column** starts off empty, but will eventually contain a list of instruments for your new score in the order that they will appear

Add instruments

To add instruments to the score, use any of the following options

- Select one or more instruments in the left column and click **Add**
- Double-click an instrument in the left column



The instrument names, and their associated staff lines, now appear in the list of instruments in the right column. You can add more instruments or voice parts, as needed. Each instrument added in this way is allocated its own Mixer channel

Note: If you want staves to share the same instrument, use the Add staff or Add linked staff commands instead (see below)

Add Staff / Add Linked Staff

To add a staff to an *existing* instrument in the score

1. Select a staff in the score list on the right-hand side (e.g. see "Staff 1" in the image below). Click **Add Staff** or **Add Linked Staff**
2. Adjust the **Staff type**, if applicable



:Summary of commands

Examples	Share mixer ?channel	?Edit staves independently	Staff added	Command
Guitar staff/tab, Piano grand staff	Yes	Yes	Unlinked	Add Staff
Guitar staff/tab	Yes	No. Edit in one staff updates others	Linked	Add Linked Staff

.See also, [Combine pitched staff with tablature](#)

Change order of instruments

:To change the order of instruments (or staves) in the score


Click either an instrument name or a staff, in the right-hand column, and use the or buttons to move it .higher/lower

Delete an instrument

To **delete** an instrument, or staff line, from the score

.Select an instrument, or a staff line, in the right-hand column, and click **Remove** •


Choose key signature and tempo



.Step 3: Choose key signature and tempo

The wizard asks for two things: The initial key signature and tempo of the score. Select any of the former and click **Next >** .to continue. An initial tempo can be set here too

Choose time signature, pickup measure, and number of measures



.Step 4: Choose time signature etc

You can set your initial **time signature** here. If the score starts with a **pickup measure** (also known as an *anacrusis* or *.upbeat* measure), then mark the **Pickup measure** checkbox and adjust the "Duration" accordingly

Measures is set to 32 by default: you can change the number here, or add/remove measures later from the score

.Click Finish to create your new score

Adjustments to score after creation

:Any settings you make in the New Score Wizard can always be changed when you start work on the score itself

Add/delete measures

.To add/delete measures or create a pickup measure, see Measure operations

Add/edit text

.To add text, see Add text (Text basics). To change existing text, see Text editing

Change instrument set-up

To add, delete, or change the order of instruments: from the menu, select Edit → Instruments...; or use the keyboard shortcut,

i. This opens the **Instruments** dialog which is virtually identical to the Choose Instruments dialog in the **New Score**

.(**Wizard** (see above

).(See also Change instrument (Staff properties

Hide a staff

To hide a staff permanently: Open the Instruments dialog (i) and untick the "Visible" box for that staff •

To hide a staff under certain conditions: See the "Hide" options in the Score menu, and Staff Properties •

Adjust layout and formatting

.To adjust the distance between staves and systems, set page margins etc., see Layout and formatting

Templates

A **Template** is simply a standard MuseScore file that has been stored in one of two "templates" folders: any files in these folders are automatically displayed on the "Chose template file" page of the New Score Wizard. Two templates folders are

:created by default

.A system templates folder •

.A user templates folder •

System templates folder

This folder contains the templates installed with MuseScore and *should not* be modified. It can be found in the following

:locations

Windows: Usually at C:\Program Files\MuseScore 2\templates; or in the 64-bit versions at C:\Program Files (x86)\MuseScore 2\templates

Linux: Under /usr/share/mscore-xxx if you installed from the package manager. If you compiled MuseScore on Linux yourself,

.(then look under /usr/local/share/mscore-xxx (with xxx being the version you are using

MacOS: Under /Applications/MuseScore 2.app/Contents/Resources/templates

User templates folder

Any templates that you create for future use should be stored here. Once in the user "templates" folder, they will automatically appear on the "Chose template file" page of the New Score Wizard—under the heading "Custom

.Templates". **Note:** prior to version 2.3, you need to restart MuseScore in order to see a newly-added template

:The default location of the user templates folder is as follows

Windows: %HOMEPATH%\Documents\MuseScore2\Templates

MacOS and Linux: ~/Documents/MuseScore2/Templates

:To configure the location of your private templates folder

.From the menu, select Edit → Preferences... → General •

See also

- [Key signature](#)
- [Time signature](#)
- [Clef](#)
- [Tempo](#)
- [Staff properties](#)

External links

[Video tutorial: MuseScore in Minutes: Lesson 1 - Score Setup](#) ↗ •


Language settings and translation updates

MuseScore will be installed and work with your "System" language (the one used for most programs, and generally .(depending on your country and the language settings of the PC, or account

Change language

;(...From the menu, select Edit → Preferences... (Mac: MuseScore → Preferences .1

:In the General tab, select the desired language from the drop-down list in the Language section .2



To update translations, click on the Update translations button. Then click on the Update buttons for the languages you .3
.(want to update (for an alternative method, see [below](#)


.As then indicated, you will have to exit and reopen MuseScore for changes and updates to take effect

Update translation

:You can update the translation as explained above, via the preferences settings, but there is another method

;From the menu, select Help → Resource Manager .1

.Click on the Update buttons for the languages you want to update .2



.Here too you will have to exit and reopen MuseScore for the update to take effect

See also

[Helping and improve translation](#) •

External links


[How to change the language in MuseScore](#) ↗ •

Checking for updates

.There are two ways to check for updates

Automated update check

;(...From the menu, select Edit → Preferences... (Mac: MuseScore → Preferences .1
:Select the Update tab .2




".Tick the box marked "Check for new version of MuseScore .3

.Now MuseScore will check for updates on every start and notify you, if need be

Check for update

:From the menu, select Help → Check for Update .1



A dialog will appear with the update status: either "No Update Available" or "An update for MuseScore is available:" .2
.followed by a link to download it

Note: These options are only available in the Mac and Windows versions of MuseScore (except the version from the Windows Store), as only those can be updated directly from MuseScore.org. Linux distributions (and the Windows Store) .have different mechanisms to make updates available

See also

[Preferences: Update](#) •

Basics

The previous "[Getting started](#)" chapter guides you through the [installation](#) and process for [creating a new score](#). The .["Basics"](#) chapter gives an overview of MuseScore and describes the general methods for interacting with the score

Note input

MuseScore allows you to enter music notation from *any* of four [input devices](#): computer keyboard, mouse, MIDI keyboard, or virtual piano keyboard. The default [input mode](#) is **step-time**, in which notes or rests are entered one at a time. .However, other [input modes](#) are also available

:After exiting the [New Score Wizard](#), your new score will consist of a series of measures filled with measure rests



:As you enter notes in a measure, the measure rests are changed to appropriate rests to fill the remainder of the measure



:Notes of different durations on the same beat are entered by using [Voices](#)



This section introduces you to the basics of entering notes and rests in step-time from a *computer keyboard*. It is also recommended that you work through the tutorial, "Getting Started: An introduction to note entry in MuseScore". This is available from the [Start Center](#)

Step 1. Select a starting position

Select a starting position for note input by clicking on a note or rest, or selecting a measure, with the mouse. If you don't select a starting point, the cursor automatically defaults to the beginning of the score when you enter **Note Input** mode. ("Step 2" [below](#))

Step 2. Enter Note Input mode

To enter **Note Input** mode, use either of the following options

- (Click on the "N" button (on the extreme left of the **Note Input** toolbar
- .Press N on your computer keyboard

To exit **Note Input** mode, use any of the following options

- .Press N
- .Press Esc
- .Click on the toolbar "N" button

Step 3. Select a duration

Still in **Note Input** mode, select a note duration using either of the following

- (Click on a corresponding note icon in the **Note Input toolbar** (directly above the document window
- (Enter the keyboard shortcut for that duration (see [below](#))

Step 4. Enter the note or rest

- .To enter a note pitch from A–G, simply click on the corresponding letter on your computer keyboard
- (To enter a rest, press 0 (zero)

This method of entry also works if you are *not* in Note Input mode—as long as you have a note/rest selected, or the score (is newly-created (in which case note entry will default to the beginning

Note: Note input in MuseScore *overwrites* existing notes or rests in a measure. If you need to *insert* notes you can make room for them by moving a section of the score using the [copy and paste](#) command. You can also insert new measures at (any point (see [Measure operations: Insert](#))

Select a note/rest duration

The following keyboard shortcuts are used to select note/rest duration in [Note Input](#) mode

- **64th** (hemidemisemiquaver): 1
- **32nd** (demisemiquaver): 2
- **16th** (semiquaver): 3
- **Eighth** (quaver): 4
- **Quarter** (crotchet): 5
- **Half** (minim): 6
- **Whole** (semibreve): 7
- **Double whole** (breve): 8
- **Longa**: 9
- (**Dot**: . (changes the selection into a dotted note/rest
- (**Double dot**: Use a custom [shortcut](#) (or apply by clicking on the icon in the note input toolbar
- **Triple dot**: Use a custom shortcut

.See also: [Tuplets](#)

Input devices

:Music notation can be entered by


- [.Computer keyboard](#)
- [.Mouse](#)
- [.MIDI keyboard](#)
- [.Virtual Piano Keyboard](#)
- [.Any combination of the above](#)

Computer keyboard

This section expands on "[Basic note entry](#)" (see above) and introduces you to the full range of commands available for entering notes or rests from the computer keyboard

Enter notes/rests

You can enter a **note** by typing the corresponding letter on your keyboard. Thus, after entering [Note Input](#) mode, type: 5 C
.D E F G A B C



Note: When you enter a note using the keyboard, MuseScore places it closest to the previous note entered (above or below)

.To enter a **rest**, type "0" (zero). Thus, after entering [Note Input](#) mode, type: 5 C D 0 E



Note: The duration selected in the toolbar applies to both notes *and* rests

.If you want to enter a **dotted note**, press . (period/full stop) after selecting the duration

.For example, after entering [Note Input](#) mode, type: 5 . C 4 D E F G A



.If you want to enter a **tuplet**: see [Tuplets](#)

.If you want to write music with two or more simultaneous lines of independent melody (i.e. polyphony): see [Voices](#)

Move notes up/down

:To move a note up or down by a semitone

- Press the ↑ or ↓ arrow

:To move a note up or down diatonically

- ↓+Press Alt+Shift+↑ or Alt+Shift

:To move a note up or down by one octave

- (↓+⌘ :Press Ctrl+↑ (Mac: ⌘+↑) or Ctrl+↓ (Mac

Add accidentals

When a note is moved up or down with an arrow key (see above), any accidental required is automatically generated by the program. Accidentals can also be added manually—see [Accidentals](#)

Chords

:If you want to add a chord note *above* your previous entry

.Press and hold Shift, then enter a note from A to G •

:Thus, typing C, D, Shift + F, Shift + A, E, F results in



:To add a note at a specific interval above or below one or more notes

;Ensure that one or more notes are selected .1

:Use one of the following options .2

;From the menu, select Notes → Add Interval... and choose an interval from the list ◦

Press Alt+1-9 for intervals *above* (intervals *below* are also possible by adding relevant shortcuts to the list in ◦

.(Preferences

.Note: To create chords with notes of different durations, you will need to use more than one Voice

Keyboard shortcuts

:Here is a list of useful editing shortcuts available in Note Input mode

.(# Up): Increase the pitch of a note by a semitone (uses) ↑ •

.(b Down): Decrease the pitch of a note by a semitone (uses) ↓ •

Alt+1-9: Add interval (unison to ninth) above current note •

J: Change note up or down to enharmonic note (alters the spelling in both concert pitch and transposed modes). •

See Accidentals

Ctrl+J (Mac Cmd+J): Change note up or down to enharmonic (alters the spelling only in the current mode). See •

Accidentals

Alt+Shift+↑: Increase the pitch of a note using key signature •

Alt+Shift+↓: Decrease the pitch of a note using key signature •

R: Repeat the last entered note •

Q: Halve the duration of the last entered note •

W: Double the duration of the last entered note •

Shift+Q (as of version 2.1): Decrease duration by a dot (for example, a dotted quarter note/crotchet becomes a •

.(quarter note/crotchet and a quarter note/crotchet becomes a dotted eighth note/quaver

Shift+W (as of version 2.1): Increase duration by a dot (for example an eighth note/quaver becomes a dotted eighth •

.(note/quaver and a dotted eighth note/quaver becomes a quarter note/crotchet

Backspace: Undo last entered note •

(Shift+←: Exchange last entered note with the note before it (repeat to keep moving note earlier •

Shift+→: Exchange note moved with Shift+← with the note that follows it •

(X: Flip direction of note stem (can be reset to Auto position in Inspector •

(Shift+X: Move note head to opposite side of stem (can be reset to Auto position in Inspector •

Mouse

.It's easy to enter notes with the mouse, but it is not the fastest way to enter lots of notes

.Click on the desired note duration symbol in the Note input toolbar .1

.Click on the score to add a pitch of the selected duration .2

.To *add* more notes to an existing chord, simply repeat step 2 .3

.To *replace* an existing chord (rather than adding to it), press Shift before clicking .4

Note: If you hover the cursor over the score in Note Input Mode it will show you a preview of the note or rest you are

.about to add

MIDI keyboard

.You can also insert pitches using a MIDI keyboard

Connect your MIDI keyboard to the computer and switch the former on .1

(Start MuseScore (this must be done **after** the keyboard is switched on .2

- [Create a new score](#) .3
 - Click the rest (selecting it) in measure 1 to indicate where you want note input to begin .4
 - Press N to enter note input mode .5
 - Select a note duration such as 5 for quarter notes (crotchets), as described [above](#) .6
 - Press a note on your MIDI keyboard .7
- .The pitch should be added to your score

Note: The MIDI keyboard enters one note or chord at a time. This mode of note input (often called "step-time entry") is fast and reliable. Beginning with version 2.1 MuseScore introduced a limited [real time entry mode](#) , in which the musician plays a passage and MuseScore tries to produce the notation

If you have multiple MIDI devices connected to your computer, you may need to inform MuseScore which is the MIDI keyboard. Go to Edit → Preferences... (Mac: MuseScore → Preferences...). In the preferences dialog, click on the I/O tab and select your device under the section labeled "PortAudio"

Virtual Piano Keyboard

You can also input notes using the on-screen **piano keyboard**

- (To toggle the display on and off:** Press P (or select View → Piano
- To resize the keyboard:** Position the mouse pointer over the piano keys, hold down Ctrl (Mac: Cmd) and move the mouse scroll wheel up (larger) or down (smaller

The method of note entry is similar to that for a [midi keyboard](#)


- Ensure that you are in [Note Input mode](#) .1
- To enter a .2

Single note: Click on the appropriate piano key

Chord: Select the note you wish to add to, press and hold Shift, then click on a piano key (in versions before 2.1, use Ctrl (Mac: Cmd)). Repeat as required

Input modes

In addition to the existing [Step-time](#) and [Repitch](#) modes, three more input modes have been added in MuseScore 2.1 (see [links below](#)). All can be accessed by clicking the small arrow next to the "N" button on the left of the Note Input toolbar



- (Step-time (default):** The default mode of note entry. See [Basic note entry](#) (above
- Repitch:** Replace pitches without changing rhythms
- Rhythm:** Enter durations with a single click or keypress
- Real-time (automatic):** Perform the piece at a fixed tempo indicated by a metronome beat
- Real-time (manual):** Perform the piece while tapping a key or pedal to set the beat

Coloring of notes outside an instrument's range

Depending on the skill of the musician, certain notes are considered beyond the range of a particular instrument. For informational purposes, MuseScore *optionally* colors notes red if they are outside the range of a "professional" player, and olive green/dark yellow if outside the range of an "early amateur." The colors appear on the computer screen, but not on printed copies



To enable/disable note coloration and to set "professional" and "amateur" ranges, see [Usable pitch range](#) (Staff .(properties: all staves

Small notes/small noteheads

.Select the note(s) you want in small size .1
 Check the "Small" checkbox in the [Inspector](#). The one in the Note section is used to only change the size of the .2
 .individual notehead; the one in the Chord section will change the note head, stem, beam, and flag sizes all together

.By default, the small size is 70% of the normal size. You can change that setting in `Style → General → Sizes`

Change notes or rests already entered

Change duration

:To change the length of a single note or rest

.Make sure you are not in note input mode (press Esc to exit) and have no other notes selected .1
 Click on the note or rest and use the duration shortcuts listed [above](#), or the duration icons in the toolbar, to change it .2
 .to the duration of your choice

Increasing the duration will overwrite the notes or rests that follow it; decreasing the duration will add rests between it and .the notes or rests following

:For example, to change three sixteenth rests into a single dotted eighth rest

- .Click on the first sixteenth rest .1
- .Hit 4 to turn it into an eighth rest .2
- .Hit . to turn it into a dotted eighth rest .3

.As the duration increases, it overwrites the other two sixteenth rests following it

Change pitch

:To change the pitch of a single note

- .Make sure that you're not in note input mode and that you have no other notes selected .1
- :Select the desired note and use any of the following methods .2
 - ;Drag the notehead up or down with the mouse
 - ;(Press the the keyboard arrows: ↑ (Up) or ↓ (down)
 - Type a new note letter name (A...G). Use `Ctrl+↓` or `Ctrl+↑` to correct the octave, if necessary (Mac: `Cmd+↓` or `Cmd+↑`).

.To change the enharmonic spelling of a note, select it and use the `u` command. For more information, see [Accidentals](#)

.To change the pitches of a passage of music by a constant interval, you can use [Transposition](#)

To change the pitches of a passage of music to a different melody, while keeping the rhythm unchanged, use [Re-pitch](#)  [mode](#)

If your score contains a lot of misspelled accidentals, you might try the `Respell Pitches` command (see [Accidentals](#): [Respell pitches](#))

Change rest to note and vice versa

:To change a rest to a note of the same duration

- .(Make sure you are not in note input mode (press Esc to exit) .1
- .Select the rest .2
- .Enter the desired pitch by entering a note letter, A–G .3

.To change a note to a rest of the same duration

- .(Make sure you are not in note input mode (press Esc to exit) .1
- .Select the note .2
- .(Press 0 (Zero) .3

Note properties

- .To adjust the horizontal position of a note/chord: see [Offset notes](#) •
- To edit note properties in general (spacing, offset, size, color, notehead direction, playback etc.): see [Inspector and object properties](#) •
- To adjust the layout of all notes in the score: see [Layout and formatting](#), especially the sections about [notes](#), [accidentals](#) and [tuplets](#) •

See also

- [Note input modes](#) •
- [Drum notation](#) •
- [Tablature](#) •
- [Tuplet](#) •
- [Voices](#) •
- [Shared noteheads](#) •
- [Preferences](#) •

External links

- [How to enter a chord](#)  •
- [How to enter a rest](#)  •
- [How to span a stem over two staves](#)  •
- [Video tutorial: MuseScore in Minutes: Lesson 3 - Note input](#)  •
- [Video tutorial: MuseScore in Minutes: Lesson 4 - MIDI Keyboard Input](#)  •
- [Video tutorial: MuseScore in Minutes: Lesson 5 - More Input Ideas](#)  •
- [\(Video: Semi-Realtime MIDI Demo Part 1: New note entry modes\)](#)  (available as of MuseScore 2.1) •

Edit mode

Edit mode allows you to perform a wide range of editing operations on individual score elements, such as

- .adjust the length and shape of slurs, lines, barlines etc •
- .add, delete and format text in text objects •
- .(adjust the position of *most* score elements (but not *text*) •

Enter/exit edit mode

.To enter Edit mode use any of the following methods

- .Double-click an element •
- .Right-click on an element and, from the menu, select **Edit Element** •
- .(Click on an element and press Ctrl+E (Mac: Cmd+E) •

.To exit Edit mode use any of the following

- .Press Esc •
- .Click on a blank area of the document window •

Text

.For text edit mode, see [Text editing](#)

Lines—such as slurs, ties, hairpins, voltas etc.—display square **adjustment handles** in Edit mode: these turn blue when selected. A slur, for example, looks like this



The end handles are used to adjust the length of the line. The middle handle is used to adjust its vertical position. In the case of slurs and ties, there are also three more handles to adjust the shape of the curve (see image above)

To reposition a handle, click on it and use a keyboard shortcut (see below). Alternatively you can drag the handle with a mouse

Each **end handle** is connected by a dotted line to an anchor on the staff. The start and end anchors mark the boundaries of the region of the score under the control of the line. By default, an end handle is positioned *vertically* above its anchor

- **To move both an end handle and its attached anchor:** Click on the handle and use Shift+ → or Shift + ←
- **To move an end handle *without* affecting its anchor:** Click on the handle and use either the left/right keyboard arrows or a corresponding Ctrl (Mac: ⌘) command. See keyboard shortcuts below

Notes

Offset notes

Sometimes it is necessary to shift a note to the right or left—to avoid a collision with another element or to override automatic notehead sharing for example

1. Enter Edit mode on the desired note
2. Press the arrow key in the direction (left or right) that you wish to nudge the note (or use Ctrl+ ← or Ctrl+ → for larger adjustments)
3. Press the Esc key. This will allow the note stem to be redrawn

Alternatively, you can select the notehead and change the "Horizontal offset" (under "Chord") in the Inspector

Adjust note stem length

1. Enter Edit mode on the desired note stem
2. Use keyboard shortcuts (below) to extend or shorten the stem
3. Exit edit mode

Note: To *reposition* a note stem, you should select it and adjust the "Horizontal offset" in the Inspector

Keyboard shortcuts

In **Edit mode** the following keyboard commands can be used to change the position of either (1) a **score element** (e.g. ornament, accidental etc.) or (2) an **adjustment handle** (e.g. slur, line etc)

- Move left 0.1 staff space : ←
- Move right 0.1 staff space : →
- Move up 0.1 staff space : ↑
- Move down 0.1 staff space : ↓
- Ctrl+ ← (Mac: ⌘+ ←): Move left one staff space
- Ctrl+ → (Mac: ⌘+ →): Move right one staff space
- Ctrl+ ↑ (Mac: ⌘+ ↑): Move up one staff space
- Ctrl+ ↓ (Mac: ⌘+ ↓): Moves down one staff space
- Alt+ ← : Move left 0.01 staff space
- Alt+ → : Move right 0.01 staff space
- Alt+ ↑ : Move up 0.01 staff space
- Alt+ ↓ : Move down 0.01 staff space

The following commands only apply to **adjustment handles**

- .Shift+ ← : Move end handle's **anchor** left by one note/rest •
- .Shift+ → : Move end handle's **anchor** right by one note/rest •
- .Tab: Go to next handle •

See also

- [Text editing](#) •
- [Slur](#) •
- [Bracket](#) •
- [Line](#) •
- [Beam](#) •
- [Hairpin](#) •

Palettes and workspaces


To the left of the document window is the [Workspace](#). This can be toggled on and off using the menu command, View → Palettes, or the shortcut, F9

.A workspace, in turn, consists of a number of palettes. Each [palette](#) is a folder containing a group of musical symbols

Workspaces

MuseScore provides two preset workspaces: **Basic** (the default option) and **Advanced** (a version with more palettes and symbols). These contain symbols drawn from the various sections of the [Master palette](#). In addition, you can create your own [custom workspaces](#) (below

- To switch between workspaces:** Use the drop-down menu at the bottom of the workspace panel •



.The names of [palettes](#) within a workspace are listed under the title "Palettes

Single Palette Mode

If you only want to allow one palette to open at a time, right click at the top of the workspace and check the "Single palette" box. This will cause a palette to automatically close when you open a different one

Docking/undocking

.To dock or undock a workspace, see [Side panels](#)

.A custom workspace allows you to select which palettes are listed, and to customize the contents of those palettes

:To create a customizable workspace

- .1 .Select an existing workspace. Use the drop-down list at the bottom of the workspace panel if needed
- .2 .Click the + button, enter a name for the new workspace and pressOK. The new workspace is added to the panel

:Alternatively you can use the menu option

- .1 .Select Edit → Workspaces, and chose a workspace
- .2 .Select New. Fill in the new workspace name and clickOK

Right-clicking over the workspace will display a menu: this has options allowing you to insert, delete, rename and reorder the palettes within it. The contents of individual palettes can be edited in a similar fashion once you've checked "Enable (Editing" for a palette. For more details, see Custom palettes and Palette menu (below

Palettes

Open/close palette

- .Click once on the name of the palette or its accompanying side-arrow

Apply symbols from a palette

:A palette symbol may be applied to the score using one of the following methods

- .Select one or more score elements and double click the palette symbol
- .Drag and drop the symbol onto the desired score element in the staff

Tip: To prevent accidental rearrangement of contents during use, right-click over a palette name and untick "Enable Editing"

:For example, to add tenuto marks (—) to a selection of notes

- .1 .Select the desired notes
- .2 In the **Articulations & Ornaments** palette, double-click on the tenuto symbol

.Once added to the score, objects can be copied, pasted, and duplicated—see Copy and paste

(Preset palettes (Advanced workspace

:The more fully-featured Advanced workspace contains the following palettes

- Grace Notes
- Clefs
- Key Signatures
- Time Signatures
- Barlines
- Lines
- Arpeggios and Glissandi
- Breaths and pauses
- Brackets
- Articulations and Ornaments
- Accidentals
- Dynamics
- Fingering
- Note Heads
- Tremolo
- Repeats and Jumps
- Tempo
- Text
- Breaks and Spacers
- Bagpipe Embellishments

- [Beam Properties](#)
- [Frames and Measures](#)
- [Fretboard Diagrams](#)

Custom palettes

Once you have created a **custom workspace** (see [above](#)), and enabled editing (see [Palette menu](#) below), you can customize the palettes within it to your own requirements

:To add an existing score element (such as a line, text, dynamic, fretboard diagram etc.) to a custom palette

- .Press and hold Ctrl+Shift (Mac: Cmd+Shift), then drag the symbol onto the palette

:To add a symbol to a custom workspace from the [Master palette](#)

- .Drag the symbol from the Master Palette window into a custom palette


:To re-arrange a symbol in a custom palette

- .Drag the symbol to the cell you want it to display in: it will swap places with the symbol currently occupying that cell

Palette menu

:Right-clicking on the name of a palette in a custom workspace brings up this menu

- **:Palette Properties...:** Adjust the appearance of the open palette



Name ◦

Cell Size: Width, Height ◦

.Element Offset: Adjust the vertical offset of all elements in the palette ◦

.Scale: Make all palette elements appear larger or smaller ◦

.Show grid: Visually divide the palette into cells, one for each element ◦

.Show 'More Elements...': Create a cell which opens the Master Palette ◦

• **.Insert New Palette:** Create a new empty palette

• **.Move Palette Up / Move Palette Down:** Reorder the palettes

• **.Enable Editing:** Allow modifying the contents of the palette

• **.Save Palette:** Save as an .mpal file

• **.Load Palette:** Load an .mpal file

• **.Delete Palette:** Remove the palette from the workspace entirely

:Right-clicking on an element *within* a palette (if editing of the palette is enabled) brings up this menu

• **Clear:** Remove the element from the palette

• **:Properties...:** Open the **Palette Cell Properties** dialogue

◦ *.Name:* The tooltip that appears when you mouse over the element

◦ *.Content offset (X, Y):* Adjust the position of the element in the palette

◦ *.Content scale:* Make the element appear larger or smaller in the palette

◦ *.Draw staff:* Draw the five lines of a musical staff behind the palette element

• **.More Elements:** Open the relevant Master Palette section

Note: Changing values in "Palette Cell Properties" only affects the appearance of elements in the palette. It does not change their sizes or offsets on the score page

Behavior of applied text and lines

If the symbol you are adding to the score from a palette contains a text element (e.g. staff text, dynamic, fingering, volta etc.), then properties such as font-type, font-size, text color, and alignment will adapt according to the following rules

.Text properties which have not been altered by the user will adopt the relevant, prevailing text styles .1

Custom text-properties—i.e. those changed by the user before saving the symbol to a custom palette—remain as .2
.customized

By contrast, the line properties of lines applied from a palette *always* remain unchanged (i.e. as set by the user before .(saving to a custom workspace, or as predefined in the Basic/Advanced workspaces

See also

[Master palette](#) •

Inspector and object properties

.Most score elements have properties that can be edited in one of two ways

Click on any element, and many of its properties can be viewed and changed from the Inspector panel on the right- •
.hand side of your screen


Right-click on an element and select an option with the word Properties in it. This option opens a dialog with •
.advanced properties, only available for certain types of elements

Inspector

The **Inspector** is shown by default on the right of your screen. It can be displayed or hidden from the menu: select View •
. (and check/uncheck Inspector, or use the shortcut F8 (Mac: fn+F8

In the **Inspector**, the properties of any selected object are displayed and can be edited. This applies to virtually every single element in the score window—notes, text, barlines, articulations etc. Multiple elements can also be selected and edited simultaneously, as long as they are of the same type. However, if the selected objects are of *different* types, then .the Inspector restricts you to editing color and visibility only


The **Inspector** panel can be un-docked to become a floating panel by clicking the double-chevron symbol or double-
.clicking the top bar of the panel



.To re-attach the panel double-click on the top bar again. See also: Side panels

Inspector categories

When you select one or more elements of a specific type, the properties which can be edited are conveniently divided into categories in the Inspector. Categories can be identified by their bold, centered lettering. For example, if you select a :barline, you will see the following displayed at the top of the Inspector



For details about how to adjust the properties of various score elements, refer to the relevant sections in the handbook.

:However, a few general points will be covered here

Element

All score elements, except frames, breaks and spacers, display this category in the Inspector when selected. The various options are as follows

- Visible:** Uncheck this box to make selected elements **invisible**: alternatively, use the shortcut **v** (toggle). Invisible elements do not appear in the music when printed out or exported as a PDF or image. If you still want them to remain on display in the document window, make sure that the "Show Invisible" option is selected in **View → Show Invisible**. Invisible elements will then be colored light gray
- .Color:** Click on the rectangle to open a "Color Select" dialog. Adjust the color and opacity of selected elements
- Horizontal offset / Vertical offset:** Allows you to position selected elements exactly (in terms of space units). A positive number moves the elements right or down; a negative number moves the elements left or up. Snap to grid buttons are also provided

Element Group

This category is displayed only when you have selected a mixture of different types of elements, and allows editing of color and visibility only

Segment

This category is used to increase or decrease the space before/after an element in a music staff. Adjusting leading/trailing space here also affects any associated lyric syllables

Chord

This category is displayed only if notes are selected. Any change to a notehead property under **Chord** affects the whole chord (i.e. all the notes in one voice) at that location—and not just the selected note. If you want to make changes to the (position of just one note in a chord, then use the Element category (above

Note

This category allows you to make changes to selected notes (but for note position—see Element). It contains the following properties

- Small:** Make notehead smaller (you can specify the relative size of all small notes from the menu **Style → General... → Sizes**)
- .Head group:** See Notehead groups
- .Head type:** See Notehead types
- .Mirror head:** Position notehead to the left or right of the stem (default is "Auto")
- .Tuning:** Adjust tuning of note to the nearest cent
- .Play:** Unticking this box silences the note
- .Velocity type:** Sets the MIDI velocity of notes directly. Chose one of two options
- .Offset:** Make the value shown in "Velocity" *relative* to the previous dynamic marking ◦
- .User:** Make the value shown in "Velocity" *absolute* (i.e. the MIDI velocity is *unaffected* by dynamic markings ◦
- .Velocity:** Set the MIDI velocity according to the option displayed in "Velocity type"
- .Fix to line:** When ticked, the note is fixed to the top line of the standard 5-line staff
- .Line:** A positive number moves the "fixed" note down; a negative number moves it upwards

Select

:This category appears differently according to the selection you have made

- If you select a notehead, the "Select" category displays buttons which allow you to easily switch the selection to the (stem, beam, hook, duration dot (or dots) or tuplet number associated with the notehead (see image below



If you select a range of measures, the "Select" category allows you to select either all notes, grace notes (from version 2.1) or rests

Beam

This section is displayed in the Inspector when you select one or more note beams, and allows you to make fine adjustments to beam position and angle, and also change the spacing of beamed notes. See [Adjust beam with the inspector](#)

Clef

This section appears when you select a clef: the tick box allows you to turn on/off the display of a preceding [courtesy clef](#)



Properties dialogs

Properties of some objects are accessed by right-clicking on the object and choosing a "Properties" option from the context menu: these are in addition to the object's properties displayed in the Inspector

Note: **Properties** should not be confused with **Styles**. Changes to **properties** only affect the single element selected; all (**style** controls apply to the entire score)

Articulation properties

Right-click on an articulation and select Articulation Properties... See [Articulations and ornaments](#)

Fretboard diagram properties

Right-click on a [fretboard diagram](#) and select Fretboard Diagram Properties... Allows you to create custom fretboard diagrams. See [Edit fretboard diagram](#)

Line properties

Right-click on a [line](#) and select Line Properties... There are settings for the beginning, end, or continuation of the line. You can add or remove text, adjust the text's placement, and set the length and angle of optional hooks. Click the ... button to access [text properties](#) for text included in the line. See [Custom lines and line properties](#)

Measure properties

Right-click on an empty part of the measure and select Measure Properties... Adjust visibility, bar duration, repeats, stretch and numbering. See [Measure properties](#)

Staff properties

Right-click either an empty part of a measure or the name of an instrument and select Staff Properties... This dialog allows you to adjust attributes of both the single staff and the instrument it is a part of. See [Staff properties](#)

Text properties

Right click on a text-based element and select Text Properties... See [Text styles and properties](#). If the element is a line with text in it, see → [above](#)

Time signature properties

Right-click on a time signature and select Time Signature Properties... Used to adjust appearance of time sig. and beam

.properties of notes. See [Time signatures](#)

See also

- [Measure operations](#)
- [Note input](#)
- [Layout and formatting](#)
- [Staff properties](#)
- [Part extraction](#)

upload

גודל	קובץ מצורף
KB 67.14	Note inspector.jpg ↗
KB 91.41	Staffproperties.jpg ↗
KB 1.03	Buttonstaffproperties.jpg ↗
KB 22.51	Staffproperties2ndaccess.jpg ↗
KB 25.03	View_en.png ↗
133.85 KB	Note inspector.png ↗
KB 53.21	Measure Properties 1.png ↗
KB 2.65	notes.png ↗
KB 3.25	inspector_select.png ↗
KB 10.85	Barline inspector.png ↗
KB 60.54	Measure Properties 2.png ↗
KB 3.08	inspector-top-bar.jpg ↗
KB 7.36	Previous_Next_Buttons.png ↗
KB 30.14	Staff_Properties_en.png ↗
KB 2.09	clef_inspector.png ↗

Measure operations

.(**Note:** To ensure that [inserted](#) or [appended](#) measures display correctly, [multimeasure rests](#) should be set to off (toggle

Select

Single measure

.To [select](#) a single measure, click on a space within the measure •

Range of measures

.To select a continuous range of measures, see [Shift + click selection](#) and [Shift selection](#) •

Insert

Insert an empty measure into the score

:Use one of the following options

- [\(Select](#) a measure or a frame, then press `Ins` (no shortcut on Mac)
- Select a measure or a frame, then chose from the menu: `Add → Measures → Insert Measure`

Insert multiple measures

:Use one of the following options

- [Select](#) a measure or a frame, then press `Ctrl+Ins` (no shortcut on Mac); fill in the "Number of measures to insert" field and press OK
- Select a measure or a frame, then chose from the menu: `Add → Measures → Insert Measures...`; fill in the "Number of measures to insert" field and press OK

Append

Append an empty measure to the end of a score

:Use one of the following options

- .(Press Ctrl+B (Mac: ⌘+B)
- .Select from the menu: Add → Measures → Append One Measure

Append multiple measures to the end of a score

:Use one of the following options

- .Press Alt+Shift+B (Mac: Option+Shift+B); fill in the "Number of measures to append" field and press OK
- Select from the menu: Add → Measures → Append Measures...; fill in the "Number of measures to append" field and press .OK

Delete

Delete a single measure

- 1 .:Select the measure
- 2 .Press Ctrl+Del (Mac: Cmd+Del); or from the menu, select Edit → Measures → Delete Selected Measures


Delete a range of measures

- 1 .:Select the range of measures to delete
- 2 .Press Ctrl+Del (Mac: Cmd+Del); or from the menu, select Edit → Measures → Delete Selected Measures

Notes: (1) In multi-staff scores, measure deletion also removes all corresponding measures in the other staves of the system; (2) If you wish to delete *only* the measure contents (and not the measure itself), use the Del command instead of ".step "2

Properties

...To edit the properties of a measure, right-click an empty part of the measure and select Measure Properties



.You can use the   buttons, at the bottom left of the dialog, to navigate to the previous or next measure

Staves

- The *visible* property allows you to show/hide the notes and staff lines for the current measure
- The *stemless* property allows you to show/hide all note stems for the current measure. Notes that normally have a stem such as half notes (minims) and quarter notes (crotchets) only show the note head when marked as stemless

Measure duration

This feature allows you to adjust the time signature of a single measure regardless of the time signature indicated in the score. You can use it to create a **pickup measure** (also known as *anacrusis* or *upbeat*), **cadenza**, **ad lib** section etc



- **Nominal** is the *apparent* time signature and cannot be edited
- **Actual** can be set to anything you like regardless of the *nominal* time signature

Example: In the image below, the quarter note *pickup measure* has a *nominal* time signature of 4/4, but an *actual* time sig. of 1/4. The measures in the middle are in normal 4/4 time. The complementary measure at the end of the staff, with a dotted half note, has an *actual* time sig. of 3/4



Other

Exclude from measure count

Use "*Exclude from measure count*" for "irregular" measures, i.e. ones that should not get counted in the measure numbering. Normally, a pickup measure is marked as "*Exclude from measure count*"

Add to measure number

You can also use the "*Add to measure number*" option to influence the measure numbering. You can enter positive or negative numbers here. Please note that this affects all subsequent measures. A value of "-1" has the same effect as marking a measure to be excluded from measure count

Layout stretch

You can increase or decrease horizontal space between score elements (notes, rests, etc.) with this option. This provides a more precise control over the exact same measure spacing property as the menu commands or keyboard shortcuts for Increase/Decrease Stretch ({} and {}), which are accessed outside of the Measure Properties dialog while a measure is selected

(Play Count (as of version 2.1) / Repeat count (prior to version 2.1)

If the measure contains an end repeat barline, you can define how often it is played

Break multi-measure rests

This property will separate a multi-measure rest at the start of the selected measure. This option should be checked **before** you turn on the "*Create multi-measure rests*" option in Style → General..., in the "**Score**" tab

Multi-measure rests are automatically broken at important breaks, such as rehearsal marks, time signature changes, double barlines, irregular measures, etc. The default for scores is *off*, for parts is *on*

Numbering

MuseScore automatically numbers the first measure of each System (except for the first system, actually except for a measure with the number 1), but more numbering options are possible. From the main menu, choose Style → General..., in the left pane, choose the "**Header, Footer, Numbers**" tab. At the bottom of the right pane is the "**Measure Numbers**" ("Bar Numbers") section

.Mark the checkbox next to the "Measure Numbers" ("Bar Numbers") to turn on automatic measure numbers

.Mark "Show first" if you want the first measure numbered

Mark "All staves" if you want numbers on all staves. Otherwise, only the top staff of each system shows measure numbers

Choose to show numbers on "Every system" which numbers the first measure of each line, or show numbers by "Interval" and specify the size of the interval. For example, an interval of 1 numbers every measure; an interval of 5 numbers every fifth measure

Split and join

You may want have to have a longer or shorter measure without changing the time signature. You can change a measure's duration in Measure Properties, but there is now a new option to split or join measures. (Beams may be automatically modified

Join measures

.:Select the measures you want to join .1

.From the menu bar, select Edit → Measure → Join Selected Measures .2

Note: If you select measures on only one staff in a score with multiple staves, the same measures will be joined in each staff of the system

:For example, the image below shows the result of applying the **Join** command to four measures in the top staff



Split a measure

.:(Select a note (or chord) .1

.From the menu bar, select Edit → Measure → Split Measure Before Selected Note .2

.*Note:* If you select only one note from one staff, each staff of the system will be split at the same place

External links

- [How to delete measures](#) 
- [How to span a measure over multiple systems](#) 
- [How to get scores without time signature \(and clef\)](#) 

Voices

A **voice** is a musical line or part which can have its own rhythm independently of other voices on the same staff. Voices are sometimes called "layers" in other notation software

You can have up to 4 **voices** on *each* staff line. In a polyphonic measure, **voice 1** usually takes the *up-stem notes* and **voice 2** takes the *down-stem notes*



N.B. Be careful not to confuse the concept of MuseScore voices (1, 2, 3, 4) with the order of voices found in vocal scores (SATB etc.). In particular, when creating a *closed* SATB score, use only (MuseScore) voices 1 and 2 for both upper and

.lower staves. There is no need to use (MuseScore) voices 3 and 4 unless there are more than two parts in the *same* staff

When to use voices

- .If you need stems pointing in opposite directions within a chord, on a single staff
- .If you need notes of different durations within a single staff, played simultaneously

How to enter notes in different voices

:The following instructions show you how to notate a passage of music in two voices

Enter voice 1 notes first: Make sure you are in *note input mode*: the Voice 1 button becomes highlighted in blue in the toolbar. Enter the notes in the top voice first. When inputting, some notes may have down-stems, but these will flip automatically when the second voice is added

:The following excerpt shows a treble staff with just the voice 1 notes entered



(Select one or more noteheads (in any voice) .2
 (Click on the destination voice in the Note Input toolbar or use the shortcut Ctrl+Alt+1-4 (Mac: Cmd+Option+1-4) .3

Note: For a successful move, the following conditions need to be met

- .The chord in the destination voice must be the same duration as the note to be moved there •
- Alternatively, if the destination voice is occupied by a rest, it must be of sufficient duration to accommodate the moved note •
- .Notes should *not* be typed •

See also

- Keyboard shortcuts: Voices •
- Noteheads: Shared noteheads •

External links

- How to merge/combine/implode two staves in one with two voices ↗ •
- Video tutorial: How To Write Two Parts On One Staff: Voices ↗ •

Copy and paste

MuseScore supports standard **copy**, **cut**, **paste** and (from version 2.1) **swap with clipboard** operations. These commands can be applied to a range of

- Musical notes:** e.g. to repeat a section of music, or shift a passage by a beat or a measure •
- Other score elements:** such as articulations, staff text, dynamics, fingering etc •

(**Note:** Lines cannot be copied but they *can* be duplicated (see below

:Copy/cut/paste/swap commands are accessed in three ways

- (From the **Edit menu** (above the document window) •
- .From the menu displayed by **right-clicking** on an element or range of elements •
- .Using one of the standard **keyboard shortcuts** •

Summary of commands

Main menu	Right-click menu	(Kbd Shortcut (Mac	(Kbd Shortcut (Win	Command
Edit → Cut	Cut	Cmd+X	Ctrl+X	Cut
Edit → Copy	Copy	Cmd+C	Ctrl+C	Copy
Edit → Paste	Paste	Cmd+V	Ctrl+V	Paste
Edit → Swap with clipboard	Swap with Clipboard	Cmd+Shift+X	Ctrl+Shift+X	Swap with clipboard

Note: Before carrying out a copy, cut, paste or swap procedure, you should be in normal mode. Press the Esc key to exit into normal mode

Notes

:You can cut, copy, paste or swap notes as follows

Copy or cut

To copy/cut a *single* chord

- .Hold down Shift and click on a note in the chord .1
- .(Apply a **Copy** or **Cut** option (see table above) .2

To copy/cut a *range* of chords

- .Click on the first note or measure that you want to select .1
- .Shift+Click on the last note or measure that you want to select. A blue rectangle highlights the region you selected .2

.(Apply a **Copy** or **Cut** option (see [table](#) above .3

Paste

.Click on the note or measure where you want your pasted selection to begin .1

.(Apply a **Paste** option (see [table](#) above .2

Swap with Clipboard

Available from version 2.1 onwards, the **swap with clipboard** operation combines two commands into one: (1) First it overwrites a selected part of the score with the contents of the clipboard, just like the *paste* command; (2) Secondly, it transfers the overwritten part of the score *back to* the clipboard, just like the *copy* command

:It can be used, for example, to swap two equal-length sections of a score, **A** and **B**

;Select section **A**, then apply the **cut** command .1

;(Clear the selection (by pressing **Esc** or clicking on a blank area of the document window .2

Press **Shift** and click on a note at the start of section **B**. Or, if **B** begins at the start of a measure, you can also simply .3

;select the measure

.(Apply a **Swap with clipboard** option (see [table](#) above .4

".Section **B** is now in the clipboard. **Paste** it back to the blank area of score left by step "1" .5

Copy pitch of a single note only

It is possible to copy the *pitch* of a note *only* (and no other properties), by clicking on the notehead and applying the standard copy and paste, or copy and swap procedure. The pitch of the destination note changes to match that of the copied note but the duration remains the same

Other elements

Score elements such as staff text, dynamics, fingering, etc. can be cut, copied and pasted *one at a time* (but from version 2.2 [multiple-selection](#) cut/copy/paste is possible for fretboard diagrams

.Multiple-selection cut/copy/paste is available for [articulations](#) such as sforzato, staccato etc

Note: The Swap with clipboard command is only intended for use with sections of music and not other score elements

Copy or cut

.(Select the element (or elements .1

.(Apply a **Copy** or **Cut** option (see [table](#) above .2

Paste

.Click on the note where you want your pasted selection to begin .1

.(Apply one of the **Paste** options (see [table](#) above .2

In the case of articulations, they are pasted to the destination notes in exactly the same order (continuous or intermittent) as they were in the initial selection

Quick repeat

:To quickly copy and paste a note, measure, or passage

.Select a chord, measure, or passage as described [above](#) .1

. Press **R** .2

MuseScore copies and pastes the selected notation to a point immediately after the last note in the selection. Any existing music in the destination range is replaced

Duplicate

:To instantaneously copy and paste a text element, line, or other object

- .Hold down Ctrl+Shift (Mac: Cmd+Shift), click on the element and drag it anywhere in the score .1
- .Release the mouse button, and the selected element is cloned to the new location .2


Selection filter

.The **Selection Filter** allows you to chose *exactly* which voices and elements you want to include in your selection

- .To display the Selection filter, press F6 (Mac: fn+F6); or from the menu, chose View → Selection Filter •

The Selection Filter appears by default below the Palettes. To change the viewing location, see Viewing and Navigation: Side panels

Example: Suppose you want to copy measures 1 and 2 in the following passage (see image), to give measures 3 and 4



- ;(Make sure the Selection Filter is displayed (see above .1
- ;Uncheck the "Articulations & Ornaments" and "Slurs" tickboxes .2
- .(Copy and paste the desired measures (in this example, 1-2 into 3-4 .3

Note: The Selection Filter works with the swap with clipboard command as well

See also

If you want to change notes without altering the rhythm, you may combine transposition or re-pitch mode ↗ with copy and .paste

External links

- Video tutorial: Lyrics, copying & dynamics ↗ •

Selection modes

Objects in the score—such as notes, measures, articulations etc.—can be selected in several ways: (1)one at a time, (2) .as a continuous range, or (3) as a list

Select a single object

.Most score objects can be selected by simply clicking on them in "normal" (i.e. not note-input) mode

Select a single note

- ;.Make sure you are not in note input mode .1
- .Click on a note .2

Note: Selecting a single note then copying and pasting it, will only copy and paste the pitch—not duration or other properties (such as stemless). To copy the entire note, including all properties, you need to hold down Shift—as for chord .(selection (below

Select a chord

- .1 ;Make sure you are not in note input mode
- .2 .Press and hold Shift, then click on a note in the chord

Select a single measure

- .Click on a blank space within the measure

.(**Note:** To select a range of consecutive measures, see [Shift selection](#) and [Shift + click selection](#) (below)

Select a continuous range of objects

:There are several ways to select a *continuous* range of notes, chords or measures

Shift selection .1

- .1 ;Make sure you are not in note entry mode
- .2 Select the first note, chord, rest or measure in the range. You can extend the selection up or down to adjacent staves, if needed, using Shift+↑ or ↓
- .3 .Then choose one of the following options
 - o .→+To advance the selection one chord at a time to the right: Press Shift
 - o .←+To advance the selection one chord at a time to the left: Press Shift
 - o .(→+To advance the selection one measure at a time to the right: Press Shift+Ctrl+→ (Mac: Shift+Cmd
 - o .(←+To advance the selection one measure at a time to the left: Press Shift+Ctrl+← (Mac: Shift+Cmd
 - o .(→+To advance the selection to the beginning of the line: Press Shift+Home (Mac: Shift+Fn
 - o .(←+To advance the selection to the end of the line: Press Shift+End (Mac: Shift+Fn
 - o .(→+To extend the selection to the beginning of the score: Press Shift+Ctrl+Home (Mac: Shift+Cmd+Fn
 - o .(←+To extend the selection to the end of the score: Press Shift+Ctrl+End (Mac: Shift+Cmd+Fn

Shift + click selection .2

:To select a range of **notes or rests**

- .1 ;Make sure you are not in note entry mode
- .2 ;Click on the first note or rest in the range
- .3 .Press and hold Shift, then click on the last desired note or rest

Note: The final selected element can be in the same staff or in staves above or below the initial note/rest. All selected elements will be enclosed in a blue rectangle, including associated lines and articulations (but not voltas). You can repeat the operation to extend the selected range as required

Select a range of measures

- .1 ;Click on a blank space in the first desired measure
- .2 .Hold down Shift, then click on a space in the last measure of the desired range

.**Note:** As with selecting notes, the range can be extended vertically as well as horizontally

Drag selection .3

This method can be used to select notes or rests, or, independently, to select non-note symbols such as staccato dots, lyrics etc

- .Press and hold Shift, then drag the cursor across the desired range

Select All .4

This method selects the *whole* musical score including notes, rests and associated elements. Use one of the following options

- .(Press Ctrl+A (Mac: Cmd+A
- .From the menu bar, select Edit → Select All

Select section .5

:This method is used to select a **section**—a region of the score starting and/or ending with a section break

;Click on an empty space in a measure in the section .1

.From the menu bar, select Edit → Select Section .2

.Note: See Copy and paste: Selection filter to disable certain types of elements from being selected in a range selection

Select a list of objects

:To select a *list* (or discontinuous range) of score elements

;Click on the first element .1

.Hold down Ctrl (Mac: Cmd) and successively click on the desired additional elements .2

.Note: This method cannot be used to select measures. Use single or range selection instead

Select all similar

:(To select all elements of a specific type (e.g., all barlines, all text elements, all staccato markings

;Select an element .1

;...Right click and chose Select .2


:Several options are available .3

.All Similar Elements: Selects all elements in the score similar to the chosen object ◦

.All Similar Elements in Same Staff: Selects all elements in the same staff similar to the chosen object ◦

All Similar Elements in Range Selection only applies if a range has been selected. Selects all elements in ◦
.the range similar to the chosen object

More...: opens a dialog that lets you fine-tune more options. For example, if you have a notehead selected, the ◦
:(dialog will look something like this (as of version 2.1—previous versions had fewer options



Select

;Same notehead: In this example, only noteheads of the same group will be selected ◦

;Same pitch: Only noteheads of the same pitch will be selected ◦

;Same type: All noteheads (of any group) will be selected ◦

;Same duration: Only noteheads of same duration will be selected ◦

;Same note name: Noteheads of that name in all octaves will be selected ◦

.Same staff: Only noteheads on the same staff will be selected ◦

Action

;Replace selection: The default option: starts the selection from scratch ◦

;Add to selection: Keeps everything you have already selected, and adds the current selection to it ◦

;Search in selection ◦

.Subtract from selection: Keep everything you have already selected, but takes away the current selection ◦

What selections are useful for

- [Copy and paste](#)
- [Edit mode](#)
- [Inspector and object properties](#)
- [Tools](#)

See also

- [Basics](#) chapter, esp. [Note input](#)
- [Notation](#) chapter, esp. [Accidental](#)
- [Text](#) chapter, esp. [Text editing](#) and [Grid-based movement of symbols and staff text](#)

Viewing and navigation

This chapter describes the options available in the **View** Menu, and in the **Zoom** and **Page View/Continuous View** .menus (located in the toolbar above the score). It also details the various navigation commands and functions

View menu

Show sidebars/panels

- [Start center](#): F4
- [Palettes](#): F9
- [Master palette](#): Shift+F9
- [Inspector](#): F8
- [Play Panel](#): F11
- [Navigator](#): F12
- [Mixer](#): F10
- [Synthesizer](#)
- [Selection filter](#): F6
- [Piano keyboard](#): P

Zoom in/out

:There are several ways to zoom the score in or out

:Keyboard shortcut •

- (++) Zoom In: Ctrl++ (Mac: Cmd ◦
- .(-+ Zoom Out: Ctrl +- (Mac: Cmd ◦


:View menu •

- Zoom In: View → Zoom In
- .Zoom Out: View → Zoom Out

Mouse •

- (Zoom In: Scroll *up* with the mouse wheel while holding down Ctrl (Mac: Cmd
- .(Zoom Out: Scroll *down* with the mouse wheel while holding down Ctrl (Mac: Cmd

- **Drop-down menu**: To set a specific zoom, use the dropdown menu in the standard toolbar to set the view . "magnification of the score (25–1600 %) or display it using the options "Page Width", "Whole Page", or "Two Pages



(To return to 100% zoom: Use the shortcut Ctrl+0 (Mac: Cmd+0) •

Toolbars (display)

As of MuseScore 2.1, this menu option allows you to hide or display the toolbars above the document window: File > Show/Hide Toolbars (Operations, Playback Controls, Concert Pitch, Image Capture, Note Input (see [Toolbars](#) below)


Show Status bar

The **Status bar**, at the bottom of the screen, gives information about selected score elements. Tick/untick this option to display or hide the status bar.


Split display

It is possible to split the document display so as to view two documents at once, or to view two different parts of the same document. Tabs allow you to choose which document to display in each view. You can drag the barrier separating the two views to adjust the amount of space in the window devoted to each document.

- **Documents Side by Side:** Divides the window vertically into two score views
- **Documents Stacked:** Divides the window horizontally into two score views, one above the other



Side by Side



Stacked

Visibility options

This section allows you to display or hide various non-printing elements:


- **Show Invisible:** View/hide elements that have been made invisible for printing and export. If this option is ticked, invisible elements are shown in the score window as light gray
- **Show Unprintable:** View/hide breaks and spacer symbols
- **Show Frames:** View/hide the dotted outlines of frames
- **Show Page Margins:** View/hide Page Margins

Full screen

Full Screen mode expands MuseScore to fill your screen so more content is visible.

Page/Continuous View

You can switch between two different views of the score using the drop-down list in the toolbar area.



:To scroll the score

- **.Vertically:** Move the mouse wheel up or down
- **.Horizontally:** Press Shift and move the mouse wheel up or down

Page View

In **Page View**, the score is formatted as it will appear when printed or exported as a PDF or image file: that is, page by page, with margins. MuseScore applies system (line) and page breaks automatically, according to the settings made in .Page settings and Style: General. In addition, you can apply your own system (line), page or section breaks

.(To choose between **horizontal** or **vertical** page scrolling, see Preferences: Canvas (Scroll pages)

Continuous View

In **Continuous View**, the score is shown as one unbroken system. Even if the starting point is not in view, measure numbers, instrument names, clefs, time and key signatures will always be displayed on the left of the window



.Note: Because the layout is simpler, MuseScore may perform faster in Continuous View than Page View

Toolbars



The **Toolbar** area is located between the **Menu bar** and **document window**. It contains symbols which allow you to perform certain operations. It can be divided into the following toolbars

- **.File Operations:** New score, Load score, Save, Print, Undo, Redo
- **.Zoom/Page View**
- **.Playback controls:** Enable MIDI, Rewind, Play/Stop, Loop, Play Repeats, Metronome
- **.Concert Pitch:** Displays score in written or concert (sounding) pitch
- **.Image Capture:** Allows you to take a snapshot of part of the score
- **.(Note Input:** Note entry mode, Duration, Tie, Rest, Accidentals, Flip stem direction, Voice (1, 2, 3, 4)

To choose which toolbars to display, right-click on an empty space in the toolbar area (or on the title bar of the Inspector) and, from the menu, check or uncheck the required options. This menu also allows you to view or hide the **Piano keyboard**, **Selection sidebar**, **Palettes**, the **Inspector**, and (if already displayed) the **'Drum Tools'** (i.e. Drum input palette)

.These display options can also be accessed in the View menu, and, as of 2.1, in View → Toolbars

Side panels

The **workspaces**, **Inspector** and **Selection filter** are conveniently displayed as **side panels** to the left and right of the score window. To undock a side panel use one of the following methods

- ;Drag the panel
- ;Click on the double chevron at the top of the panel
- .Double click in the title area at the top of the panel

:To dock a panel use one of the following procedures

- .Drag the panel to the top/bottom of an existing side panel and it will stack vertically above/below that panel
- Drag the panel to the middle of an existing side panel and it will overlay that panel. Both panels can then be accessed by tabs


.Alternatively, double-clicking the title bar of the panel will restore it to its previously docked position

Navigation

There are various commands available to help you navigate through the score. These are listed under [Keyboard shortcuts: Navigation](#)

Navigator

The **Navigator** is an optional panel which allows you to navigate a long score more easily, or go to specific pages. To view/hide, go to the [View → Navigator](#), or use the shortcut F12 (Mac: fn+F12). It appears at the bottom of the document window if scrolling pages horizontally, or on the right-hand side of the document window if scrolling pages vertically (see [Preferences: Canvas](#))



The blue box represents the area of the score that is currently visible in the main window. You can drag either the blue box or the scroll bar, or click on an area to immediately go to it

Find

:The **Find** function allows you to speedily navigate to a specific measure, [rehearsal mark](#) or page number in the score

.Press Ctrl+F (Mac: Cmd+F), or select Edit → Find. This opens the **Find (or Go to) bar** at the bottom of the workspace .1

:Use one of the following options .2

- **To go to a numbered measure:** enter the measure number (counting every measure, starting with 1, (irrespective of [pickup measures](#), [section breaks](#) or manual changes to measure number offsets
- **(To go to a numbered page:** enter the page number using the format pXX (where XX is the page number
- **To go to a numerical rehearsal mark:** enter the number using the format rXX (where XX is the name of the rehearsal mark (as of version 2.1
- **To go to a rehearsal mark starting with a letter:** enter the name of the [rehearsal mark](#) (the search is case insensitive

N.B.: It is best to avoid naming rehearsal marks with the single letters "R," "r," "P", "p," or one of these letters with an integer (e.g. "R1" or "p3"), as this can confuse the search algorithm


See also

- Save/Export/Print
- File format
- Layout and formatting

Open/Save/Export/Print

:In the **File** menu you can find the following options

- .Open, Open recent
- ...Save, Save As..., Save a Copy..., Save Selection..., Save Online
- ...Export..., Export Parts
- ...Print



Open

Apart from native format files (*.mscz and *.mscx), MuseScore can also open MusicXML, compressed MusicXML and .MIDI files, as well as a variety of files in other formats

:To open any supported file

:Chose one of the following options .1

- .Press Ctrl+O
- .Click on the "Load score" icon on the left side of the toolbar area
-From the menu bar, select File → Open
- .Select a file and click Open; or simply double-click a file .2

.**Open recent...** allows you to chose from a list of recently-opened scores

Save

.(**Save...**, **Save As...**, **Save a Copy...** and **Save Selection...** allow you to save native MuseScore files (.mscz and .mscx

.**Save...**: Save current score to file •


.**Save As...**: Save current score to new file •

.**Save a Copy...**: Save current score to new file, but continue to edit original file •

Save Selection...: Save selected measures to new file. In MuseScore versions earlier than 2.1, to ensure that the file is saved correctly, the time signature needs to be displayed in the *first* measure of the selected passage, unless it is 4/4

Save Online...: To save and share your scores on the web at [MuseScore.com](https://musescore.com) . For details, see [Share scores online](#) •

Export... and **Export Parts...** allow you to create non-MuseScore files, such as PDF, MusicXML, MIDI, and various audio and image formats. In the **Export** dialog, you can choose which format to export to



.Export...: Export current score to format of your choice •

.Export Parts...: Export current score and all linked parts to separate files in a format of your choice •

MuseScore remembers which format you picked the last time and makes that the default for the next time **Note:** There is a known issue with Windows XP and Vista, where you have to manually (un)set the filename's extension when choosing a different format than the one selected the previous time

Print

Print... allows to print your MuseScore file directly to a printer from MuseScore. Depending on your printer you will have different options, but generally you can define the page range, number of copies and collation

If you have a PDF printer installed, you could also "export" to PDF using **Print**, but it's usually better to use the native PDF option under Export for more accurate rendition. **Note:** For this to work properly with Adobe PDF, make sure to uncheck "Rely on system fonts only, do not use document fonts" in Printer properties

See also

- [File format](#) •
- [Part extraction](#) •

Undo and redo

.MuseScore remembers an unlimited number of undo/redo actions

:The standard shortcuts are

(Undo Ctrl+Z (Mac: ⌘+Z) •

(Redo Ctrl+Shift+Z or Ctrl+Y (Mac: ⌘+Shift+Z) •



:Or use the toolbar buttons

Share scores online

.Go to musescore.com/sheetmusic  to view other scores from MuseScore

You can save and share your scores online at [MuseScore.com](https://musescore.com) . You can choose to save a score privately for personal access from any computer, or share it publicly. MuseScore.com enables the viewing and playback of scores in your web browser - an additional feature entitled *VideoScores* allows synchronization between the score and a YouTube video. For use outside of a web browser, you can download the score in a variety of formats (including PDF, MIDI, MP3, MusicXML, (and the original MuseScore file


Create an account

- Visit [MuseScore.com](https://www.musescore.com) and click on "Create new account". Pick a username and enter a valid email and press "Create New Account".
- Wait a few minutes for an email from MuseScore.com support. If no email arrives, check your spam folder.
- Click the link in the email and visit your [user profile](#) to change your password.

Share a score directly from MuseScore

To save a score online

- Make sure that the Concert Pitch button is **off**, and that the individual parts are correctly transposed.
- From the menu, select File → Save Online.... The "Log in to MuseScore" dialog will appear.



- Enter your email address or MuseScore username, and password, then click OK. **Note:** If you don't have a MuseScore account yet, create one first by clicking on the "Create an account" link. That will open your browser app and bring you to [musescore.com/user/register](https://www.musescore.com/user/register).
- Upon successfully logging in, you'll be able to enter your score information.

Score Information

You're logged in as [redacted] [Sign out](#)

Title

Description

Make this score private
 Respect the [community guidelines](#). Only make your scores accessible to anyone with permission from the right holders.

License **All Rights reserved** [What does this mean?](#)

Tags
 Use a comma to separate the tags

[Save](#) [Cancel](#)

Score Information

You're logged in as [redacted] [Sign out](#)

Title

Description

Make this score private
 Respect the [community guidelines](#). Only make your scores accessible to anyone with permission from the right holders.

License **All Rights reserved** [What does this mean?](#)

Tags
 Use a comma to separate the tags


[Save](#) [Cancel](#)

- .Title:** The title of the score ○
- .Description:** The descriptive text that will appear next to it ○
- Make the score private:** If ticked, the score can only be viewed via a private link. If unticked, the score is ○
 .visible to all

License: Chose an appropriate copyright license from the drop-down list. **Note:** [Creative Commons license](#) , allows people to use your scores under certain restrictions

Tags: You can add **tags** to help identify scores on MuseScore.com. Use commas to separate multiple tags

In case you already saved the score online earlier, it will automatically update the existing one, and, as of version 2.1, you can enter some additional information in a changlog section of the dialog, which you can then retrieve on MuseScore.com under "Revision history" for that score. Uncheck **Update the existing score** to save online as a new score



As of version 2.1) If you are using a different [SoundFont](#) than the default one and if you are able to export [MP3 files](#), a checkbox **Upload score audio** will be visible



If the checkbox is checked, MuseScore will render the audio of the score using the current [synthesizer](#) settings and upload the audio to MuseScore.com

Upload a score on MuseScore.com

You can also upload a score directly on MuseScore.com

Click the [Upload link](#)  on MuseScore.com

You have the same options as with the Save Online menu

You have also access to more information, such as **Genre**

Note: Should you reach the **five score upload limit**, you can still upload [scores directly from MuseScore](#), but only the last five are visible. If you wish more than this amount, upgrade to a [Pro Account](#)  first

Edit a score on MuseScore.com

If you want to make changes to one of your scores on MuseScore.com, edit the MuseScore file on your own computer, save it, and then do the following

If you originally shared the score [directly from within MuseScore](#), simply go to File → Save Online... again to update the online score

If you originally [uploaded the score](#) via the [Upload page](#)  on MuseScore.com, then you must follow these steps to update the online score

Go to the score page on MuseScore.com

Click the three dots menu : on the right and choose "Update this score"

In the form, you can upload a replacement score file as well as change the accompanying information and privacy settings

Switch to the direct method of updating an online score

It is much more convenient to update online scores from directly within MuseScore than by updating the score manually from the score page. Follow these steps if you originally uploaded the score via the [Upload page](#)  and now want to switch to the direct method

Go to the score page on MuseScore.com and copy the URL

Open the score file on your computer with MuseScore

From the menu, select File → Score Properties... and paste the URL into the "Source" field

Now whenever you want to update the online score simply go to File → Save Online

External links

[How to delete a score saved on MuseScore.com](#) 

Concert pitch

You can choose to display the score in either **written** or **concert** (sounding) pitch. Written pitch displays the score as it *should* look when printed for musicians to read. However, during preparation you may prefer the convenience of seeing the transposing instruments notated as *they sound*, without transposition. In this case you should select the "Concert .pitch" option

:To toggle the score display between **written** or **concert** pitch use one of the following options

- Press the Concert Pitch button (located in the top right of the toolbar area). When this button is highlighted the score is .in concert pitch
- From the menu bar, select Notes and tick/untick the Concert Pitch option

Before printing the score, exporting it to PDF or saving it online, you should ensure that the Concert Pitch button is **off**, and .that the individual parts are correctly transposed

See also

- [Transposition: Transposing instruments](#)
- [Accidental: Respell pitches](#)

External links

- [\(Concert pitch ↗ \(Wikipedia article](#)
- [\(Transposing Instrument ↗ \(Wikipedia article](#)
- [\(Concert pitch or not?? ↗ \(MuseScore forum discussion](#)


Notation

In the previous "Basics" chapter you learn how to enter notes and interact with the palettes. The "Notation" chapter .describes the different types of notation in more detail, including more advanced music notation

."See also "Advanced topics

Barlines

:Barline symbols are available in the **Barlines** palette



Change barline type

:To change an existing barline, use one of the following

- .Select a barline, then double click on a symbol in the Barlines palette
- .Drag a symbol from the Barlines palette onto a barline in the score
- .Drag a symbol from the Barlines palette onto a measure
- .Select a measure, then double-click on a symbol in the Barlines palette
- .Select a barline then adjust "Style" in the "Barline" section of the Inspector

:To change a non-single to a single barline

- .Select the barline and press Del

:To hide a barline

- .Select the line and press v, or uncheck Visible in the Inspector

Insert barline

:To insert a new barline between existing ones, either

- .Drag a symbol from the Barlines palette onto a note or rest
- .Select a note or rest, then double-click a symbol in the Barlines palette

Custom barlines

It is possible to create custom barlines by selecting one or more barlines, and adjusting the properties in the "Barlines" section of the **Inspector**

- .**Style:** Chose from a range of preset barlines
- .**Spanned staves:** The maximum equals the number of staves in the system
- .**Span from:** Sets the position of the *top* of the barline. "0" is the top staff line. Positive numbers start lower down the staff, negative numbers above
- .(" **Span to:** Sets the position of the *bottom* of the barline (see "Span from
- .**Span preset:** Set a span preset option


.See also, [Mensurstrich](#)

.Changes to color and horizontal/vertical offset can also be made in the Inspector

Connect barlines

Barlines may extend over multiple staves, as in the grand staff of a piano, or in an orchestral score to join instruments in the same section. To join barlines

.Double-click on a barline to enter Edit mode .1



Click on the lower blue handle and drag it down to the staff you wish to connect to. The handle snaps into position so there is no need to position it exactly .2

.Press Esc to exit edit mode. This will update all other relevant barlines as well .3



See also

- [Measure operations](#)
- [Add fermata to barline](#)

Clefs

Commonly used **Clefs** (Treble, Bass, Alto, Tenor) can be found in the Clefspalett in the Basicworkspace. For a more (complete range, see the **Clefs** palette in the Advanced workspace (see image below



.Note: You can tailor the display of clefs to your specific requirements using [a custom palette](#)

Add a clef

Add clef to beginning of measure

Method 1—add clef to beginning of a measure, whether or not it is the first measure in a system

- Select a measure and double-click a clef symbol in the palette, OR
- .Drag a clef from the palette onto a measure

Method 2—only for changing the clef at the start of a system

- Select the existing clef at the beginning of the system and double-click a new clef from the palette, OR
- .Drag a new clef from the palette directly onto the existing clef

Add mid-measure clef

.To create a mid-measure clef

- .Click on a note, then double-click a clef in the palette

Note: If the clef is not the first in the system, it will be drawn smaller

In this image, the top staff starts with a treble clef and switches immediately to bass clef, then after a note and a rest, changes back to treble clef



Note: Changing a clef does not change the pitch of any note. Instead, the notes move to preserve pitch. If you want, you can use [Transposition](#) in conjunction with a clef change

Courtesy clefs

When a clef change occurs at the beginning of a system, a **courtesy clef** will be generated at the end of the previous system

.To show or hide *all* courtesy clefs

- ;From the menu, select Style → General... → Page .1
- ".Check/uncheck "Create courtesy clefs" .2

.It is also possible to show/hide courtesy clefs on a case-by-case basis

- ;("Create courtesy clefs" should already be ticked in the "General" menu (see above) .1
- .Select a clef and tick/untick "Show courtesy" in the [Inspector](#) .2

Remove a clef

- .Select a clef and press Del

Hide clefs

(Display clef only in the first measure (for all staves

- ;From the menu, select Style → General... → Page .1
- ".Uncheck "Create clef for all systems" .2

(Display clef only in the first measure (for a particular staff

- 1. Right click on the staff, select Staff properties... and uncheck "Show clef"
- 2. Open the master palette and select the "Symbols" section
- 3. Drag and drop a clef from the master palette onto the first measure of the staff; OR select the first note and double-click a clef in the master palette

Note: This option may be useful to TAB users who do not want the clef to repeat on every subsequent line

Hide all clefs in a particular staff

- 1. Right click on the staff, and select Staff properties
- 2. Uncheck "Show clef"

Key signatures

Standard **key signatures** are available in the Key Signatures palette in the Basic or Advanced workspaces. It is also possible to create custom key signatures (below



Add a new key signature

Add new key signature to *all* staves

Use any of the following methods

- Drag a key signature from the palette onto an empty part of a measure
- Select a measure and double-click a key signature in the palette
- Select a note and double-click a key signature in a palette

Add new key signature to *one* staff only

If you wish to change the key signature of only *one* staff line, leaving others unchanged

- Press Ctrl (Mac: ⌘) and hold while you drag a key signature from a palette onto a measure

Replace an existing key signature

Replace key signature for *all* staves

Use any of the following methods

- Drag a key signature from the palette onto the key signature to be replaced (or onto the measure containing the key signature)
- Select the key signature to be replaced, and double-click a new key signature in a palette

Replace key signature for *one* staff only

If you wish to replace the key signature of only one staff, leaving others unchanged

- Press Ctrl (Mac: ⌘) and hold while you drag a key signature from a palette onto the key signature to be replaced (or onto the measure containing the key signature)


Remove a key signature

:Use any of the following methods

- .Click on an existing key signature and press Del
- .Drag the empty key signature from the palette (in the advanced workspace) onto the measure


Naturals on key signature changes

By default, MuseScore only shows cancelling naturals when the key signature changes to that of C Major/A minor (no sharps or flats). In all other cases, it simply shows the new key signature without cancellations



:However, you can opt to display cancelling naturals for *all* key signature changes

:From the menu, select **Style** → **General...** → **Accidentals**. You'll see the options .1



.Select one of the three options .2

.If you are in a part and want the new option to apply to *all* parts, click on **Apply to all parts** .3

.Click OK to exit .4

:For example, selecting the option **"Before key signature if changing to fewer # or b"** gives



:And the option **"After key signature if changing to fewer # or b. Before if changing between # and b"** gives



Key signature changes and multi-measure rests

:Multi-measure rests are interrupted if there is change of key signature



Courtesy key signatures

:To turn off the display of a *particular* courtesy key signature

.Select the relevant key signature and untick "Show courtesy" in the "Key Signature" section of the Inspector •

:To turn off the display of *all* courtesy key signatures


".From the menu, select **Style** → **General...** → **Page**, and untick "Create courtesy key signatures" •

.Note: Courtesy key signatures are not displayed at section breaks

Custom key signatures

:To create a custom key signature

.Press Shift+K to display the **Key signatures** section of the Master palette .1



In the **Create Key signature** panel, drag accidentals from the palette onto the "staff" above to create the desired key .2
".signature. Use the Clear button, if required, to remove all accidentals from the "staff

.(Press Add to move the new key signature into the library (center panel) .3

.Note: Playback of custom key signatures is not currently supported

:To move a key signature from the Master palette to a custom palette ↗


.Drag and drop the key signature onto a palette •

:To apply a key signatures to the score *directly from the Master palette*, use one of the following methods

- .Select a measure and double-click a key signature in the Master palette
- .Drag a key signature from the Master palette onto a measure

Time signatures

.**Time signatures** can be found in a Palette of the same name in both the Basic and Advanced workspaces



Add a time signature to a score

:To **add** a time signature, use any of the following methods

- .Drag and drop a time signature from a palette onto a space in a measure •
- .Select a measure and then double-click a time signature in a palette •
- .Select any note or rest and double-click a time signature in a palette •

.The time signature will appear at the beginning of the measure in question

:To **replace** a time signature, use any of the following methods

- .Drag and drop a time signature onto an existing time signature •
- .Select a time signature in the score, then double-click a time signature in a Palette •

Delete a time signature

.To delete a time signature in the score, select it and press Del

Create a time signature

:If the time signature you require is not available in any of the existing palettes, it can be created as follows

- .Press Shift+T to display the **Time signatures** section of the Master Palette .1
- .Select a time signature to edit in the center panel .2
- In the **Create Time Signature** panel, edit the various parameters (numerator, denominator, text, beaming) to get the .3
time signature and properties you want. To restore the default beaming pattern, press Reset
- Press Add to add the newly-created time signature to the center .4
panel, right-click on it and select Clear
- .Drag and drop the time signature from the Master Palette to the desired score location .5


:To move a time signature from the Master Palette to a custom palette

- .Drag and drop the time signature onto a palette in a custom workspace •

Time signature properties

:To display the **Time Signature Properties** dialog

-Right-click on a time signature and select Time Signature Properties •



- Global value:** Shows the global time signature and is set automatically when you add a time signature to the score. It is the reference for beats (as shown in the status bar) and tempo markings
- Actual value:** Shows the time signature associated with a particular staff. This is normally the same as the global time signature, but can be set independently if required. See Local time signatures
- Note Groups;** Allows you to change the default beaming of notes associated with a time signature. See Change default beaming
- Appearance:** Allows you to edit the displayed text without affecting the underlying time signature. For an example, see Additive meters

Change default beaming

:To adjust note-beaming for a particular time signature

;...Right-click on the time signature and select, Time Signature Properties .1

To break a note beam in the **Note Groups** panel, click on the note following it. To reset the beam, click in the same place. Alternatively, you can change beaming by dragging a beam icon onto a note, as follows .2

- .Start beam at this note  ○
- .Do not end beam at this note  ○
- .1/8th note beam to left of this note  ○
- .note beam to left of this note 1/16  ○

.The Reset button cancels any changes made in that session

Note: As of version 2.1, checking the box for "Also change shorter notes," means that any beam changes at one level are applied automatically to shorter durations as well. In versions before 2.1 you must adjust beams for the different note durations independently

Additive (composite) meters

Additive (or composite) time signatures are sometimes used to clarify the division of beats within a measure. To create an additive time signature

- ;...Right-click on a time signature in the score and select Time Signature properties .1
- ;In the **Appearance** section, adjust the "Text" property as required .2
- .Adjust note beaming in the **Note Groups** section if required .3

(Note: The [Time Signatures](#) section of the Master palette also allows you to create additive time signatures (see above

Local time signatures

In certain cases a score may show staves with different time signatures running at the same time. For example, in Bach's
:26. Goldberg Variation

The image shows two identical musical staves for 'VARIATIO 26 a 2 Clav.' with a tempo marking of ♩ = 63. The upper staff is in treble clef with a time signature of 18/16. The lower staff is in bass clef with a time signature of 3/4. The music consists of a continuous eighth-note pattern in the upper staff and a bass line with chords and rests in the lower staff.

In the above example, the [global time signature](#) is 3/4, but the time signature of the upper staff has been set
.independently to 18/16

:To set a **local time signature** for just one staff

.Hold down Ctrl (Mac: Cmd) and drag and drop a time signature from a palette onto an empty measure •

Pickup measures and cadenzas

Occasionally you will need to decrease or increase the duration of a measure without changing the time signature—for
.example, in a pickup measure (anacrusis) or in a cadenza etc. See [Measure operations: Measure duration](#)

Time signature changes and breaks

[Multi-measure rests](#) are interrupted when a time signature change occurs. Also, a [section break](#) will prevent a courtesy
.time signature being shown at the end of the previous measure

See also

[Key signature](#) •

External links

[How To Using Polyrhythm, mixed meters and local time signatures in MuseScore](#) [↗](#) •
.Additive meters [↗](#) at Wikipedia •

Accidentals

The most common types of **accidentals** are provided in the Accidentals toolbar above the score and in the Accidentals
[palette](#) in the [basic workspace](#). A more comprehensive range can be found in the Accidentals palette in the advanced
.workspace

#	b	×	bb
q	()		

Add accidental

Accidentals are automatically added to a note, as appropriate, when you increase or decrease its pitch

.(Increase the pitch of a note by one semitone (favors sharps :† •

.(Decrease the pitch of a note by one semitone (favors flats :‡ •

To add either (i) a double flat or double sharp, (ii) a courtesy (also known as *cautionary* or *reminder*) accidental, or (iii) a non-standard accidental, use one of the following options

.Select a note and click on an accidental in the toolbar above the score •

.(Select a note and double-click an accidental in the Accidentals palette (basic or advanced workspace •

.Drag an accidental from the Accidentals palette on to a note •

:If you wish to add parentheses to a **cautionary accidental**, use one of the following

.Select the accidental in the score and double-click the parentheses symbol in the Accidentals palette •

.Drag the parentheses symbol from the palette onto the accidental •

.(Select the accidental and check the "Has bracket" box in the Inspector (as of version 2.1 •

.If you later change the pitch of a note with cursor keys, manual settings to the accidental are removed

.If required, accidentals can be deleted by clicking on them and pressing Del

Change enharmonic spelling

:To change the enharmonic spelling of a note, or notes, in both written *and* concert pitch views

;Select a note, or group of notes .1

;Press J .2

.Continue pressing J to cycle through the enharmonic equivalents .3

:To change the enharmonic spelling in the written pitch view, without affecting the concert pitch view, or vice versa

;Select a note, or group of notes .1

;(Press Ctrl+J (Mac: Cmd+J) .2

.Continue pressing the same combination of keys to cycle through the enharmonic equivalents .3

Note: If the pitches of selected notes are not all the same, the effect may be unpredictable

Respell pitches

.From the menu, select Notes → Respell Pitches •

See also

Key signature: Change •


External links

Accidental [↗](#) at Wikipedia •

Enharmonic [↗](#) at Wikipedia •

Arpeggios and glissandi

Arpeggio and **Glissando** symbols can be found in the "Arpeggios & Glissandi" palette in the advanced workspace. This palette also includes strum arrows, an arpeggio bracket, wind instrument articulations, and slide in/slide out symbols



:To add a symbol to the score, use one of the following methods

- .Select one or more notes, then double-click a symbol in the "Arpeggios & Glissandi" palette •
- .Drag a symbol from the "Arpeggios & Glissandi" palette onto a note •

Any symbol can be customized by adjusting its properties in the Inspector. Edit handles are also provided in most cases to allow adjustment of length/curvature in Edit mode. If needed for future use, you can save the result in a custom palette

Arpeggios

When an arpeggio or strum arrow is added to the score, it initially spans only one voice. However, you can easily adjust its height by double-clicking the symbol and dragging the handles up or down (for finer adjustment use the keyboard arrows). Playback of the symbol can be turned on or off in the Inspector



(Glissandi (slides

.A **Glissando** or, more informally, a **slide**, spans two consecutive notes, normally in the same voice



.Chord glissandi are also possible



Adjust start and end points

.1 Double-click the symbol to enter edit mode

.2 Click on the start or end handle

o Use Shift+↑↓ to move the handle up or down, from note to note

o Use Shift+←→ moves the handle horizontally, from note to note

This method also allows you to move handles between notes in different voices or even from one staff to another—for cross-staff glissandi, for example. You can also use the keyboard arrow buttons or Ctrl + arrow to make final adjustments to the positions of the handles

Custom glissandi

: To customize the glissando to your requirements, select it and adjust the Inspector properties as follows

- **Type:** Choose between a straight or wavy line
- **Text:** Edit, or delete the text. *Note:* If there isn't enough room between notes, the text is not displayed
- **Style:** Chose how the glissando plays back. There are four options: Chromatic, White keys, Black keys, Diatonic
- **Play:** Check/uncheck the box to turn playback on or off

Wind instrument articulations

Fall, Doit, Plop and **Scoop** symbols are provided. To change the length and curvature, select the symbol, enter edit mode and adjust the handles as described in Edit mode: Lines

Slide in/out

Slide in and **Slide out** lines can also be found in the "Arpeggios & Glissandi" palette. To edit the length and angle of a .(line, double-click on it and drag the handle (or use keyboard arrows for finer adjustment

External links

- [Arpeggio](#)  at Wikipedia •
- [Glissando](#)  at Wikipedia •

Articulations and ornaments

:A comprehensive set of symbols can be found in the **Articulations and Ornaments palette** in the Advanced workspace



.There is also an abbreviated version in the Basic workspace

Articulations

Articulations are the symbols added to the score to show how a note or chord is to be played. The principal symbols in this group are

- [Fermatas](#) •
- Staccato •
- Mezzo-staccato / Portato •
- Staccatissimo •
- Tenuto •
- Sforzato •
- Marcato •

.Specialist articulations are also included for bowed and plucked strings, wind instruments etc

Ornaments

:**Ornaments** include

- Mordents, Inverted Mordents, Pralltrillers •
- Trills •
- Turns •
- [Bends](#) •

.Note: **Appoggiaturas** and **acciaccaturas** can be found in the [Grace Notes palette](#)

Add articulation/ornament

:Use either of the following methods

- .[Select](#) a note or a [range](#) of notes, then double-click a symbol in a palette •
- .Drag a symbol from a palette onto a notehead •

Add accidental to an ornament

:To apply an accidental to an existing ornament, such as a trill

- .1 Select the note to which the ornament is attached
- .2 Open the [Symbols section](#) of the [Master palette](#)

Search for and apply the desired accidental to the score (small accidentals can be found using the search term `.3` ;(=""figured bass
.(Drag the accidental into position (or reposition using keyboard shortcuts or the Inspector .4

Add fermata to a barline

A fermata can be applied directly to a barline by selecting the barline and double-clicking the fermata from a palette. This .does not affect playback though

Keyboard shortcuts

- Toggle Staccato: Shift+S •
- Toggle Tenuto: Shift+N •
- Toggle Sforzato (accent): Shift+V •
- Toggle Marcato: Shift+O •
- / :.(Add Acciaccatura (grace note) •

.Keyboard shortcuts can be customized in MuseScore's Preferences

Adjust position

Immediately after adding an articulation or ornament from a palette, the symbol is automatically selected: It can then be :moved *up or down* from the keyboard as follows

- ;(Press up/down arrow keys for fine positioning (0.1 sp at a time •
- .(Press Ctrl+↑ or Ctrl+↓ (Mac: Cmd+↑ or Cmd+↓) for larger vertical adjustments (1 sp at a time •
- .To flip a symbol to the other side of the note (where applicable), select it and pressX •

:To enable adjustments in *all* directions from the keyboard

Double click on the symbol to enter Edit mode, or click on it and press Ctrl+E (Mac: Cmd+E) , or right-click on the .1 ;"symbol and select "Edit element

Press arrow keys for fine positioning (0.1 sp at a time); or press Ctrl+Arrow (Mac: Cmd+Arrow) for larger adjustments (1 .2 .(sp at a time

You can also change the horizontal and vertical offset values in the Inspector. To position more than one symbol at a .time, select the desired symbols and adjust the offset values in the Inspector

.Note: The symbol can also be repositioned by clicking and dragging, but for more precise control, use the methods above

Articulation properties

Most properties of articulations/ornaments can be edited from the Inspector. Other properties (i.e. direction and anchorposition) can also be accessed by right-clicking on the symbol and selecting Articulation Properties

You can also make **global** adjustments to all existing and subsequently-applied articulations by selecting Style... → .General... → Articulations, Ornaments

See also

Grace notes •

External links

Ornaments  at Wikipedia •

Bends

A variety of simple and complex (multi-stage) bends can be created with the **Bend Tool** ^{full}  , located in the Articulations .and Ornaments palette of the Advanced workspace

Apply a bend


:To apply one or more bends to the score, use one of the following options

- .Select one or more notes and double-click a bend symbol in the palette
- .Drag a bend symbol from the palette on to a note

Edit a bend

:To edit a bend, use one of the following

- ".Right click on a bend symbol in the score and select "Bend properties"
- .Select a bend symbol in the score and press "Properties" in the "Bend" section of the Inspector



Preset options are available, if needed, on the left hand side of the **Bend properties** window. The current bend is represented by a graph consisting of gray lines connected by square, blue **nodes** (see image above). The slope of the line indicates the type of bend

- Up-slope = Up-bend
- Down-slope = Down-bend
- Horizontal line = Hold

The **vertical axis** of the graph represents the amount by which the pitch is bent up or down: one unit equals a quarter-tone: 2 units a semitone, 4 units a whole-tone, and so on. The **horizontal axis** of the graph indicates the length of the bend: each gray line segment extends for 1 space (sp) in the score

:A bend is modified by adding or deleting nodes in the graph

- .To **add** a node, click on an empty intersection
- .To **delete** a node, click on it

Adding a node *lengthens* the bend by 1 sp; deleting a node *shortens* the bend by 1 sp. The *Start* and *End* points of the bend can be moved up and down only

Adjust height

The height of the bend symbol is automatically adjusted so that it appears just above the staff. This height can be reduced, if necessary, with a workaround

- 1 . Create another note on the top line (or space) of the staff, vertically above the note at which you want the bend to start
- 2 . Apply the bend to the higher note first: this will give you a bend symbol with the lowest height
- 3 . To increase the height of the bend move this note downward
- 4 . Drag the bend symbol downwards to the correct position
- 5 . (Mark the top note invisible and silent (using the Inspector)

Adjust position

:To adjust position use one of the following

- .Drag the bend symbol with a mouse

- Click on the symbol and adjust the horizontal and vertical offsets in the [Inspector](#)
- Double click on the symbol; or click on it and press **Ctrl+E** (Mac: **Cmd+E**); or right-click on the symbol and select "Edit element." Then use the arrow keys for fine positioning (0.1 sp at a time); or **Ctrl+Arrow** (Mac: **Cmd+Arrow**) for larger adjustments (1 sp at a time)

Custom bends

After a bend has been created in the score it can be saved for future use by dragging and dropping the symbol to a palette while holding down **Ctrl+Shift** (Mac: **Cmd+Shift**). See [Custom Workspace](#)

Beams

Note beams are set automatically, based on the time signature. To adjust the default beaming, right-click on a time signature and select "Time Signature Properties." See [Change default beaming](#) for details

However, if you want to adjust note beaming manually, on a case-by-case basis, use the **beam symbols** found in the **Beam Properties** palette in the "Basic" or "Advanced" [workspaces](#)



Beam symbols

The following is a list of beam symbols and their effects

- (Start a beam at this note (or rest)
- (Do not end a beam at this note (or rest)
- Do not beam this note
- Start a second level beam at this note
- Start a third level beam at this note
- back to) Automatic mode: the mode MuseScore chooses on note input, dependent on current [time signature](#) and its [beam settings](#)
- Start feathered beam (slower) at this note
- Start feathered beam (faster) at this note

Change note beaming

To change one or more *note beams* (except feathered beams, below), use either of the following methods

- Drag and drop a beam symbol from a [workspace](#) onto a note in the score
- [Select](#) one or more notes in the score and double click the desired [workspace](#) beam symbol

To apply *feathered note beams*, use either of the following methods

- Drag and drop a feathered-beam symbol from a workspace onto a note beam in the score
- Select one or more note beams in the score, then double click on a feathered-beam symbol in the workspace

Notes: (1) Feathered beams may use 2 or 3 lines depending on the tempo and the desired rate of the change; (2) To create a 2-line feathered beam, you need to start with a *continuous* run of beamed sixteenth notes; (3) To create a 3-line feathered beam, you need to start with *continuous* run of beamed thirty-second notes; (4) Playback of feathered beams is not supported

Adjust beam with the keyboard/mouse

Adjust beam angle

1. Double-click on a note beam or select it and press **Ctrl+E** to put it into edit mode—the right end handle is automatically selected.
2. Use the up/down arrows or drag the right end handle to change the angle of the beam.
3. Press **Esc** to exit edit mode.

Adjust beam height

1. Double-click on a note beam or select it and press **Ctrl+E** to put it into edit mode—the right end handle is automatically selected.
2. Press **Shift+Tab** or click the left handle to select it.
3. Use the up/down arrows or drag the left end handle to change the height of the beam.
4. Press **Esc** to exit edit mode.

Adjust beam with the inspector

:Alternatively, you can use the Inspector for all of these operations

Adjust beam angle

1. Click on a note beam.
2. Tick the "User position" box in the "Beam" section of the **Inspector**.
3. Set the "Position" values to get the desired beam angle.

Adjust beam height

1. Click on a note beam.
2. Tick the "User position" box in the "Beam" section of the **Inspector**.
3. Set the "Position" values as desired.

Make the beam horizontal

1. Select a note beam.
2. Tick the "Horizontal" box in the "Beam" section of the inspector.
3. If desired, adjust the beam height with the keyboard/mouse: see above.

.If you want all note beams in the score to be horizontal there is a "Flatten all beams" option in **Style** → **General** → **Beams**


Adjust feathered beams

:To adjust feathered beams

1. Select a note beam.
2. Adjust the values in the "Grow left" and "Grow right" boxes in the "Beam" section of the Inspector.

Local relayout

MuseScore (following accepted music engraving practice) spaces notes according to their time values, allowing for accidentals, lyrics etc. In systems where there is more than one staff, this may result in irregular note spacing, as in the following example



Local relayout is a tickbox option in the Inspector allowing you to specify those passages in the score where you want

the note spacing to be independent of other staves in the system. Applying "Local relayout" to the note beams in the top staff of the previous example results in a more even distribution of notes



:To do a local relayout

- .1 Select one or more note beams
- .2 Tick the option **Local relayout** in the "Beam" section of the **Inspector**

Flip note beam

:To flip a beam from above to below the notes, or vice-versa

- .1 Select one or more note beams
- .2 Use any of the following options
 - o Press the x key
 - o Press the "Flip direction" icon in the bottom right of the toolbar area
 - o Select a "Direction" option (Auto, Up or Down) in the "Beam" section of the **Inspector**

Reset Beam Mode

:To restore beams to the mode defined in the local time signatures

- .1 Select the section of the score you want to reset. If nothing is selected, the operation will apply to the whole score
- .2 Select Layout → Reset Beam Mode

See also

- [Cross-staff notation](#)
- [Edit mode](#)
- [Note input](#)

External links

- [How to add a beam over a rest](#)
- [How to place a beam between notes](#)

Brackets

.MuseScore provides standard **brackets** and a curly **brace** within the **Brackets** [palette](#) in the advanced [workspace](#)



Add

:To add a bracket or brace to systems, use one of two methods

- Drag a bracket symbol from a palette on to an empty space in the first measure of the staff where you want the bracket to start
- Select the first measure of the staff where you want the bracket to start and double-click a bracket symbol in a palette

Delete

- Select the bracket and press Del

Change

- Drag a bracket symbol from a palette onto an existing bracket in the score

Edit

:When you first apply a bracket it only spans one staff. To extend to other staves

.1 Enter Edit mode

Drag the handle downwards to span the required staves. The handle snaps into position, so exact placement is not .2
.required

Style

The default thickness and distance from the system of brackets and braces can be adjusted in Style → General... → System

Breaths and pauses

.**Breath** and **pause** markings are available in the **Breaths & Pauses** palette in the advanced workspace



Add symbol

To add a breath or pause (the latter also called a *caesura*, or informally "tram lines" or "railroad tracks") to the score, use one of the following options

- Select a note or rest and double-click a breath or pause symbol in a palette
- Drag a breath or pause symbol from a palette onto a note or rest in the score



.The symbol is placed after the note

Adjust position

:To adjust the position of the breath or pause, use any of the following options

- Click on the symbol and adjust the Horizontal or Vertical offsets in the Inspector
- Enter edit mode on the symbol, and use arrow key shortcuts

Adjust pause length

From version 2.1 onwards, you can adjust the pause length (in seconds) of the added symbol using the "Breath" or "Caesura" category in the Inspector

Grace notes

A **grace note** is a type of musical ornament, usually printed smaller than regular notes. The **Short grace note**, or Acciaccatura, appears as a small note with a stroke through the stem. The **Long grace note**, or Appoggiatura, has no .stroke



Create grace notes

.Grace notes can be found in the "Grace notes" [palette](#) in the Basic or Advanced workspace

Add a grace note

:Use one of the following methods

- ;Select a regular note and double click a grace note in [palette](#)
- ;Drag a grace note symbol from a palette onto a regular note
- .Select a note and press / to create an acciaccatura only

This will add a grace note of the same pitch as the regular note. To add a *sequence* of grace notes to a regular note, (simply repeat the above actions as many times as required. See also, [Change pitch](#) (below

Note: When a grace note is added to the score, a slur is *not* automatically created with it, so the latter needs to be added separately. See [Slurs](#)

Add a chord of grace notes

:Grace note chords are built up just like regular chords

Enter the first note of the chord as shown above .1

.(Select this first grace note and enter subsequent notes as you would for any other regular chord (i.e.Shift+A...G .2

You can also create a grace note chord by using the **add interval** shortcut in step 2:Alt+1...9 for intervals from a unison to a ninth above

Change pitch

:The pitch of a grace note can be adjusted just like a regular one

Select one or more grace notes .1

:Adjust pitch using the keyboard arrow commands, namely .2

;or ↑ to increase or decrease the pitch by a semitone ↑ ◦

.Alt+Shift+↑ or Alt+Shift+↓ to increase or decrease the pitch one step at a time, according to the key signature ◦

Change duration

If you want to change the duration of a previously created grace note, select it and choose a duration from the toolbar (enter with one of the keys 1...9 (see [Note input](#)

Manual adjustment

The position of a grace note after a note (such as a trill termination) may have to be adjusted by selecting the note, going into [edit mode](#) and using the left/right keyboard arrows; or change the chord offset values in the Inspector

External links

- [Grace note](#) at Wikipedia
- [Appoggiatura](#) at Wikipedia
- [Acciaccatura](#) at Wikipedia

Hairpins

Add a hairpin

:**Hairpins** are [line](#) objects. To create a hairpin

:[Select](#) a range of notes or measures .1

- .Use one of the following shortcuts .2
- .to create a crescendo hairpin :> ◦
- .(to create a diminuendo hairpin (decrescendo) :< ◦



:Alternatively, use one of the following options

- .Select a range of notes or measures, and double-click a hairpin in a palette •
- .Drag and drop a hairpin from a palette onto a staff line •

Adjust length

:Double-click on the hairpin to enter edit mode. Then click on the end handle that you want to move .1



:Use one of the following shortcuts .2

- .Shift+ → to move the end handle, and its anchor, right by one note or rest ◦
- ;Shift+ ← to move the end handle, and its anchor, left by one note or rest ◦

:This method of extending or shortening the hairpin maintains playback integrity and allows it to cross line breaks



:To change the position of an end handle *without* changing the position of its anchor, use the following shortcuts .3

- .to move the handle right by 0.1 sp → ◦
- .to move the handle left 0.1 sp ← ◦
- .Ctrl+ → (Mac: Cmd+ →) to move the handle right one sp ◦
- .Ctrl+ ← (Mac: Cmd+ ←) to move the handle left one sp ◦

Note: The commands listed in step 3 are only used to tweak the final appearance of the hairpin (e.g. see image below): they do *not* change its playback extent nor do they allow it to cross line breaks. If you want the latter, use the .(Shift+ → or Shift+ ← commands instead (step 2



Note: The "Reset" command (Ctrl+R (Mac: Cmd+R)) will undo these small adjustments, but will not undo anchor .changes

Cresc. and dim. lines

In addition to hairpins, there are *cresc.* _ _ _and *dim.* _ _ _lines with the same function in the Lines palette. To change the text (e.g. to *cresc. poco a poco*, or *decresc.* instead of *dim*), right-click on the line and choose LineProperties

:To turn a hairpin into its equivalent text line

- .Select the hairpin .1
- ".In the Inspector, set "Line style" to "Wide dashed" .2

.In the Inspector, select the "Text line" checkbox .3

Hairpin playback

Crescendo and diminuendo lines only affect playback from one note to the next: they have no affect (currently) on the .playback of a single note or a series of tied notes


By default, hairpins will affect playback only if dynamics are used before and after the hairpin. For example, a crescendo spanning notes between **p** and **f** dynamics will cause a dynamic change on playback. However, between any two successive dynamics only the first appropriate hairpin will have effect: a diminuendo between **p** and **f** will be ignored; of .two or more crescendos between **p** and **f** , all but the first will be ignored

A hairpin may be used without dynamic marks, by adjusting "Velocity change" in the Inspector (values in the range 0 to .(127

Lines

:The **Lines** palette of the Advanced workspace includes the following types of **lines**

- Slur
- (Hairpins (crescendo and diminuendo
- (Volta brackets (1st, 2nd, 3rd time endings etc
- (Octave lines (8va, 8vb, 15ma etc
- Keyboard pedal markings
- (Extended ornament lines (Trills etc
- Guitar barre line
- Straight line
- (Ambitus (early music symbol



Applying lines to the score

:Most lines (except Slurs , Volta brackets and the Ambitus) can be applied from a palette in the following ways

To apply a line to *just* one note

- .1 ;Click on a note, then Ctrl+Click on the next note
- .2 .Double-click a line

To apply a line across a range of notes

- .1 Select a range of notes
- .2 Double-click a line

To apply a line from a note to the end of that measure

:Use any of the following methods

- Click on a note, then double click a line
- Drag and drop a line onto the score

To apply a line across a range of measures

- .1 Select one or more measures
- .2 Double click a line

Adjust vertical position

:To adjust the vertical position of one or more lines

- .1 Ensure you are not in note-input or edit mode
- .2 Use either of the following
 - Click on one or more lines and change the vertical offset in the Inspector
 - Click on a line, press and hold **Shift** and drag it up/down with a mouse

Note: You can also adjust the vertical position in Edit mode

Change length

- .1 (Ensure you are not in note input mode (press **Esc** to exit
- .2 Double click the line that you want to change to enter edit mode
- .3 Click on an end handle and use one of the following shortcuts
 - (**Shift**+**→** to move the end handle, and its anchor, right by one note (or, in the case of oltas, one measure
 - (**Shift**+**←** to move the end handle, and its anchor, left by one note (or, in the case of Voltas, one measure

:To change the position of an end handle *without* changing the position of its anchor, use the following .4

- (to move the handle right by 0.1 **sp** (1 sp = one staff space = the distance between two staff lines
- .to move the handle left 0.1 sp
- **Ctrl**+**→** (Mac: **Cmd**+**→**) to move the handle right one sp
- **Ctrl**+**←** (Mac: **Cmd**+**←**) to move the handle left one sp

Note: You can also drag the endpoint handles with a mouse

Text lines

.A **text line** is a line that has text embedded within it—such as a volta, ottava, guitar barre line etc

When you apply a text line to the score from a palette, the line properties (see below) always remain unchanged, but the properties of embedded text may vary depending on circumstances. See Behavior of applied text and lines for details

Custom lines and line properties

Lines may contain features such as embedded text or hooks at the ends (e.g. ottavas and voltas). They can be customized once they have been added to the score, and the results saved to a workspace for future use

;.1 Right-click on a line and select Line Properties

.2 Add any text you want to appear in the line

- **Begin:** Text added here appears at the beginning of the line
- **Continue:** Text added here appears at the beginning of a continuation line
- **End:** Text added here appears at the end of the line

.Click on the ... buttons to adjust the Text properties at each position as required

;If a hook is required, tick the appropriate **'Hook'** box, and adjust the hook length and angle .3

Select an option from **"Place"**: "Above or "Below" positions the text so that it overlaps the line; "Left" places the text .4
;to the left of the line

.(**Note**: Additional placement options are available in the **"Text properties"** dialog (see step 2, above

;Click OK to exit Line Properties .5

Make adjustments to **Color**, **Thickness** and **Line type** (solid, dashed etc.) in the **'Line'** section of the Inspector. .6

;Ticking **"Diagonal"** here allows you to create a diagonal line by dragging the end handles

.If you wish to save the resulting line for future use, see Custom palettes .7

Copying lines

Once applied to the score, lines cannot be copied using the usual copy and paste procedures. However, you can duplicate lines within a score: press and hold Ctrl+Shift (Mac: Cmd+Shift), click on the line and drag it to the desired location

Extended ornament lines

To add an accidental to an extended ornament, such as a trill line, select the line and double-click a symbol from the .Accidentals palette

External links

[Piano pedal marks](#)  at Wikipedia •

[Guitar Barre](#)  at Wikipedia •

Measure rests

Full measure rest

A **whole rest**, centred within a measure (shown below), is used to indicate that an entire measure (or a voice within a .measure) is silent, regardless of time signature



To create one or more full measure rests

:Use the following method if all selected measures are "standard"—i.e. with no custom durations

.Select a measure, or range of measures 1

.Press Del .2

:If one or more of the measures contains a custom duration, use the following method instead

.Select a measure, or range of measures .1

.(Press Ctrl+Shift+Del (Mac: Cmd+Shift+Del .2

To create a full measure rest in a *particular* voice

.In the appropriate voice, enter a rest that extends for the full measure .1

.(Make sure the rest is selected, then press Ctrl+Shift+Del (Mac: Cmd+Shift+Del .2

Multimeasure rest

A **Multimeasure rest** indicates a period of silence for an instrument: the number of measures is shown by the number .above the staff



Multimeasure rests are automatically interrupted at important points, such as double barlines, rehearsal marks, key- or time signature changes, section breaks etc

To display multimeasure rests

:To turn multimeasure rests on or off

.Press M on your keyboard •

:Alternatively

...From the menu, choose Style → General .1

;Click on the "Score" tab, if it is not already selected .2

".Tick/untick "Create multi-measure rests" .3

.Note: It is recommended that you enter all notes in the score first before enabling multi-measure rests

Break multimeasure rest

:You may want to have a multi-measure rest divided into two multi-measure rests

.(Ensure that the option to display multimeasure rests in the score is *off* (see [above](#)) .1

;Right-click on the measure where you want the second multi-measure rest to start .2

".From the menu, choose Measure Properties and tick "Break multi-measure rest" .3

.See also: [Measure operations: Break multimeasure rest](#)

Octave lines

Octave (Ottava) lines are used to indicate that a section of music is to be played one or more octaves above or below written pitch: The line may be dotted or solid. Ottavas are available in the [Lines palette](#) of the Basic and Advanced [workspaces](#)

or *8va* ———] : Play one octave above written pitch] ——— 8
or *8vb* ———] : Play one octave below written pitch] ——— 8

8va/8vb lines are particularly common in piano scores, though they are sometimes used in other instrumental music.¹
.15ma (2 octaves above) and 15mb (2 octaves below) are also occasionally used



Apply an octave line

:Use one of the following

.[Select](#) a range of notes, then double click an octave line from a palette •

.[Select](#) one or more measures, then double click an octave line from a palette •

.(Click on a note, then double-click an octave line from the palette (extends line from selected note to end of bar •

.(Drag an octave line from a palette onto a note (extends line from selected note to end of bar •

.See also, [Lines: Adjust vertical position](#)

Change length

.See [Lines: Change length](#)

.Octaves can be customized just like any other line. See [Lines: Custom lines and line properties](#)

External links

[Octave](#)  at Wikipedia •

[↶](#) .(Gerou/Lusk. *Essential Dictionary of Music Notation* ([Internet Archive](#) ) .1

Slurs

A **slur** is a curved line between two or more notes indicating that they are to be played *legato*—smoothly and without separation. Not to be confused with [Ties](#), which join two notes of the same pitch

There are a number of ways to add a slur to a score, and all may be useful depending on the context (adding a slur from the [lines palette](#) is also possible but not recommended

Add slur in note-input mode

- .1 ;While in [note input mode](#), type in the first note in the slurred section
- .2 ;Press s to begin the slurred section
- .3 ;Type in the remaining notes in the slurred section
- .4 .Press s again to end the slurred section

Add slur *outside* note-input mode

Method 1


.1 :Make sure you are *not* in note input mode and select the first note that you want the slur to cover




.2 :Press s to add a slur extending to the next note



.3 :Optional) Hold Shift and press → (right arrow key) to extend the slur to the next note. Repeat as required)



.4 :Optional) Press x to flip the slur direction)



.5 :Press Esc to exit [edit mode](#)



Method 2

.1 ;Make sure you are *not* in [note input mode](#)

;Select the note where you want the slur to start .2

:Chose one of the following options .3

To add a slur to one voice *only*: Hold down Ctrl (⌘ on a Mac) and select the last note that you want the slur to cover

To add slurs to *all* voices: Hold down Shift (⇧ on a Mac) and select the last note that you want the slurs to cover

.Press s .4

Adjust slur

:If you only want to adjust the *position* of a slur

;Select the slur .1

:Use any of the following methods .2

.Drag the slur ◦

.Adjust the horizontal and vertical offset values in the Inspector ◦

:(To adjust *all* the properties of a slur (length, shape and position

;Make sure you are *not* in note input mode .1

;"Double-click the slur to enter edit mode (or select it and press Ctrl+E; or right-click it and select "Edit Element .2

;Click on a handle to select it, or use Tab to cycle through the handles .3

:To move the *left and right handles* from note to note, use the following shortcuts .4

.Shift+ → : Move to next note ◦

.Shift+ ← : Move to previous note ◦

.(.Shift+↑ : Move to lower voice (voice 2 to voice 1 etc ◦

.(.Shift+↓ : Move to higher voice (voice 1 to voice 2 etc ◦

:To adjust the position of *any* handle, use any of the following methods .5

.Drag the handle ◦

.Use the arrow keys for fine adjustment (0.1 sp. at a time). For larger adjustments (1 sp. at a time) use Ctrl+Arrow ◦

.Press Esc to exit edit mode .6

Note: The two outer handles adjust the start and end of the slur, whilst the three handles on the curve adjust the contour. The middle handle on the straight line is used to move the whole slur up/down/left/right

Extended slurs

A slur can span several systems and pages. The start and end of a slur is anchored to a note/chord or rest. If the notes are repositioned due to changes in the layout, stretch or style, the slur also moves and adjusts in size

This example shows a slur spanning from the bass to the treble clef. Using the mouse, select the first note of the slur, hold down Ctrl (Mac: ⌘) and select the last note for the slur, and press s to add the slur



.x flips the direction of a selected slur

Dotted slurs

Dotted slurs are sometimes used in songs where the presence of a slur varies between stanzas. Dotted slurs are also used to indicate an editor's suggestion (as opposed to the composer's original markings). To change an existing slur into a dotted or dashed slur, select it and then in Inspector (F8) change Line type from Continuous to Dotted Or Dashed

See also

- [Tie](#) •
- [Edit mode](#) •
- [Note input](#) •

Ties

A **tie** is a curved line between two notes of the *same* pitch, indicating that they are to be played as one note with a combined duration (see [external links](#) below). Ties are normally created between adjacent notes in the same *voice*, but MuseScore also supports ties between non-adjacent notes and between notes in different *voices*.

In [note-input mode](#), if you specify a tie immediately after entering a note or chord, the program automatically generates the correct destination notes to go with the ties. Or, you can simply create ties "after the fact," between existing notes

Note: Ties, which join notes of the *same* pitch, should not be confused with [slurs](#), which join notes of *different* pitches and indicate *legato* articulation.

Tie notes together

1. Press Esc to make sure you are not in note input mode
2. Click on a note, or use Ctrl (Mac: Cmd) + click to select more than one note



3. Press + or the tie button




Ties will be created between the selected note(s) and the following note(s) of the same pitch

Tie chords together

To tie all the notes in a chord at once, either

- Click on the stem of the chord, or
- Hold down Shift and click on any note in the chord

Then press + or the tie button. Ties will be created between all the notes in the selected chord and the following notes of the same pitches



Add tied notes in note input mode

To create a single note tie during [note input](#)

1. (Select a single note (one that is not part of a chord
2. (Select a new [note duration](#) for the following note, if required (but see "Note" below
3. Press + or the tie button

Note: This shortcut works, as described above, only if there is no chord following the selected note. If there is, then the duration is ignored and the tied note is added instead to the following chord

Add a tied chord in note input mode

- .1 Make sure one note is selected *in a chord*
- .2 (Select a new note duration for the following chord, if required (but see "Note" below)
- .3 , Press + or the tie button

Note: This shortcut works, as described above, only if there is no chord following the selected note. If there is, then the duration is ignored and the tied notes are added instead to the following chord

Tied unison notes

:If the chords to be tied contain unison notes the best way to ensure correct notation is

- .1 Assign each note of a unison pair to a separate voice
- .2 (Ensure that one of the unison pairs is set to "stemless" (to remove the duplicate stem and tail)
- .3 Apply the ties voice by voice. Make adjustments for position, length as required

Flip a tie

.x flips the direction of a selected tie, from above the note to below the note, or vice-versa

See also

[Slur](#)

External links

- [How to create ties leading into a 2nd ending](#) 
- [Ties \(music\)](#)  at Wikipedia

Tremolo

Tremolo is the rapid repetition of one note, or a rapid alternation between two notes or chords. It is indicated by strokes through the stems of the notes or chords. If the tremolo is between two, the bars are drawn between them. Tremolo symbols are also used to notate drum rolls

The tremolo palette in the advanced workspace contains separate symbols for one note tremolos (shown with stems below) and for two note tremolos (shown with no stem below)



.To add tremolo to a single note, select the note head and double-click the desired symbol in the tremolo palette

In a two note tremolo, every note has the value of the whole tremolo duration. To enter a tremolo with the duration of a half note (minim), enter two normal quarter notes (crotchets), and after applying a tremolo symbol to the first note, the note values automatically double to half notes

Tuplets

Tuplets are used to write rhythms beyond the beat divisions usually permitted by the time signature. For example, a sixteenth note **triplet** divides an eighth note beat into three sixteenth notes instead of two



:In 6/8 time, an eighth note **duplet** divides a dotted quarter note into two eighth notes instead of three



Create a tuplet

The exact method of tuplet entry depends on whether you are starting off in Note input mode or Normal mode. We'll start off with a simple example: the creation of an eighth note triplet

Create a triplet in normal mode

Select a note or rest that specifies the full duration of the desired triplet group. In the case of an eighth note triplet, you will need to select a quarter note or rest—as in the example below



From the main menu, choose Notes → Tuplets → Triplet, or press Ctrl+3 (Mac: ⌘+3). This will give the following result



The program automatically changes to note-input mode and selects the most appropriate duration—in this example an eighth note. Now enter the desired series of notes/rests. For example



Create a triplet in note input mode

1. (Ensure you are in note input mode (press N
2. Navigate to the note/rest (or blank measure) where you want the triplet to start (use the left/right arrow keys as required
3. Select a final duration for the whole triplet group. In the case of an eighth note triplet, click on the quarter note in the (note input toolbar (or press 5 on the keyboard
4. From the main menu, choose Notes → Tuplets → Triplet, or press Ctrl+3 (Mac: ⌘+3). This creates a triplet number/bracket (and appropriately divides the original note/rest (see image above
5. The program automatically selects the most appropriate duration—in this example an eighth note—allowing you to immediately start entering the desired series of notes/rests

Create other tuplets

To create other tuplets (Duplet (2) to Nonuplet (9)), substitute one of the following commands at the relevant step above

- (Press Ctrl+2–9 (Mac: Cmd+2–9
- From the menu, select Notes → Tuplets, then click on the desired option


For more complex cases, see [below](#)

Custom tuplets


(To create other tuplets than the default options (e.g. 13 sixteenth notes in the space of one quarter note

1. In Note input mode, select a note duration equaling the total duration of the tuplet; or, if in Normal mode, select a note or rest of the desired overall duration
2. Open the **Create Tuplet** dialog from the menu: Notes → Tuplets → Other

Select the desired number ratio (e.g. 13/4 for thirteen sixteenth notes in the space of a quarter note) under "Relation" in the "Type" section. Specify "Number" and "Bracket" using the radio buttons in the "Format" section



.Click OK to close the dialog .4



.Enter the desired series of notes/rests .5

Delete a tuplet


.To delete any tuplet, select the number/bracket and press Del

Change display of tuplets

- To change the way that tuplets are displayed in the score, adjust the properties in the "Tuplet" section of the Inspector
- .Some general settings for tuplets can also be found in Style → General... → Tuplets

Using the Inspector

To change the display properties of tuplets in the score, select the tuplet numbers/brackets, and adjust the desired properties in the "Tuplet" section of the Inspector



If neither the number nor the bracket of the tuplet is shown in the score, select a note from the tuplet, then use the Tuplet button in the Inspector to display the "Tuplet" section



Direction

- .Auto" places the bracket/number in the *default* position"
- .Up" places the bracket *above* the note heads, regardless of the stem, or beam position"

- ".Down" places the bracket *below* the note heads, regardless of the stem, or beam position"

Number type

- ".Number" shows an integer"
- ".Relation` shows a ratio of two integers"
- ".Nothing" turns off number display"





Bracket type

- "Automatic" *hides* the bracket for beamed notes and *shows* the bracket if the tuplet includes unbeamed notes or".rests
- ".Bracket" displays the bracket"
- ".Nothing" hides the bracket"

Using the Style menu


To make fine adjustments to the way that *all* tuplets in the score are displayed, from the menu, select `Style → General...` and `.select Tuplets`





Two adjustments are possible: Vertical and Horizontal

- Vertical adjustment has three options with values in space units and one (un)ticked option
 - Maximum slope: default value is 0.50; range is from 0.10 to 1.00
 - Vertical distance from stem (see (2) below): default value is 0.25; range is from -5.00 to 5.00
 - Vertical distance from note head (see (3) below): default value is 0.50; range is from -5.00 to 5.00
 - Avoid the staves: by default ticked
- Horizontal has four options with values in space units
 - Distance before the stem of the first note (see (5) below): default value is 0.50; range is from -5.00 to 5.00
 - Distance before the head of the first note: default value is 0.00; range is from -5.00 to 5.00
 - Distance after the stem of the last note (see (6) below): default value is 0.50; range is from -5.00 to 5.00
 - Distance after the head of the last note: default value is 0.00; range is from -5.00 to 5.00



External links

- [How to create triplets and other tuplets](#)
- [How to create nonstandard tuplets](#)
- [Tuplet](#) at Wikipedia
- [\[The User Guide to Tuplets in MuseScore](#) [video]

Repeats and jumps

Simple repeats

You can create a **simple repeat** by placing a **start** and an **end repeat barline** at the beginning and end of a passage. These barlines are applied from the [Barlines](#) palette, and, as of version 2.1, also from the **Repeats & Jumps** palette



Note: If the start of a repeat coincides with the *beginning* of a piece or section, the start repeat barline can be omitted if desired. Similarly, an end repeat barline can be omitted at the *end* of a score or section.



1st and 2nd endings

First create a simple repeat (as shown above), then apply the first and second time endings—see [Volts](#)

Playback

To hear repeats during playback, make sure the "Play Repeats"  button on the toolbar is selected. Likewise, you can turn off repeats during playback by deselecting the button.

To set the number of times that a repeat section plays back

1. (Make sure the start and end repeat barlines are in place (e.g. [Simple repeats](#) above)
2. Right-click on the last measure before the end repeat barline and select [Measure properties](#)
3. Adjust "[Play count](#)" ("Repeat count" prior to version 2.1) as required

Repeat symbols and text

Text and symbols related to repeats are located in the **Repeats & Jumps** [palette](#) (in the Basic and Advanced workspaces). This palette contains

- Symbols for measure repeat, Segno, Coda, and, as of version 2.1, repeat barlines
- D.S., D.C., To Coda, and Fine text

	
	
	Fine
To Coda	D.C.
D.C. al Fine	D.C. al Coda
D.S. al Coda	D.S. al Fine
D.S.	
	

To add a **repeat** symbol to the score use either of the following

- Drag and drop a repeat symbol from the palette *onto* (not above!) the desired measure (so the measure changes color)
- Select a measure, then double-click the desired repeat symbol in the palette

Jumps

Jumps are symbols in the score which tell the musician, and playback, to skip to a named marker (see below). Jumps include the various kinds of D.C. (Da Capo) and D.S. (Dal Segno) text

If you click on a *jump*, some text boxes and a checkbox are displayed in the **Jump** section of the [Inspector](#). These have the following effects on playback

- **Jump to:** Playback jumps to the marker whose "Label" is the same as the "Jump to" tag
- **Play until:** Playback continues until it reaches a marker whose "Label" is the same as the "Play until" tag
- **Continue:** Playback jumps to the next marker whose "Label" is the same as the "Continue" tag
- **Play repeats:** (As of version 2.2) Ticking this box tells MuseScore to play repeats after D.C. (Da Capo) or D.S. (Dal

Segno) jumps. If this option is not ticked then simple Repeats are not taken after jumps and playback works as if it were the last repeat. *Note:* Ticking this option makes no difference to playback in versions prior to 2.2

Note: The tags *start* and *end*, referring to the beginning and end of a score or section, are *implicit* and don't need to be added by the user

Markers

Markers are the places referred to by the jumps. A list of markers (in addition to the implicit "start" and "end") follows

- (Segno (tag: *segno* :  •
- (Segno Variation (tag: *varsegno* :  •
- (Coda (tag: *codab* :  •
- (Coda Variation (tag: *varcoda* :  •
- (**Fine**: (tag: *fine* •
- (**To Coda**: (tag: *coda* •

If you click on a marker, the following properties appears in the **Marker** section of the Inspector

- Marker type:** This can be changed from the dropdown list, if required •
- Label:** This is the (identifier) tag associated with the marker. See also Jumps (above) •

Examples of jumps

- Da Capo (D.C.):** At the "D.C." sign, playback jumps to the start (i.e. to the implicit *start* tag) and plays the entire (score or section again (i.e. up to the implicit *end* tag) •
- Da Capo (D.C.) al Fine:** At the "D.C. al Fine" sign, playback jumps to the start (i.e. to the implicit *start* tag) and plays (the score up to the **Fine** (i.e. the *fine* tag) •
- Dal Segno (D.S.) al Fine:** At the "D.S. al Fine" sign, playback jumps to the **Segno** symbol (i.e. the *segno* tag) and (then plays up to the **Fine** (i.e. the *fine* tag) •
- Dal Segno (D.S.) al Coda:** At the "D.S. al Coda" sign, playback jumps to the **Segno** symbol (i.e. the *segno* tag) and (then plays up to the **To Coda** (i.e. the *coda* tag). Playback then continues at the **Coda** symbol (i.e. the *codab* tag) •

Note: The properties (i.e. the tag names) of jumps and markers can be set via the Inspector. You need to modify them if using multiple jumps and markers

See also

- Barlines •
- Volta •

External links

- (MuseScore in Minutes: Repeats and Endings, part 2  (video tutorial) •
- (How to separate a coda from the rest of the score  (MuseScore HowTo) •

Voltas

Volta brackets, or first and second ending brackets, are used to mark different endings for a repeat



To add a volta to the score

Use one of the following methods

- Select a measure, or range of measures and double-click a Volta icon in the Lines palette •
- (Drag-and-drop a volta from the Lines palette, then adjust the length as required (see below) •

To change the number of measures that a volta covers

.Double-click the volta to enter edit mode. The end handle is automatically selected .1
 Press Shift+ → to move the end handle *forward* one measure. Press Shift+ ← to move the handle *backward* one .2
 .measure. Repeat as required


Note: Only the Shift commands will alter the *playback* start and end points of the volta. To make fine adjustments to the *visual* start or end points you can use other keyboard arrow commands, or drag the handles with a mouse, but these do .not affect the playback properties

When you select a start or end handle, a dashed line appears connecting it to an anchor point on the staff. This anchor .shows the position of the *playback* start or end point of the Volta




Text

You can change the text and many other properties of a volta bracket using the line properties dialog. Right-click on a ".volta bracket and choose Line Properties.... The figure below shows the volta text as "1.-5



You can also right-click on the volta and bring up the volta properties dialog. From here, you can change both the displayed Volta text (the same from the line properties above) and the repeat list. If you want one volta to be played only on certain repeats and another volta on other repeats, enter the repeat times in a comma separated list. In the example below, this volta will be played during repeat 1, 2, 4, 5 and 7. Another volta will have the other ending, like 3, 6 and .possibly other higher numbers like 8, 9, etc



Playback

Sometimes a repeat plays more than two times. In the figure above, the volta text indicates that it should play five times before it continues. If you want to change the number of times MuseScore plays a repeat, go to the measure containing the end repeat barline and change its Play count (Repeat Count prior to version 2.1). See [Measure operations: Other .properties](#) for details

External links

- [MuseScore in Minutes, Lesson 8: Repeats and Endings, Part 1](#)  •
- [How to create ties leading into a 2nd ending](#)  •

Transposition

Transposition is the act of raising or lowering the pitch of a selection of notes by the same interval. You can choose to transpose notes either manually or by using the [Transpose dialog](#)

Manual transposition


- .1 Select the notes that you wish to transpose
- .2 Use any of the following options

- **To transpose chromatically:** Press ↑ or ↓. Repeat as required
- **To transpose diatonically:** Press Alt + Shift + ↑ or ↓. Repeat as required
- **To transpose by an octave:** Press Ctrl + ↑ or ↓ (Mac: Cmd + ↑ or ↓)

Note: In versions prior to 2.1, F2 (Mac: fn+F2) transposes the whole score and key signature UP one semitone. Shift+F2 (Mac: Shift+fn +F2) transposes the score and key signature DOWN one semitone

Automatic transposition

MuseScore's **Transpose** dialog gives you more options for transposing notes



Note: By default this dialog opens from the **Notes** menu, but you can also chose to open it using a keyboard shortcut (see [Preferences](#)).

Transpose Chromatically

By Key

:To transpose notes up or down to the nearest key

- .1 ;".Select the notes you want to transpose; no selection equals "select all"
- .2 ;...From the menu bar, choose Notes → Transpose
- .3 ";Tick "Transpose Chromatically" and "By Key"
- .4 ;Tick/untick "Transpose key signature" and "Transpose chord symbols" if required
- .5 ;Tick one of "Closest," "Up" or "Down;" and select a destination key signature from the drop-down menu
- .6 .Click OK

By Interval

:To transpose selected notes up or down in semitone increments

- .1 ;".Select the notes you want to transpose; no selection equals "select all"
- .2 ;...From the menu bar, choose Notes → Transpose
- .3 ";Tick "Transpose Chromatically" and "By Interval"
- .4 ;Tick/untick "Transpose key signature" and "Transpose chord symbols" if required
- .5 ;Tick "Up" or "Down;" and select a transposition interval from the drop-down menu
- .6 .Click OK

Transpose Diatonically

:To transpose selected notes up or down by a diatonic interval

- .1 ;".Select the notes you want to transpose; no selection equals "select all"
- .2 ;...From the menu bar, choose Notes → Transpose
- .3 ";Tick "Transpose Diatonically"
- .4 ;Tick/untick "Transpose key signature" and "Transpose chord symbols" if required
- .5 ;Tick "Up" or "Down;" and select a transposition interval from the drop-down menu
- .6 .Click OK

Transposing instruments

Transposing instruments, such as the B-flat trumpet or E-flat alto sax, sound lower, or higher than their written pitch. MuseScore has a number of features to facilitate the scoring of these instruments

Concert pitch

MuseScore's default viewing mode shows the musical notation in **written pitch**, but you can choose to display the score in concert pitch instead. In the latter mode, the musical notation of *all* instruments matches the actual pitches that you hear on playback

To switch to concert pitch, use one of the following options

- Press the Concert Pitch button to highlight it
- From the menu bar, select Notes and tick the Concert Pitch option

You should ensure that the Concert pitch button is OFF before printing the main score or any parts

Change staff transposition

Instrument transpositions are already set up in MuseScore. However, if you want a rare instrument or transposition that is not available in MuseScore, you may need to edit the instrument transposition manually

...Right-click an empty part of the instrument staff and select Staff Properties .1

At the bottom of the window, select the interval of transposition, any octave shifts, and whether the interval is "Up" .2
..((sounds higher than written) or "Down" (sounds lower than written

You can also use the Change Instrument... button in the Staff Properties window to automatically change the transposition to that of a different standard instrument

External links

- ([How to transpose](#) ↗ (MuseScore How-To
- ([Concert pitch or not??](#) ↗ (forum discussion

Drum notation

Entering percussion notation is somewhat different to entering notation for pitched instruments (such as the piano or violin). However, it is recommended that you first read the chapter on Note input for pitched instruments before proceeding

Percussion staff types

When you create a percussion staff using the New Score Wizard or the Instruments dialog, MuseScore automatically chooses the most appropriate staff type (1-, 3-, or 5-line) for the instrument: this can be changed, if required, using the "Staff type" column on the Chose instruments / Instruments page. Any additional changes (e.g. to a 2-line staff) can be (made from the score itself (see Advanced Style Properties

On a 5-line percussion staff, each instrument is assigned a vertical staff position (line or space) and a notehead shape. For a drumset, one or two voices can be used. If the latter, **voice 1** (the upper voice) usually contains (up-stem) notes played by the hands while **voice 2** (the lower voice) usually contains (down-stem) notes played by the feet (see image (below



Note input methods

You can add notes to a percussion staff from any of the following

- External MIDI keyboard
- (Piano keyboard (virtual
- Computer keyboard
- Mouse

:These methods can be used in any desired combination

MIDI keyboard

:To add notes to a percussion staff from a **MIDI keyboard**

.Ensure that the MIDI keyboard is connected and functioning correctly .1

Note: If you click on the percussion staff without entering note input mode, you can *demo* the percussion instruments from the MIDI keyboard

.Click on the note or rest where you want to start .2

.Enter note input mode .3

Select the correct voice. For example, snares, sidesticks and all cymbals are normally added to voice 1; bass drum .4
.to voice 2

.Set note duration .5

Press an instrument key to add a note to the score. To add another note at the same position, keep the first key held .6
.down while pressing the second key

Note: Refer to a **GM2 drum map** for details about which MIDI keyboard key corresponds to which percussion instrument.
.Some keyboards (e.g., Casio) display percussion symbols next to the keys as an aid to the user

Piano keyboard

:To add notes to a percussion staff from the virtual **Piano Keyboard**

.(Ensure that the Piano keyboard is displayed. Press P (or select it from the menu, View → Piano Keyboard .1

Note: If you click on the percussion staff without entering note input mode, you can *demo* the percussion instruments from the Piano keyboard

.Click on the note or rest where you want to start .2

.Enter note input mode .3

Select the correct voice. For example, snares, sidesticks and all cymbals are normally added to voice 1; bass drum .4
.to voice 2

.Set note duration .5

.Click on a (virtual piano) key to add a note to the score .6

To add another note to an existing one, press Shift and hold it while pressing the new note (in versions before 2.1, .7
.(use Ctrl (Mac: Cmd

Note: Refer to a **GM2 drum map** for details about which piano key corresponds to which percussion instrument

By default, the piano keyboard is docked at the bottom of the screen—to the left of the Drum input palette. However you
:can undock it by dragging, then dock the panel in several ways

Drag the panel downwards to the center and it will overlay the Drum input palette, full length. Both panels can then •
.be accessed by Tabs
.Drag the panel downwards to the right/left and it will dock to the right/left of the Drum input palette •

Computer keyboard

:To enter notes on a percussion staff using your computer keyboard

.Click on the note or rest where you want to start .1

.(Enter note input mode. The Drum input palette now appears at the bottom of the screen (see below .2

.Select the desired note duration .3

.Press the shortcut key (A–G) for the instrument that you wish to enter—refer to the Drum input palette window .4

.[If you wish to add another note to an existing one in that voice, press Shift + [A–G .5

Note: Voice allocation is determined by the color of the note in the drum input palette: blue for voice 1, green for voice 2

Mouse

To add a note to a percussion staff

.Use the following method to add a *new* note or to replace an *existing* chord

- .1 .Select the note or rest where you want to start. You can also select a measure .1
- .2 .(Press N to to enter note input mode. The Drum input palette now appears at the bottom of the screen (see below) .2
- .3 .Set note duration .3
- .4 .:Chose one of the following options .4
- .Double-click a note in the Drum input palette ◦
- .Select a note (e.g. Bass drum, or Snare) in the Drum input palette, then click a note or rest in the score ◦

To add a note to an existing chord in the percussion staff

- .1 .Ensure you are in note input mode .1
- .2 .Select a note duration equal to the note you are adding to .2
- .3 .Click on the new note in the Drum input palette .3
- .4 .Click above or below the existing note in the percussion staff .4

Note: Voice allocation is determined by the color of the note in the drum input palette: blue for voice 1, green for voice 2

Drum input palette

When a percussion staff is selected and note input mode is ON, a window opens at the bottom of the screen called the **Drum input palette**. This window is *essential* for mouse input, and displays shortcuts for computer keyboard input, but can be ignored if using a MIDI keyboard or the virtual Piano Keyboard

Each note in the palette represents a percussion instrument: hovering the mouse pointer over the note displays the instrument name



The letters A–G (shown above certain notes in the palette) are designated as shortcuts for entering particular instruments (bass drum, snare, closed hi-hat etc.), rather than referring to note pitches. They can be changed or reallocated as desired in the Edit Drumset window


When the **Drum input palette** is open, double-clicking a note in the palette or entering a shortcut letter will add that instrument note to the percussion staff. The color of the note in the palette shows the voice allocated for that note—blue for voice 1, green for voice 2. This can be changed in the Edit Drumset dialog if required

This voice allocation applies only to keyboard and mouse entry of notes: entry via a MIDI keyboard or the virtual Piano keyboard allows any voice to be used

Edit Drumset

:To open the **Edit Drumset** window, use one of the following options

- .Click on the Edit Drumset button at the left of the **Drum input palette** •
- ."...Right-click on a percussion staff and select "Edit Drumset" •



The **Edit Drumset** dialog displays the percussion instruments available and the MIDI notes/numbers to which they are allocated. It also determines how each instrument is displayed on the staff— its name, position, notehead type and note-stem direction. *Any changes made here are automatically saved in the parent MuseScore file*

:Clicking on a row in the left-hand column allows you to edit the display properties for that note as follows

.Name: The name you want displayed in the Drum input palette when you mouse over the note

Notehead: Chose a notehead for that instrument from a drop-down list of options (if set to "Invalid," the instrument will not display in the Drum input palette)

Staff line: This number indicates the staff line/space on which the note is displayed. "0" means that the note is displayed on the top line of the 5-line staff. Negative numbers move the note upwards step by step, while positive numbers move it downwards in the same way

.Stem Direction: Auto, Up or down

.Default voice: Assign to one of four voices. This does not affect input from a MIDI keyboard or the virtual Piano keyboard

.Shortcut: Assign a keyboard shortcut to enter that note

The customized drumset can be saved as a .drm file by pressing **Save**. You can also import a customized drumset using the **Load** button

Note: In MuseScore 2.1, some of the pitches in the Tenor Drums instrument do not play back; there is a DRM file designed to fix this, which you can download [here](#) , via right-click → Save target as

Roll

.To create a drum roll, use Tremolo

External links

- [\[How to create jazz drum notation\]](#)  [MuseScore How-To •
- [Video tutorial: MuseScore in Minutes: Lesson 7 - Tablature and Drum Notation\]](#)  •
- [\[Drum Parts\]](#)  [video •
- [\[Editing the Drum Palette in MuseScore 1.1\]](#)  [video •
- [\[Saving Drumset Changes in MuseScore 1.1\]](#)  [video •
- [Guide to Drum and Percussion Notation\]](#)  •

Tablature

Music for fretted, stringed instruments is commonly notated using **tablature**, also known as **tab**, which provides a visual representation of the strings and fret numbers



Tablature can also be combined with traditional staff notation



Create a new tablature staff

If you wish to create tablature as part of a new score, use the [New Score Wizard](#). If you want to add tablature to an existing score, use the [Instruments](#) dialog. Or, alternatively, you can [convert an existing standard staff](#). See below for details.

With the New Score wizard

(To create tablature in a new score (for combined staff/tablature systems see [below](#))


1. Open the [New Score wizard](#)

2. Enter the score details (optional). Click [Next](#)

3. On the **Chose template file** page, click on [Choose Instruments](#)

4. On the **Instruments** page, select one (or more) tablature options under "Plucked strings" in the left-hand column

(see image below). Then click [Add](#)



Note: You can use the dropdown list above the Instrument list to change the category displayed. Alternately you can search for the instrument using the "Search" field below the Instrument list

5. Complete the rest of the New Score Wizard

:If the desired tablature is not available in the **Choose Instrument** list

- .At step "4" (above), select an existing "Plucked strings" tablature staff .1
- .Press Add to move it to the right-hand column .2
- .Check the drop-down menu to the right of the newly-added instrument for the most suitable Tab option, if any .3
- .Complete the rest of the New Score wizard and exit .4
- .(Modify the number of strings and tuning of the tablature, if needed, in the **Staff properties** window (see → [below](#) .5
- .Change the Instrument name in Staff Properties, if required .6

.This allows you to create tablature for any chromatically-fretted instrument

With the Instruments dialog

:(To add a single tablature staff to an existing score (for combined staff/tab system see → [below](#)

- .(...Open the **instruments** dialog (press I; or from the menu bar, select Edit → Instruments .1
- .(Add the tab staff as described in [Add instruments](#) ("Create a new score .2

By changing staff type

:To convert an existing standard staff to tablature, or tablature to a standard staff

- Right click on the staff and select **Staff Properties**.... If "Instrument" is already set to a plucked-strings type, then exit .1
- .staff properties and go to step 4 .2
- If "Instrument" is not a plucked-strings type, click on **Change instrument** and select an appropriate instrument from .2
- ."Plucked strings
- .Click on OK twice to exit staff properties .3
- .(...Open the **instruments** dialog (press I, or from the menu bar select Edit → Instruments .4
- .Click on the staff in the right-hand column and change the "Staff type" to the desired option .5
- .Click OK to exit the Instrument editor and return to the score page .6

Note: If you subsequently need to make further adjustments to the staff (e.g. tuning, number of lines/strings etc.), right
....click on the staff and select **Staff Properties**

:(Alternative method (using just the "Staff Properties" dialog

-Right click on the staff and select **Staff Properties** .1
- .If the Instrument displayed *is* in the "Plucked strings" category, go to step 4 .2
- If the Instrument displayed is *not* in the "Plucked strings" category, click **Change instrument** and select an appropriate .3
- instrument from "Plucked strings". Click on OK
- .Click **Advanced Style Properties**..., change "Template" to the desired option and press < Reset to Template .4
- ..Click OK twice to close the **Staff Properties** dialog box .5


Note: Other adjustments to the staff (e.g. tuning, number of lines/strings etc.), can also be made in the **Staff Properties**...
..dialog

Edit string data


Change tuning

.*Note:* If you only want to **view** (rather than change) the instrument tuning, follow steps 1 and 2 only

-Right-click on the staff and select **Staff Properties** .1



:Press the Edit String Data... button at the bottom of the dialog box. The **String Data** dialog opens .2



.Click on a string pitch and select Edit String.... Or, alternatively, just double-click the string pitch .3

.Select a new pitch in the **Note Selection** box and click OK. Or, alternatively, just double-click the new pitch .4

.Click OK to close the **"String Data"** dialog box. Then click OK to close the **"Staff/Part Edit Properties"** dialog box .5

Notes: (1) If tuning is changed when the tablature for that instrument already contains some notes, fret marks will be adjusted automatically (if possible); (2) Any change of tuning to a particular instrument applies *only* to the score at hand, and does not change any program default settings

Add a string

.Right-click on the staff, select Staff Properties..., then press Edit String Data .1

....Click on a string pitch and select New String .2

Select the new pitch and press OK—or, alternatively, just double-click the new pitch. The new string is inserted .3
.below the selected string

.Note: After adding a tablature string you will need to adjust the number of lines in the **Staff properties** dialog

Delete a string

.Right-click on the staff, select Staff Properties..., then press Edit String Data .1

.Click on a string pitch and select Delete String .2

.Note: After deleting a tablature string you will need to adjust the number of lines in the **Staff properties** dialog

"Mark unfretted string "open

This feature is used to mark a (bass) course as unstopped (i.e. outside of the fingerboard and always sounding open): as on a Baroque lute or Theorbo etc. This means that only "0" (zero) or "a" is accepted as a fret mark: any other fret mark will .be converted to 0/a

- .Right-click on the staff, select Staff Properties..., then press Edit String Data .1
- .Check one or more boxes in the "Open" column .2

Change number of instrument frets

.This property defines the maximum fret number which can be entered on a tablature staff

- .Right-click on the staff, select Staff Properties..., then press Edit String Data .1
- .Select or enter a new number in the **Number of frets** spin box .2

Change tablature display

You can customize both the appearance of a tablature staff and the way that it displays the fret marks. To access these :options

- ...Right click on the staff and select Staff Properties .1
- .Click on the Advanced Style Properties... button .2

Combine pitched staff with tablature

Plucked-string instruments—such as the guitar—are commonly notated using both a music staff and tablature (TAB) :together. MuseScore gives you the option of having the two staves either **unlinked** or **linked**

Unlinked Staves: You can enter, delete or edit notation in one staff without affecting the other. To transfer music .1
.notation from one staff to the other, select the desired range and copy and paste it into the other staff

Linked Staves: Any changes you make in one staff are automatically applied to the other staff as well ("mutual .2
."translation

A note on fret mark conflicts: When the same note is entered in two different voices, MuseScore tries to ensure that the fret marks do not overlap on the same string. Any overlaps which *do* occur are marked with red squares: these appear *only* in the document window and *not* on any printed copy. In almost all cases (e.g. frets 0 to 4 on the 6th string), overlapping is the desired result and no further adjustment is required. As of version 2.2, you can hide the red marks by ".selecting "View" and unticking "Show Unprintable

Create a staff/tablature pair with the New Score wizard

- .Open the New Score wizard .1
- .Enter the score details (optional). Click Next .2
- .On the **Chose template file** page, click on Choose Instruments .3
- .Select a pitched staff in the "Plucked strings" section of the left-hand column. Then click Add .4
- :Select the newly-created staff line (i.e. marked "Staff ...") in the right-hand column and chose one of two options .5
 - .Click Add Staff to create an **unlinked** staff/tab pair ◦
 - .Click Add Linked Staff to create a **linked** staff/tab pair ◦
- In the **Staff type** column, click on the dropdown list for the newly-created staff and select a tablature option (this can .6
(.be modified later, if required, on the score page—see Staff Properties
- .Complete the rest of the New Score Wizard, or click Finish .7

Note: To create unlinked staves with *separate* mixer channels, instead of step "5" (above), select a Tablature staff in the .left-hand column and click Add. Then continue with steps 6 and 7

Create a staff/tablature pair in an existing score

- (...Open the **Instruments** editor (press I, or from the menu bar, select Edit → Instruments .1
- .Select a pitched staff in the "Plucked strings" section of the left-hand column. Then click Add .2
- :Select the newly-created staff line (i.e. marked "Staff ...") in the right-hand column and chose one of two options .3
 - .Click Add Staff to create an **unlinked** staff/tab pair ◦
 - .Click Add Linked Staff to create a **linked** staff/tab pair ◦
- In the **Staff type** column, click on the dropdown list for the newly-created staff and select a tablature option (this can .4
(.be modified later, if required, on the score page—see Staff Properties

- .Change the staff order using the ↑ button if needed .5
- .Click OK to return to the score .6

Note: To create unlinked staves with *separate* mixer channels, instead of step "3" (above), select a Tablature staff in the left-hand column and click Add. Then continue with steps 4–6

Create a staff/tablature pair from an existing staff

:(To add tablature to a plucked-string staff in the score (or vice versa

- .(...Open the **Instruments** editor (press I, or from the menu bar, select Edit → Instruments .1
- .Select the staff line (marked "Staff 1") in the right-hand column that you want to add to .2
- :Chose one of two options .3

Click Add Staff to create an **unlinked** staff/tab pair ◦

Click Add Linked Staff to create a **linked** staff/tab pair ◦

In the **Staff type** column, click on the dropdown list for the newly-created staff and select an option (this can be .4

.(modified later, if required, on the score page—see [Staff Properties](#)

.Change the staff order using the ↑ button if needed .5

.Click OK .6

Notes: To create unlinked staves with *separate* mixer channels, instead of step "3" (above), select an appropriate staff in the left-hand column and click Add. Then continue with steps 4–6

Enter notes in tablature

Using a computer keyboard

First, ensure that you are not in note-input mode. Select the measure or existing note from which you want to begin •
 .note entry

.Switch to note input mode (N): a short 'blue rectangle' appears around one tablature string: this is the *current string* •
 .(Select the duration of the note or rest that you wish to enter (see [below](#) •

Press the up/down arrow keys to move the cursor to the desired string. Use the left/right arrow keys to navigate •
 .through the score

Press 0 to 9 to enter a fret mark from 0 to 9 on the current string; to enter numbers with several digits press each •
 digit in sequence. Keys A to K (skipping I) can also be used: convenient when working in French tablature. For L, M,
 ...N, use the alphanumeric keyboard and type respectively 10, 11, 12

.Note: You cannot enter a number higher than the "Number of frets" value set in the [Edit String Data](#) dialog

.Press ; (semicolon) to enter a rest of the selected duration •

.You can enter notes in different [voices](#) if required—just as you would in a standard staff •

.(See also, [Edit notes](#) (below

Historical tablature

:As of version 2.1, period notation for bass strings (lutes and sim.) is supported

French tablature: letters with prefixed slash-like strokes right under the tab body: i.e. 7th string: "a", 8th string: "/a", •
 .9th string: "//a" and so on, all in the first position below the tab body

Italian tablature: numbers with 'ledger line'- like segment of string above the tab body: i.e. 7th string: "0" one •
 position above the tab body with one 'ledger line'; 8th string: "0" two positions above the tab body with two 'ledger
 .lines' and so on

Input of is via computer keyboard only: by moving the note entry cursor below (French) or above (Italian) the tab body,
 'shadow' slashes or ledger lines will indicate the target string to which the fret mark will be applied; pressing one of the fret
 .keys, will enter (and lay out) the note on that string

Using a mouse

:To enter notes into tablature with a mouse

- (Enter note input mode and select the note or rest duration (see below
- Click on a string to create a note there. Notes are initially created on fret 0 (ora for French tablatures): to correct,
- .type in the right number from the keyboard
- .+You can also increase/decrease the fret mark using Alt+Shift+↑ or Alt+Shift
- .You can enter notes in different voices if required—just as you would in a standard staff

.(See also, Edit notes (below

Select note duration

:In note input mode, you can use any of the following methods to set note duration in tablature

Press Shift+1 to Shift+9: Sets duration from a 128th note to a longa (availability of these shortcuts may depend on the •
;(platform and/or keyboard layout

Press NumPad 1 to Numpad 9: Sets duration from a 128th note to a longa (if a numeric keypad exists and NumLock is •
;(on

;Click on a note duration icon in the Note Input toolbar above the document window •
.Press Q to decrease the selected duration and W to increase it •

Edit notes

Note input mode

:To edit an existing fret mark in **note-input mode**

- .Position the cursor above the fret mark and simply retype the number
- .+Increment or decrement the fret mark using Alt+Shift+↑ Or Alt+Shift

Non note input mode

:To edit an existing fret mark *outside* **note-input mode**

.Select one or more fret marks .1

:Use any of the following commands .2

.↓ / ↑ To increment or decrement, without changing the string: Press ○

↓ / ↑+To increment or decrement, changing strings, when possible, to minimize the fret number: Press Alt+Shift ○

. (↓ / ↑+To move to an adjacent string (if the string is free and can produce that note): Press Ctrl+↑ / ↓ (Mac: Cmd ○

.Note: The fret mark cannot be higher than the "Number of frets" value set in the Edit String Data dialog

Crosshead notes

:To change a fret mark to a crosshead note

.(Select one or more fret marks (in non-note-input mode .1

.Press Shift+X to toggles ghost noteheads on/off .2

Summary of keyboard commands

Note input mode

:to get	:Type
.Select above string as current	↑
.Select below string as current	↓
Select a duration (128th note to a longa)	Shift+1 to Shift+9
Select a duration (128th note to a longa)	NumPad 1 to NumPad 9
.Decrease current input duration	Q
.Increase current input duration	W
.Enter a fret digit / letter	to 9 0
.(Enter a fret digit / letter (excluded	A to K

.Increase current fret mark	:Type Alt+Shift
.Decrease current fret mark	↓+Alt+Shift
Enter a rest	(semicolon) ;

Normal mode

:to get	:Type
(Change <u>duration</u> of selected note or rest (128th note to longa	to 9 0
).(Increase the pitch of the selected note (MuseScore chooses the string	↑+Alt+Shift
.Increase the pitch without changing string	↑
Decrease the pitch of the selected note (MuseScore chooses the	↓+Alt+Shift
).(string	
.Decrease the pitch without changing string	↓
.Move note to above string, keeping the pitch (↑+Ctrl+↑ (Mac: Cmd	
.Move note to below string, keeping the pitch (↓+Ctrl+↓ (Mac: Cmd	
.Toggle the ghost notehead on/off	Shift+X

External links

[Video tutorial: MuseScore in Minutes: Lesson 7 - Tablature and Drum Notation](#) ↗ •

Sound and playback

MuseScore has "Sound and playback" capabilities built-in. This chapter covers the playback controls and ways to extend the instrument sounds.

Mid-staff instrument changes

When a musician is required to double on a different instrument for a section of a piece, the instruction to switch instruments is generally placed above the staff at the beginning of that section. A return to the primary instrument is handled in the same manner.

MuseScore enables users to insert a special class of text called **Change Instrument** text for this purpose. This class of text is different from either **Staff** or **System** text in that it links the text to the playback and changes the sound to the new instrument.

Instrument changes as of version 2.1

Version 2.1 introduces a greatly improved mid-staff instrument change over previous versions. There are still some limitations that need to be considered prior to using it.

Mid-staff instrument changes are limited to the same type of staff. For example, you cannot change between a percussion staff and a pitched instrument staff or vice versa.

The instrument name is not changed in the mixer. It will still be listed under the instrument in the original definition of the staff.

The key signature is not automatically updated at the instrument change. You must manually change the Key signature if needed.

You can now enter the notes a musician would play once the instrument is changed and the correct key signature is entered if necessary.

.Unless you are changing the type of staff, you will always use the **Change Instrument** text .5

Instrument changes in version 2.0

.There are several limitations to this in version 2.0 which should be understood before attempting to use it

Automatic transposition from concert pitch to the appropriate key for the transposing brass and woodwind instruments is not currently supported. For changes to instruments notated in a different key (C flute to E \flat flute;

Oboe to English Horn, etc.), the use of ordinary **Staff Text** to indicate the change is preferable, and the transposition must be done after the music is entered (using **Notes** → **Transpose** from the main menu). To avoid discord on playback, the instrument assigned to that staff should be muted in the F10 Mixer

If it is necessary to hear the new instrument sound on playback, the **Change Instrument** text function must be used. .2

However, after a mid-staff instrument change where the two instruments on the staff are not notated in the same key, *no attempt should be made to enter new music directly from the keyboard*. Instead, the music must be (a) pasted in, or (b) entered *before* the instrument change is affected. New input into measures following an instrument change is subject to two known program bugs, which cannot be resolved in the current 2.0.x versions without adversely affecting backwards compatibility. (This has been fixed in [version 2.1](#)) In addition, the score must remain notated in concert pitch, or discord will result from the transposition. As a convenience to the players, a copy of the part may be saved as a separate file and the required sections transposed to the appropriate key before the part is (.printed. (Note that transposing a linked part will affect the score as well

When changing from one concert-pitch instrument to another, or from one transposing instrument to another in the same key (Bb trumpet to Bb cornet or Flugelhorn, etc.), the **Change Instrument Text** may be used to ensure that the playback sound is altered to the new instrument. Input may be done in the usual manner, and is not affected by the bugs mentioned above .3

Incompatibilities


.There are some incompatibilities between the two versions

Instrument changes created with version 2.0 and opened in version 2.1 or above will continue to either display the notes wrong or play the notes wrongs as in version 2.0. Deleting and reentering the instrument change will fix most incompatibility issues with only minor changes being needed .1


Instrument changes created with version 2.1 or above and opened in version 2.0 will generally playback correctly .2
.but continue to display the wrong notes

Add an instrument change


- .1 .Select the start point of the change by clicking on a note or rest
- .2 .Open the main palette by typing F9 (or by using the **View** menu), and click on **Text** to open the text sub-palette



- .3 Double-click on **Instrument**
- .4 .The word "Instrument" will appear above the anchor note or rest
- .5 .Double-click the word "Instrument", then type **Ctrl+A** to select all of it
- .6 .Type the actual text you wish to appear in the score, then click outside the box to exit text edit mode
- .7 "...Right-click the text and choose **"Change Instrument**



Choose the instrument, then click OK .8



See also

- [Change instrument](#)
- [Mid-staff sound change](#)

External links


- [How to change instrument sound \(e.g. pizz., con sordino\) midway through score](#)

Mixer

.The Mixer allows you to change instrument sounds and adjust the volume and panning for each staff

:To display/hide the mixer, use one of the following

- .(Press F10 (Mac: fn+F10
- .From the main menu, select View → Mixer



Note: Separate reverb and chorus effects for *each* channel are not yet implemented; use the [synthesizereffects](#) unit instead.

.The name of each mixer channel is the same as the **Part name** in the [Staff properties](#) dialog

- To **silence** a selected staff, tick its "Mute" checkbox. Repeat as required
- To **solo** a selected staff, tick the "Solo" checkbox for that staff

Dials

To turn a dial clockwise, click and drag upwards. To turn a dial counter-clockwise, click and drag downwards. You can also hover the mouse pointer over the dial and then move the mouse wheel. Double-clicking on any dial restores it to its default position.

Sound

The "Sound" drop-down menu lists every instrument supported by your current SoundFont. If you have multiple SoundFonts loaded in the Synthesizer, all the patches from all the SoundFonts (and/or SFZ files) will appear in a single long list—in the order previously set in the Synthesizer.

Tip: To find an instrument, click on the "Sound" list and type the first letter of the instrument name. Repeat as required.


(.Mid-staff sound change (pizz., con sordino, etc

Some instruments come with multiple channels in the Mixer that can be used to change sounds midway through a score.

For example, a staff for a stringed instrument (violin, viola, cello etc.) is allocated *three* channels: one for "arco" (or "normal"), another for "pizzicato" and another for "tremolo." A trumpet staff will have one channel for "normal" and another reserved for "mute," and so on.

The following instructions use pizzicato strings as an example, but the same principle can be applied to any other instrument staff that allows sound changes.

1. Select the first note of the section you want to be pizzicato.
2. From the main menu, choose Add → Text → Staff Text.
3. Type "pizz." This text is for visual reference only and does not affect playback.
4. Right-click on the applied staff text and select Staff Text Properties.
5. In the "Change Channel" tab of the "Staff Text Properties" dialog, select one or more voices on the left.
6. From the dropdown menu, select pizzicato.



Click OK to return to the score .7

Every note after the staff text you added now sounds pizzicato. To return to a normal strings sound later in the piece, follow the same guidelines as above except type "arco" in step 3 and select normal in step 6.

See also

- [SoundFont](#)
- [Synthesizer](#)
- [Change instrument](#)

External links

Play mode

:Basic playback functions are accessed from the **Play toolbar** located above the document window



:From left to right, the icons are

- **(Rewind to start position:** Playback returns to the beginning of the score, or to the start of the loop (if one is set
- **.Start or stop playback:** See [Start/stop playback](#)
- **.Toggle loop playback:** See [Loop playback](#)
- **.Play repeats:** Turn off if you want playback to ignore repeats
- **.Pan score during playback:** Turn off if you want the score to remain stationary
- **.Play metronome:** See [Metronome playback](#)

Playback commands

Start/stop playback

:To start playback

Click on a note, rest or the blank part of a measure to establish the starting point **Note:** If no selection is made, .1
. playback returns to the place it left off—or, if no previous playback, to the start of the score

.2 Press the play button  button; or press Space

.During playback you can jump to a specific note or rest in the score by simply clicking on it

:To stop playback

• Press the **Playback** button; or press Space

During playback

:Once playback has started, the following commands are available


- ← :Go back to previous chord
- → :Advance to next chord
- (←+Go back to start of previous measure:Ctrl+← (Mac: Cmd
- (→+Advance to start of next measure:Ctrl+→ (Mac: Cmd
- .(Rewind to start of score:Home (Mac: ⌘+Home); or press the **Rewind** button (playback toolbar

.During playback you can still use [keyboard shortcuts](#) to open and close [panels](#), such as Play, Synthesizer, Mixer etc

Play panel

:To open the Play Panel use one of the following options

- .(Press F11 (Mac: Fn+F11
- .From the menu bar, select View → Play Panel



The Play Panel offers temporary controls over playback, including playback speed (labelled 'tempo'), loop playback (with specified starting and ending positions), and general volume

Note: Changes to the parameters in the Play Panel *are not* saved with the score: they only affect playback in the *current* session. Permanent changes to **tempo** should be made using [tempo text](#). To change the default **playback volume** of the score, see [Synthesizer](#)

Count in

You can switch on and off a count-in to be played each time the playback starts. The count-in plays beats for a full measure (according to nominal time signature at playback starting point); if the starting point is mid-measure or at a 'short' measure (anacrusis), it also plays enough beats to fill that measure. The conductor icon in the play panel enables, or disables count-in

Metronome playback

You can also switch on/off the accompanying metronome as the score is played (see the metronome icon on the play panel)

Loop playback

You can loop playback of a selected passage in the score using either the **Play toolbar** (see image above) or the [play panel](#)

:To loop from the Play toolbar

- Playback should be **off**, and the "Loop playback button" **on**
- [Select](#) the desired region of the score for loop playback
- Press the playback button
- Playback will now cycle within the region marked by the blue flags
- Use the "Loop playback" button to toggle the loop on or off

:To loop from the Play Panel

- Select the note from which you want playback to start and click on the "Set loop in position" button. The "Loop Playback" button becomes active
- Select the last note of the desired playback region and click on the "Set loop out position" button
- Press the play button
- Playback will now cycle within the region marked by the blue flags
- You can use the "Loop playback" button to toggle the loop on or off

SoundFonts and SFZ files

Audio playback is provided by MuseScore's onboard [synthesizer](#), which houses a large selection of **virtual** (or **software**) **instruments**—including percussion and sound effects

MuseScore supports virtual instruments in two formats

- **.SoundFont (.sf2/.sf3):** A single file containing one or more virtual instruments
- **.SFZ (.sfz):** A set of audio and definition files containing one or more virtual instruments

SoundFonts

A Soundfont (.sf2/.sf3) is a single file containing one or more virtual instruments. As of version 2.2, MuseScore is installed with a SoundFont called **MuseScore_General.sf3**. This is a GM ([General MIDI](#) ) set containing over 128 instruments, .sound effects and various drum/percussion kits

Note: Older versions of MuseScore are installed with a different Soundfont: MuseScore 2.0–2.1 with **.FluidR3Mono_GM.sf3**; MuseScore 1 with **TimGM6mb.sf2**

GM (General MIDI) is a universal format, so once your score is set up for correct playback using MuseScore's native .Soundfont, you should be able to export it in a format of your choice and have it play back on any other user's computer

Many different Soundfonts are available on the Internet: some free, some commercial. For a list of free soundfonts, see [below](#)

Install a SoundFont

After finding and decompressing a SoundFont (see [below](#)), double-click to open it. In most cases, the SoundFont file type will already be associated with MuseScore, and MuseScore will start and a dialog will appear asking if you want to install the SoundFont. Occasionally an application other than MuseScore will be associated with the SoundFont file type; if this is the case, you will need to right-click or control-click on the file, so as to display a menu from which you can choose to open the file in MuseScore. In either case, when the dialog appears asking if you want to install the SoundFont, click "Yes" to place a copy of the SoundFont file in MuseScore's SoundFonts directory. This directory can be viewed or :changed in MuseScore's Preferences, but the default location is

Windows: %HOMEPATH%\Documents\MuseScore2\Soundfonts •

macOS and Linux: ~/Documents/MuseScore2/Soundfonts •

In contrast to user-added SoundFonts, the initial default SoundFont installed with MuseScore is located in a system :directory, meant only for that purpose, which should *not* be modified. This directory and its default SoundFont file is

Windows (32-bit): %ProgramFiles%\MuseScore 2\sound\MuseScore_General.sf3 •

Windows (64-bit): %ProgramFiles(x86)%\MuseScore 2\sound\MuseScore_General.sf3 •

macOS: /Applications/MuseScore 2.app/Contents/Resources/sound/MuseScore_General.sf3 •

(Linux (Ubuntu): /usr/share/mscore-xxx/sounds/MuseScore_General.sf3 (with xxx being the MuseScore version •

Uninstall

.To uninstall a SoundFont, simply open the folder where its file is installed and delete it

SFZ

An SFZ consists of a bunch of files and directories, an SFZ file and a bunch of actual sound files in WAV or FLAC format, with the SFZ file being a text file that basically describes what sound file is located where and to be used for what .instrument and pitch range

Note: For full support of SFZ, MuseScore 2.1 or later is need, prior versions had only limited support, namely for Salamander Grand Piano

Install an SFZ


After downloading an SFZ (see [below](#)), you need to manually extract all the files that belong to the SFZ (the SFZ file .itself and all the subdirectories) into the directory listed [above](#). Leave the subdirectories and their contents as they are

Uninstall

.To uninstall an SFZ, simply open the folder where its files are installed (see[above](#)) and delete them all

The **Synthesizer** is MuseScore's central control panel for sound output. Once a SoundFont has been installed, it needs to be loaded into the Synthesizer in order for MuseScore to use it for playback. To make a different SoundFont the default, load it in the Synthesizer and click Set as Default.

To display the Synthesizer, go to View → Synthesizer. For more details, see Synthesizer



List of downloadable soundfiles

GM SoundFonts

The following sound libraries conform to the General MIDI (GM2) standard. This specification gives you a sound set of 128 virtual instruments, plus percussion kits

- [\(GeneralUser GS ↗\)](#) (29.8 MB uncompressed)
Courtesy of [S. Christian Collins ↗](#)
- [\(Magic Sound Font, version 2.0 ↗\)](#) (67.8 MB uncompressed)
- [\(Arachno SoundFont, version 1.0 ↗\)](#) (148MB uncompressed)
Courtesy of [Maxime Abbey ↗](#)
- (MuseScore 1 came with [TimGM6mb ↗](#)) (5.7 MB uncompressed)
License: GNU GPL, version 2
Courtesy of [Tim Brechbill ↗](#)
- [\(MuseScore 2 \(up to version 2.1\) comes with FluidR3Mono_GM.sf3 ↗\)](#) (13.8 MB)
- [\(MuseScore 2 \(as of version 2.2\) comes with MuseScore_General.sf3 ↗\)](#) (35.9 MB) [\(SF2 version ↗\)](#) (208 MB)
License: released under the [MIT license ↗](#)
Courtesy of [S. Christian Collins ↗](#)
- [\(Timbres of Heaven, version 3.2 ↗\)](#) (369 MB uncompressed)
Courtesy of Don Allen

Orchestral soundfiles

- (Sonatina Symphonic Orchestra (503 MB uncompressed)
Downloads: [SoundFont ↗](#) | [SFZ format ↗](#)
License: Creative Commons Sampling Plus 1.0
[Aegean Symphonic Orchestra ↗](#)
- (Courtesy of [Ziya Mete Demircan ↗](#)) (352 MB uncompressed)

Piano soundfiles

SF2 Pianos

- [Acoustic grand piano, release 2016-08-04 ↗](#)

Description: Yamaha Disklavier Pro Grand Piano, sf2 format, 36MiB compressed, 113MiB uncompressed, 121 samples, 5 velocity layers

.More information: <http://freepats.zenvoid.org/> including other soundfonts

License: Creative Commons Attribution 3.0

Courtesy of [Roberto Gordo Saez](#)

[Salamander C5 Light](#)

(Courtesy of [Ziya Mete Demircan](#) (24.5 MB uncompressed)

SFZ Pianos

[Salamander Grand Piano](#)

Downloads: [version 2](#) | [version 3](#)

Description: Yamaha C5, 48kHz, 24bit, 16 velocity layers, between 80 MB and 1.9 GB uncompressed

License: Creative Commons Attribution 3.0

Courtesy of Alexander Holm

([Detuned Piano](#)) (244 MB uncompressed)

License: Creative Commons Attribution-ShareAlike 3.0

[Plucked Piano Strings](#)

Description: 44.1kHz, 16bit, stereo, 168 MB uncompressed

License: Creative Commons Attribution-ShareAlike 3.0

[The City Piano](#)

Description: Baldwin Baby Grand, 4 velocity layers, 696 MB uncompressed

License: Public domain

Courtesy of Big Cat Instruments

[Kawai Upright Piano, release 2017-01-28](#)

Description: 68 samples, 44kHz, 24bit, stereo, 2 velocity layers, 58MiB uncompressed

License: GNU General Public License version 3 or later, with a [special exception](#)

Courtesy of Gonzalo and Roberto

Unzipping downloaded soundfiles

Since soundfiles are large, they are often zipped (compressed) into a variety of formats, including .zip, .sfArk, and .tar.gz.

.You need to unzip (decompress) these files before they can be used

.ZIP is standard compression format supported by most operating systems

sfArk is a compression format designed especially for compressing SoundFont files. To decompress it, use

[Polyphone](#) (cross-platform software); or this online service: <https://cloudconvert.com/sfark-to-sf2>

tar.gz is a popular compression format for Linux. Windows users can use [7-Zip](#); Mac users can use [The Unarchiver](#), or macOS' built-in Archive Utility. Note that if using 7-Zip, you will need to apply decompression twice—

.once for GZip and once for TAR

Troubleshooting

:If the toolbar play panel is greyed out, or not visible, follow the instructions below to get your sound working again

Right-click on the menu bar and make sure there is a check mark next to the Playback Controls menu item. If this step .1

.does not solve your problem, go to Step 2

If the play panel disappears after changing the SoundFont, go to Edit → Preferences... → I/O tab and click OK without .2

.making any changes. After restarting MuseScore, the play panel should reappear

.If you are setting up a SoundFont for the first time, please use one of the recommended SoundFonts listed above

If playback stutters, then your computer may not be able to handle the SoundFont being used. The following advice may

:help

Reduce the amount of RAM (memory) used by MuseScore by using a smaller SoundFont. See the [list](#) above for

.suggestions

Increase the amount of RAM available for MuseScore by quitting all applications except MuseScore. If you still have

.problems and a large SoundFont is important to you, consider more RAM for your computer

See also

- [Synthesizer](#)
- [Mixer](#)

External links

- [How to change the SoundFont or add another](#)
- [\(The SFZ Format](#) (for details about the sfz specification


Swing

MuseScore's **swing** feature allows you to change the playback of your score from a straight to a swing rhythm. Swing can be applied globally or only to a section of the score, and is fully variable

Apply swing to a score section

1. Click on the note where you want swing to start

2. Double-click **Swing** in the Text palette (shown below)



3. Edit the Swing text as required

4. If you need to vary swing from the default setting, right click the Swing text and select System text properties... Click on the "Swing Settings" tab and adjust note duration and "Swing ratio" as required

Swing text can be edited just like any other text element: you can change it, style it, make it invisible etc

Triplet in tempo marking

Often this notation is used to indicate swing



MuseScore does not have a way to include a triplet in text as a tempo marking, but there is an easy workaround

1. Add Swing text as described above and make it invisible (shortcut v, or untick "Visible" in the Inspector)
2. Add an appropriate Image of the required tempo marking to the score. This can be downloaded from the bottom of the "How To" page: [How to create a visual swing marking](#)
3. Resize and reposition the image as required

Return to straight rhythm

If you want playback to return to straight time after a swing section

1. Add **Swing** text to the first note or rest of the "straight" section (see above)
2. Edit the text to indicate a return to straight time: e.g. "Straight"
3. Right-click on the text and select System Text Properties.... Click on the "Swing Settings" tab and set "Swing to "Off"

Apply swing globally

If you wish to apply swing to the whole score, you can do so from the menu

1. Select Style → General... → Score
2. In the "Swing Settings" section, set the desired note value and "swing ratio"

External links

- [How to create a visual swing marking](#)

Synthesizer

Overview

.To display the **Synthesizer**: from the menu, select View → Synthesizer

:The Synthesizer controls MuseScore's sound output and allows you to

- Load and organize different sound sample libraries to play back the music
- Apply effects such as reverb and compression
- Adjust overall tuning
- .Alter the output volume of both music and the (optional) metronome

:The Synthesizer window is divided into four sections/tabs

- **.Fluid**: A software synthesizer that plays SF2/SF3 SoundFont sample libraries
- **.Zerberus**: A software synthesizer that plays SFZ format sample libraries
- **.Master Effects**: Used to apply multi-effects to the score
- **.Tuning**: Used to adjust overall playback tuning

Save/Load Synthesizer settings


:The buttons at the bottom of the Synthesizer window have the following functions


Function	Button
Saves <i>all</i> current synthesizer settings as the <i>default</i> settings. These are automatically applied to the Synthesizer when you open MuseScore	Set as Default
.Loads the last saved <i>default</i> settings to the Synthesizer	Load Default
.Saves <i>all</i> current synthesizer settings to the <i>current</i> score only	Save to Score
.Loads the settings from the <i>current</i> score to the synthesizer	Load from Score

Notes: (1) "Synthesizer settings" include the order of Soundfonts and SFX files, the effects configuration, master tuning and volume. (2) Only one set of Synthesizer settings can be in effect at a time—i.e. if multiple scores are open at once, it is not possible to make changes to the Synthesizer in one score and leave other scores' settings untouched. (3) Changes to synthesizer settings will not be heard in exported audio files unless saved to the score first (see table, above). See also (Tuning (below

Fluid

Click on the **Fluid** tab to access the control panel for SF2/SF3 SoundFont sample libraries. By default, the SoundFont .FluidR3Mono_GM.sf3 should already be loaded





You can load, rearrange and delete soundfonts as required. Playback can be shared between any combination of different .soundfonts (and/or SFZ files). The order of soundfonts in **Fluid** is reflected in the *default* order of instruments in the mixer

To load a soundfont

- Click on the Add button .1
- .Click on a soundfont in the list .2

To be able to load the soundfont, it first needs to be installed in your **Soundfonts folder**. This will ensure that it appears in .(the list in step 2 (above

To reorder the soundfonts

- Click on a soundfont .1
- .Use the up/down arrows (on the right-hand side) to adjust the order .2
- .Repeat with other soundfonts in the list if required .3

If you have not changed any sounds in the Mixer, then the SoundFont at the top of the list is the one that will be used for playback. However, if you are using the Mixer to play different instruments with sounds from different SoundFonts, playback will only work correctly if you have the same SoundFonts loaded *in the same order* in the Synthesizer. Therefore, if you are using multiple SoundFonts, it is advised to click the Save to Score button in the Synthesizer, so that the next time you open that score you can recall the list of SoundFonts loaded (and other Synthesizer settings) with the Load .from Score button

To remove a soundfont

- Click on the name of the soundfont .1
- .Click on the Delete button .2


This removes the soundfont from the synthesizer but does not uninstall it from the Soundfonts folder: it will still be .available if you wish to reload it later

Zerberus

Click on the **Zerberus** tab to access the control panel for SFZ sound sample libraries. You can add or delete files in a similar way to the Fluid tab. Note that, as with Fluid, the the SFZ files must first be installed in your **soundfonts** folder .before they can be loaded into the synthesizer

Volume

At the right in the Synthesizer are two sliders. One controls the playback volume, the other controls the volume of the optional built-in metronome. You can turn the metronome on or off by clicking the button underneath its volume slider. As with all the rest of the Synthesizer controls, any changes made here are temporary unless saved to the score or set as the .new default



Effects

The **Master Effects** tab of the Synthesizer allows you to adjust the degree of reverb and, as of version 2.0.3, compression applied to your score.



.To turn an effect on or off

.(Select an option from the drop-down list next to **Effect A** or **Effect B** (the effects are applied in series, A → B •

To store and load effects configurations, use the buttons at the bottom of the Synthesizer window. See Synthesizer settings (above) for details

Zita 1 reverb

The **Zita 1** stereo reverb module allows you to simulate the ambience of anything from a small room to a large hall. The :pre-delay, reverb time and tone of the reverb can be finely tuned using the controls provided

- **.Delay:** Set a pre-delay for the reverb from 20-100 ms
- **Low RT60** (Low frequency reverb time): Use the grey control to adjust the center frequency (50–1000 Hz) of the low frequency band which you want to affect: the green control adjusts the reverb time (1–8 secs) of this frequency band
- **.Mid RT60** (Mid-range reverb time): Adjust the reverb time (1–8 secs) of the mid-range frequency band
- **HF Damping:** Adjusts the high frequency component of the reverb. Increasing this value increases the frequency of the cut-off point and makes the reverb appear brighter and longer
- **EQ1:** Allows you to cut or boost (-15 to +15) a frequency band (center = 40 Hz - 2 KHz) in the *lower* part of the spectrum
- **EQ2:** Allows you to cut or boost (-15 to +15) a frequency band (center = 160 Hz - 10 KHz) in the *higher* part of the spectrum
- **Output:** Controls the amount of effect applied. "Dry" is no effect. "Wet" indicates 100% reverb. "Mix" is a 50/50

.balance of wet/dry signal

Note: EQ1 and EQ2 affect the tone of the reverb only, *not* the dry (unprocessed) signal

To quickly set up an effects patch, set "Output" to "Mix" and adjust the "Mid RT60" control to the desired reverb time. Then fine tune the effect as explained above

SC4 compressor

The **SC4** stereo compressor (available as of version 2.0.3) gives you fine control over the playback's dynamic range, reducing the volume variation between loud and soft sounds. It offers the following controls

- RMS:** Adjusts the balance between RMS (0) and Peak (1) compression. In the former, the compressor responds to averaged-out levels in the signal; in Peak mode, the compressor responds to peak levels
- Attack:** (1.5–400 ms) The length of time it takes for compression to engage fully after the signal exceeds the threshold level
- Release:** (2–800 ms) The time it takes for compression to return to zero after the signal falls below the threshold level
- Threshold:** (in dB) The signal level above which compression starts to take effect. Lowering the threshold increases the amount of signal that is compressed
- Ratio:** The amount of compression applied to the signal above the threshold. The higher the ratio, the greater the compression. Varies between 1:1 to 20:1
- Knee:** Allows you to select a range between "soft knee" and "hard knee". The softer the knee, the more gradual the transition between uncompressed and compressed signal
- Gain:** Compression tends to lower the volume, so use this control to boost the signal as required

To quickly set-up, try setting RMS = 1, Threshold = -20 db, Ratio = 6. Increase Gain to restore the lost volume. Then fine-tune as explained above

Tuning

The **Tuning** tab is where you can adjust the program's **master tuning**. For Concert Pitch instruments, A4 = 440 Hz by default



:To change the Master tuning

- .Enter a new value in the **Master tuning** field, then press Change Tuning

Notes: (1) This tuning applies to all scores in the *current* session only. To make this the program default or to store it to a

particular score, see [Save/Load Synthesizer settings](#). (2) To apply the new tuning to exported audio files (WAV, MP3, .OGG), press **Save to Score** before exporting

See also

- [SoundFont](#) •
- [Mixer](#) •

Tempo

Tempo markings can be found in the [Tempo palette](#) of the Basic and Advanced [workspaces](#). They are supplied as metronome marks, but can be subsequently edited to display any tempo or expression you want. Playback tempo can be varied throughout the score by using multiple tempo markings, visible or invisible

Add a tempo marking

:Use any of the following methods

- .Select a note or rest and press the **keyboard shortcut** **Alt+T** •
- .Select a note or rest, and from the **menu bar** chose **Add → Text... → Tempo Marking** •
- ;**Select a note or rest and double-click an appropriate metronome mark in the [Tempo palette](#)** •
- .**Drag-and-drop a metronome mark from the [Tempo palette](#) directly onto a note or rest** •

Note: If a tempo marking is applied from the menu or using a keyboard shortcut, the beat note automatically follows the .time signature. The advantage of applying from a palette is that *you* can chose which beat note to use


Edit tempo

:To change the tempo of an existing metronome mark in the score

- .1 Enter [Edit mode](#) for the tempo mark in question
- .2 Edit the metronome number and/or the beat note as required
- .3 Exit Edit mode

:You can also override the tempo of an existing metronome mark from the [Inspector](#)

- .1 Select the tempo mark
- .2 Untick "Follow text" in the "Tempo Marking" section of the [Inspector](#)



- .3 Set the desired playback tempo in the "Tempo" field underneath

Note: Playback may be faster or slower if the tempo setting in the [play panel](#) is at a percentage other than 100%

Edit tempo text

Tempo marks can be [edited](#) and formatted just like any other [text](#) object. To set text properties or text style, see [Text styles and properties](#)


The tempo indicated by a metronome mark usually persists even if overwritten by an expression—such as *Andante*, *Moderato* etc. You can also *add* further text to a plain metronome mark. e.g

Andante ♩ = 75

Overriding the tempo marking

You can temporarily override the indicated tempo, and play the score back at any tempo you like using the [play panel](#)

(Display the play panel: View → Play Panel or F11 (Mac: fn+F11) .1



Move the tempo slider up or down as required. The tempo is shown both as an absolute value and as a percentage .2
of the currently indicated tempo mark. Double-click the tempo slider to reset it

Note: BPM is always measured and displayed in quarter note beats per minute, regardless of the (denominator of the)
time signature in effect

Ritardando and accelerando playback

You can simulate **ritardando** ("*rit.*") and **accelerando** ("*accel.*") playback by adding hidden tempo markings to the score.
The printed indication to the musician should be added as [staff/system text](#) in addition

In the example illustrated below, the tempo was originally 110 BPM (beats per minute). At the ritardando, the tempo decreases by 10 BPM on the first note of each measure. Each tempo change is made invisible by unchecking the **Visible**
checkbox in the [Inspector](#), so that only the ritardando shows on the printed score



A [plugin](#) has been developed to automate this process: [TempoChanges](#) ↗

Fermatas

Fermatas, available in the [Articulations and Ornaments](#) palette, have a **Time stretch** property that can be set via the [Inspector](#). By default, this property is set to 1.00. To have MuseScore play back a fermata for twice its normal duration, click on the fermata and set "Time stretch" to 2.00. This of course does not work for [fermatas applied to barlines](#), as barlines don't have a duration to stretch

See also

- [Play mode](#) •
- [Time signature](#) •

Dynamics

Dynamics are symbols indicating the loudness of a note or phrase of music. Symbols can be found in the [Dynamics palette](#) in either the Basic or [Advanced workspace](#)

<i>ppp</i>	<i>pp</i>	<i>p</i>	<i>mp</i>
<i>mf</i>	<i>f</i>	<i>ff</i>	<i>fff</i>
<i>fp</i>	<i>sf</i>	<i>sfz</i>	<i>fff</i>
<i>ffz</i>	<i>fp</i>	<i>fpz</i>	<i>rfz</i>
<i>rf</i>	<i>fz</i>	<i>m</i>	<i>r</i>
<i>s</i>	<i>z</i>	<i>n</i>	

Note: Overall playback volume of the score can be changed using the volume slider in the [Play Panel](#) or [Synthesizer](#)

Add a dynamic

To apply a dynamic to the score, use one of the following methods

- Select a note and double-click a dynamic symbol in a palette
- Drag a dynamic symbol from a palette onto a note

For additional dynamics use the Master Palette (Shift+F9). You can also create a [custom palette](#) [↗](#) for future use

To create a crescendo or decrescendo sign, see [Hairpin](#)

Adjusting playback volume for a dynamic

Click on the dynamic to select it, and adjust its **Velocity** in the [Inspector](#)—higher for louder, lower for softer

Adjusting range for a dynamic

Via the [Inspector](#) you can set the staves affected by a dynamic. The "Dynamic range" is by default set to "part," which means all staves for an instrument will be affected. Changing this to "staff" will limit the dynamic to the staff it is entered on only. Changing this to "System" will cause all instruments to play this dynamic

List of dynamics in palettes

In the Basic [workspace](#), there are 8 options in the Dynamics palette: *ppp*, *pp*, *p*, *mp*, *mf*, *f*, *ff*, *fff*

In the Advanced workspace, there are all of the above plus 15 additional options in the Dynamics palette: *fp*, *sf*, *sfz*, *fff*, *.sffz*, *sfp*, *sfpp*, *rfz*, *rf*, *fz*, *m*, *r*, *s*, *z*, *n*

In the Dynamics section of the [Master Palette](#), there are all of the above plus 6 additional options: *pppppp*, *ppppp*, *pppp*, *.ffff*, *fffff*, *ffffff*

Edit a dynamic

Any dynamic can be edited after being added to the score, just like standard text. See [Text editing](#)

See also

- [Tempo](#)

External links

- [Video tutorial: Lesson 10 - Articulations, Dynamics and Text](#) [↗](#)
- [Dynamics](#) [↗](#) at Wikipedia

Text

There are many different kinds of text objects in MuseScore (see tables below); text may also be found incorporated into [lines](#). This chapter shows you how to create, format and edit text objects, and also includes information about the following types of text

Uses

General purpose text attached to a single staff: appearing only in that instrument

Text type

Uses	Text type
.General purpose text attached to a single staff: appearing in all instrument parts	System text
.Display the chords associated with a melody: usually above the staff	Chord symbols
.Numbers or letters attached to notes showing which fingers to use	Fingering
.Create lyrics attached to a melody	Lyrics
.Facilitate rehearsals, divide score into sections, bookmark passages etc	Rehearsal marks

:For other types of text available in MuseScore, follow the links below

Uses	Text type
.Apply metronome and/or expression marks	Tempo marks
.Indicate the loudness of a note or phrase	Dynamics
.Change from straight to swing time, and vice versa	Swing text
.Apply mid-staff instrument changes	Instrument text
.Da Capo, Dal segno, Fine etc	Repeats and jumps
.Period notation for keyboardists	Figured bass
Title/composer/lyricist details at the start of a score; songsheet lyrics etc	Frame text
.Page numbers, copyright info etc. at the top/bottom of a page	Headers/Footers
.Voltas, ottavas, pedal lines, guitar barre lines etc	Text-lines

Text basics

Add text

:To add a text-based element to the score, use one of the following general methods

.Keyboard shortcut: For example, press Ctrl+T to enter [Staff text](#), Ctrl+L to enter [Lyrics](#), and so on •

.Menu command: Add → Text allows you to choose from a range of text-based elements •

Workspace: Select a note and double-click an icon in one of the palettes; or, alternatively, drag a symbol from a palette onto the staff. e.g. [Swing text](#), [Tempo text](#) etc •

Notes: (1) The exact method depends on the type of text you are adding (see [Text](#)). (2) For general-purpose **text boxes** attached to staves, see [Staff and system text](#)

Format text

:Every text-based element in the score has three levels of formatting

Text style: This is the highest level of formatting and applies to *all* text elements in the score of a *particular* type. For details, see [Text style](#) •

.Text properties: This applies to the style of *one* specific text object only. For details, see [Text properties](#) •

.Character formatting; The style applied to individual text characters during editing. For details, see [Text editing](#) •

Adjust position of text objects

:To position a text object, use any of the following methods

- Drag the object
- Select the object and adjust the horizontal or vertical offset values in the [Inspector](#)
- Select the object and apply any of the following keyboard shortcuts
 - .Move text left 0.1 staff space : ←
 - .Move text right 0.1 staff space : →
 - .Move text up 0.1 staff space : ↑
 - .Move text down 0.1 staff space : ↓
 - .Ctrl+← (Mac: ⌘+←): Move text left one staff space
 - .Ctrl+→ (Mac: ⌘+→): Move text right one staff space
 - .Ctrl+↑ (Mac: ⌘+↑): Move text up one staff space
 - .Ctrl+↓ (Mac: ⌘+↓): Moves text down one staff space

Text anchors

:When you apply a text element to the score, its anchor position will depend on the type


- **.Title, Subtitle, Composer, Poet:** Anchored to a frame
- **.Fingering:** Anchored to note heads
- **.Lyrics:** Anchored to a time position (a note/chord, but not a rest)
- **.Chord symbol:** Anchored to a time position
- **.Staff text:** Anchored to a time position
- **.System text:** Anchored to a time position

Text editing

Enter/exit text edit mode

:To enter **Text edit mode** use one of the following methods

- Double click on a text element
- Right-click on a text element and select Edit element
- (Click on a text element and press Ctrl+E (Mac: Cmd+E)



In this mode you can apply formatting to individual characters, including options such as **bold**, *italic*, underline, subscript, superscript, font family and font size. These are accessed from the **Text toolbar** below the document window



:To exit **Text edit mode** use one of the following

- Press Esc
- Click on a part of the score outside the edit window



Keyboard shortcuts

:In **Text edit mode**, the following keyboard shortcuts are available

- Ctrl+B (Mac: ⌘+B) toggles **bold face**
- Ctrl+I (Mac: ⌘+I) toggles *italic*
- Ctrl+U (Mac: ⌘+U) toggles underline
- Home End ← → ↑ ↓ moves cursor
- Backspace (Mac: Delete) removes character to the left of the cursor
- Del (Mac: → Delete or fn+Delete) removes character to the right of the cursor
- starts new line ↵
- (F2 (Mac: fn+F2) Inserts special characters (see below)

Symbols and special characters

You can use the **Special Characters** window to insert quarter notes, fractions, and many other kinds of special symbols (or characters into your text. A few symbols can also be accessed by shortcut (see below



:To open **Special Characters**, use any of the following methods

- (Click on the  icon in the text toolbar (below the score window
- (Press F2 (Mac: fn+F2)

Note: (1) This only works in Text edit mode; (2) The Special Characters dialog should not be confused with the menu item of the same name in the macOS version of MuseScore

The dialog is divided into 3 tabs: Common symbols, musical symbols and unicode symbols. The musical and unicode tabs are further subdivided into alphabetically-arranged categories

Double-clicking an item in the Special Characters dialog immediately adds it to the text where the cursor is positioned. Multiple items can be applied without closing the dialog box, and the user can even continue to type normally, delete characters, enter numerical character codes etc., with it open

Special character shortcuts

In **Text edit mode** the following keyboard shortcuts can be used to access certain special characters

- .Ctrl+Shift+B: Flat
- .Ctrl+Shift+F: Forte
- .Ctrl+Shift+H: Natural
- .Ctrl+Shift+M: Mezzo
- .Ctrl+Shift+N: Niente
- .(Ctrl+Shift+P: Piano (dynamic mark
- .Ctrl+Shift+R: Rinforzando
- .Ctrl+Shift+S: Sforzando
- .Ctrl+Shift+Z: Z
- .Ctrl+Shift+#: Sharp

See also

- [Chord symbol](#) •
- [Lyrics](#) •
- [Frame](#) •
- [Edit mode](#) •

Text styles and properties

Text Style


This is the highest level of text formatting and applies to *all* text elements in the score of a *particular* type. Staff text objects, for example, have a unique style, as do all tempo markings, all lyrics, all chord symbols and so on. Editing a text *.style* allows you to change the appearance of *all* objects which share that style *in one go*


Edit style

To edit a text style, use any of the following methods

- .From the main menu, chose *Style* → *Text...* Then select the relevant style from the list •
-Right-click a text object and select *Text Style* •

This will display the **Edit Text Styles** dialog





:The options available are divided into categories

- Text •
 - **Font:** name of the font such as "Times New Roman" or "Arial" ○
 - **Size:** size of the font in points ○
 - **Style:** style of the font, italic, bold, underline ○
 - **Color:** click on the color demonstrated to change ○
 - **Size follows "Staff space"** setting: whether size follows the distance between two lines in a 5-lines standard staff ○
 - **System flag:** text applies to all staves of a system ○
- Offset •
 - **Horizontal** ○
 - **Vertical** ○
 - **Offset Unit:** in mm or Staff space units ○
- Alignment •
 - **Horizontal:** left, right, center ○
 - **Vertical:** align top edge of text to reference point, center text vertical to reference point, center text vertical to text baseline or align bottom edge of text to reference point ○
- Frame •
 - **Frame:** add a frame around the text ○
 - **Frame Type:** Circle or Box ○
 - **Border thickness:** thickness of the line of the frame in space units ○
 - **Border radius:** for box frame, radius of rounded corner ○
 - **Text margin :** inner frame margin in space units ○
 - **Foreground color:** of the frame border ○
 - **Background color:** of the background within the frame ○

Note: Opacity is set by the parameter "Alpha channel" in the colors dialogs: a value between 0, transparent, and 255, .opaque

Create a new text style

- 1 ;...From the menu bar, select Style → Text...; or right-click on a text object and select Text Style
- 2 ; Click on New
- 3 ;Set a name
- 4 .Set all properties as desired

This text style will be saved along with the score. It will not be available in other scores, unless you explicitly save the style sheet and load it with another score

You can apply any changes made to either the score or the part you are seeing, by pressing Apply and then OK. If you are in one of the parts of your score, you also have the option to use the Apply to all parts button before OK, so you don't have to manipulate all parts individually.

Reset text to style

If you have made changes to an individual piece of text and you want to return it to the defined text style for the score, or if you changed the style with an old version of MuseScore and you want the style to correspond to the default text style in MuseScore 2, you can use the **Reset Text to Style** option.

Select the text you want to reset to style and click on Reset Text to Style in the Inspector. If you need all text from a given style to be "reset", right-click on one, then from the context menu choose Select → All Similar Elements first.

Save and load text styles

Text styles (together with all other styles in a document) can be saved as a style file and loaded into other MuseScore files. See [Save and load style](#).

Text Properties


This is the next level down in the formatting hierarchy and affects the style of the text in one specific text object only.

Edit properties

To edit the text properties of a particular object—and no other

- Right click on the text and select Text Properties

This displays the following dialog



Most of the properties on display will be familiar from the [Edit Text Styles](#) dialog. You also have a Reset to Style button allowing you to apply a style to the object from a drop-down list.

See also

- [Text editing](#)
- [Header/Footer](#)
- [Behavior of applied text and lines](#)

Staff and system text

For general-purpose text, use **Staff Text** or **System Text**. The difference between these two types of text is whether you want it to apply to a single staff, or the whole system. This matters when extracting parts: staff text will only appear in a part that contains the specific instrument the text is attached to, while system text will appear in all parts. Additionally, if you choose to hide empty staves, any staff text belonging to an empty staff will also be hidden. System text is never hidden by the "hide empty staves" feature.

Staff text

Staff text is general purpose text associated with a particular staff at a particular location in the score. To create staff text, choose a location by selecting a note or rest and then use the menu option Add → Text → Staff Text, or use the shortcut Ctrl+T (Mac: ⌘+T). A small text box appears and you can immediately start typing. You can exit the text box at any time (even without typing anything) by pressing Esc.

Staff text can, for example, be used to apply indications such as "Solo" or "Pizzicato" to one staff in a score. Depending on what the instructions of the staff text are, MIDI playback of that staff at the text location can be altered to match the instructions by right-clicking on the staff text and selecting Staff Text Properties.... See Mid-staff sound change.

System text

System text is used when you wish to apply text indications to a whole system rather than just to one staff line. This makes a difference when extracting parts, or if you choose to hide empty staves. To create system text, choose a location by selecting a note or rest and then use the menu option Add → Text → System Text, or use the shortcut Ctrl+Shift+T (Mac: ⌘+Shift+T). A small text box appears and you can immediately start typing. You can exit the text box at any time (even without typing anything) by pressing Esc.

See also


[Mid-staff sound change](#) •

External links

[How to change instrument sound \(e.g. pizz., con sordino\) midway through score](#) ↗ •

Chord symbols

Chord symbols are an abbreviated way of representing musical chords (see [Chord names and symbols](#) ↗ (Wikipedia) for further details). For example



Enter a chord symbol

- .1 Select a note or a slash
- .2 (Press Ctrl+K (Mac: ⌘+K)

The cursor is now positioned above the score ready for input. Enter the chord symbol just like normal text, as follows

- **Root note:** A, B, C, D, E, F, G
- **(Sharp:** # (hash symbol
- **(Flat:** b (small letter "b
- **(Double sharp:** x (small letter "x") or ## (two hash symbols
- **(Double flat:** bb (small letter "b" twice
- **(Natural:** natural (no space before "natural
- (For other symbols, see [Chord symbol syntax](#) (below

When you exit the chord symbol, the characters you have typed will automatically assume the correct format: by default a **root note** typed in lower case will turn into upper case (for alternative options, see [Automatic Capitalization](#)); a "#" or "b" will turn into a proper sharp (#) or flat (b) and so on. Do not try to use actual flat and sharp signs as MuseScore will not

.understand those properly

:After you have finished entering a chord symbol you can either

- (Move the cursor forward or backwards to continue entering or editing chord symbols (see [commands](#) below
- .Exit chord symbol mode by pressing Esc

Note: To fill measures with slashes, see [Fill with slashes](#) or [Toggle rhythmic slash notation](#)

Keyboard Commands

:The following commands are available during chord symbol entry

- Space move Cursor to next note, rest, or beat
- Shift+Space move cursor to previous note, rest, or beat
- Ctrl+Space (Mac: ⌘+Space) add a space to the chord name
- move cursor to next beat ;
- move cursor to previous beat :
- Tab move cursor to next measure
- Shift+Tab move cursor to previous measure
- (Ctrl plus number (1 - 9) move Cursor by duration corresponding to number (e.g.; half note for 6
- .Esc exit

Chord symbol syntax

:MuseScore understands most of the abbreviations used in chord symbols

- (**Major:** M, Ma, Maj, ma, maj, Δ (typed or ^ for the triangle
- - ,**Minor:** m, mi, min
- (**Diminished:** dim, ° (entered with lowercase letter o, shows as ° if using the [Jazz style](#), as o otherwise
- .**Half-diminished:** ø (type 0, zero). Alternatively, you can, of course, chose abbreviations such as mi7b5 etc
- + ,**Augmented:** aug

The following abbreviations are also valid: *extensions* and *alterations* like b9 or #5, sus, alt, and no3; *inversions* and *slash chords*, such as C7/E; *commas*; *parentheses*, which can enclose part, or even all, of a chord symbol

Edit a chord symbol

.An existing chord symbol can be edited in a similar way to ordinary text: See [Text editing](#)

Transpose chord symbols

Chord symbols are automatically transposed by default if you apply the menu [Transpose](#) command to the containing .measures. If this is not required, you can untick the "Transpose chord symbols" option in the same dialog

Chord symbol text

:To adjust the appearance of *all chord symbol* text, use any of the following options

- From the main menu, chose Style → Text... → Chord Symbol
- ...Right click on any chord symbol and select Text Style

.This displays the [Edit Text Styles](#) dialog, allowing you to make changes to any text property


Chord symbol style

Formatting options for **chord symbols** are available in Style → General... → [Chord Symbols](#), [Fretboard Diagrams](#). Adjustable properties are listed under the following headings

Appearance

.Three options are possible: **Standard** and **Jazz** and **Custom**. You can select between these using the radio buttons

- .In the **Standard** style, chords are rendered simply, with the font determined by your [chord symbol text](#) style



In the **Jazz** style, the MuseJazz font is used for a handwritten look, with distinctive superscript and other formatting characteristics. The Jazz style is selected by default if you use any of the Jazz templates



The **Custom** style option allows you to customise the look of chord symbols (and also ensures compatibility with older scores). Select a customised **Chord symbols style file** in the field below: this can be created by copying and modifying one of the pre-existing files in the "styles" folder. Documentation can be found in the same folder. Note, however, that this is for advanced users only, and there is no guarantee these files will be supported in the future

Note spelling

By default, MuseScore uses letter names for chord symbols. For users in regions where other note naming schemes are used, MuseScore provides the following controls

- ...,#**Standard**: A, B_b, B, C, C
- ...,#**German**: A, B_b, H, C, C
- ...,**Full German**: A, B, H, C, Cis
- ...,**Solfeggio**: Do, Do#, Re_b, Re
- ...,**French**: Do, Do#, Ré_b, Ré

Automatic Capitalization

By default, MuseScore automatically capitalizes all note names on exit, regardless of whether you entered them in upper or lower case. However, you can also choose other automatic capitalization options

- ...,**Lower case minor chords**: c, cm, cm7
- ...,**Lower case bass notes**: C/e
- ...,**All caps note names**: DO, RE, MI

You can also turn off the automatic capitalization completely, in which case note names are simply rendered the way you type them

Positioning

Default vertical position: The height at which the chord symbol is applied *above* the staff (negative values can be used)

Distance to fretboard diagram: If a fretboard diagram is present, this value is the height at which the chord symbol (is applied *above* the diagram (negative values can be used)

Minimum chord spacing: The space to leave between chord symbols

Maximum barline distance: Changes the size of the gap between the last chord symbol in the measure and the following barline. You only need to adjust this value if there is a continuous problem in the score with overlap between the last symbol in one measure and the first symbol in the next

Note: In addition to the settings described here, the default position of applied chord symbols is also determined by settings in the [Text Styles](#) dialog. The effect is cumulative

Capo

Enter the number of the capo position at which you want to display substitute chords, in brackets, after all chord symbols in the score

Fingering

Fingering symbols for various instruments are found in the [Fingering palette](#) in the Advanced workspace

0	1	2	3	4	5
p	i	m	a	c	0
1	2	3	4	5	0
1	2	3	4	5	6
φ		·	

Keyboard music employs the numbers 1–5 to represent fingers of the left or right hand. There is also [a fingering !\[\]\(2ff6e28e83bf5bb93ee3bf3d1e233c1e_img.jpg\) •](#) [. positioner plugin](#) to help you optimize the layout of piano or keyboard fingerings

Guitar music uses the numbers 0–4 to represent left-hand fingering (T is occasionally used for the thumb). Right-hand fingering is indicated by the letters p, i, m, a, c. Circled numbers represent instrument strings

The last five symbols in the palette are used for **lute** fingering in historical music. **Note:** To enable display of fingering in tablature, right-click on the TAB, select Staff Properties... → Advanced style properties, and tick "Show .Fingerings"

Add fingering to a single note

:Use any of the following methods

- .Select a note and double click one of the fingering symbols in a Palette
- Drag and drop a fingering symbol from a palette onto a note

.When fingering is added to a note, the focus immediately shifts to the symbol, so you can adjust it right away

Add fingering to several notes

- .1 [:Select](#) the desired notes
- .2 Double-click a fingering symbol in a palette

Adjust position of fingering

Single fingering

:To change the position of *one* symbol, use any of the following methods

- .For fine adjustments (0.1 sp) use the arrow keys; For larger adjustments (1 sp) use `Ctrl+Arrow`
- .Change horizontal and vertical offsets in the [Inspector](#) 
- .Drag the symbol using your mouse

Multiple fingering

:To change the position of multiple symbols

- .1 [:Select](#) the desired fingering symbols
- .2 Adjust using the horizontal and vertical offset fields in the [Inspector](#) 

Note: You can also use the [fingering positioner](#)  plugin mentioned above to optimize the layout of piano fingerings

.To restore a symbol to its default position, select it and press `Ctrl+R`

Edit fingering text

Fingering is a form of text symbol and can be [edited](#) and styled like any other. Right-clicking on the symbol gives you a .range of options

Lyrics

Enter a lyrics line

First line

- .1 ;Enter the notes of the melody line
- .2 ;Select the note where you want to start entering lyrics
- .3 ;To enter **lyrics mode**, type Ctrl+L (Mac: ⌘+L); or from the main menu, select Add → Text → Lyrics
- .4 ;Type a syllable
- .5 ;Use the following options to continue entering lyrics
 - **.Go to the next syllable:** Press Space (or Ctrl+→) at the end of a syllable
 - **.Hyphen** (to connect syllables): Press - at the end of a syllable
 - **.(-+Go to the previous syllable:** Press Shift+Space (or Ctrl+←)
 - **.Move left:** Press ← (left arrow). If the cursor is at the beginning of a syllable, it will jump to the previous one
 - **.Move right:** Press → (right arrow). If the cursor is at the end of a syllable, it will jump to the next one
 - **.Move to the syllable below:** Press ↓ (down arrow)
 - **.Move to the syllable above:** Press ↑ (up arrow)
- **Start new lyrics line:** Press ↵ (Return) at the end of an existing lyrics syllable (Note: Don't use the Enter key from the numeric keypad)
- .6 .To exit **lyrics mode**, press Esc

Subsequent lines

:(.If you want to add another lyrics line to an existing one (e.g. a 2nd or 3rd verse etc

- .1 :Chose one of the following options
 - Select the note where you want to start the new lyrics line. Enter **lyrics mode** as shown in step 3 above). The cursor moves to a new (blank) line
 - Enter text edit mode on an existing syllable, go to the end of the syllable and press↵ (Return). The cursor moves to the next line
- .2 .(Continue entering lyrics from step 4 above

:Example

The image shows a musical score for a Latin hymn. It consists of two staves: a treble clef staff on top and a bass clef staff on the bottom. The key signature is two sharps (F# and C#) and the time signature is 4/4. The melody is written in the treble clef, and the bass line is in the bass clef. The lyrics are written below the treble staff, aligned with the notes. The lyrics are: "A - des - te, fi - del - es, Can - tet nunc hym - nos Er - go qui na - tus".


Special characters

In most cases, lyrics can be edited just like normal text. However, special keyboard shortcuts are required to enter the following characters

- **.Character space:** Ctrl+Space (Mac: ⌘+Space)
- **.-+hyphen):** Ctrl+- (Mac: ⌘+-) or AltGr -
- **.Line feed:** Ctrl+↵ (Mac: ⌘+Return) or Enter (from the numeric keypad)

Melisma

A **melisma** is a syllable or word that extends over two or more notes. It is indicated by an underline extending from the base of a syllable to the last note of the melisma. The underline is created by positioning the cursor at the end of a syllable and pressing Shift+_ : once for each note in the melisma. See the image below



:The above lyric was created in the following manner

- .1 .,Type the letters, soul .
- .2 .____+At the end of the word, pressShift
- .3 .Type the letters To, then press Esc

For non-last syllables to extend, just use additional dashes-, usually only one of them will show (more when the distance between the syllables is large enough), and the syllable will right-align to the first note, similar to last syllables that got .notated with a melisma, see above

Elision (Lyric) slur / Synalepha

:Two syllables under a note can be joined with an**elision slur**, also known as a "lyric slur" or "synalepha". For example




:"To create the example lyric text, starting with the syllable text "te


;Type te .1

;Click on the keyboard icon , or press F2 to open the Special Characters palette .2

:Use one of the following options .3

Double-click one of the three elision slurs in the "Common Symbols" tab: "Narrow elision", "Elision", or "Wide elision" (these can be found between the "C Clef" and the "p" dynamic—see image below





Double-click the elision slur found after the 7/8 fraction in the "Common Symbols" tab (next to last character in the image above). Depending on the font, add one or more spaces before/after the slur using Ctrl+Space (Mac: ⌘+Space).

Note: Not all fonts include the "undertie" character (U+203F ) "undertie", present in "Special Characters" mainly for compatibility with MuseScore 1.x scores). To find out which fonts on your computer support it, see ["fontlist" \(look for any font that shows a tie between "te" and "A" instead of a blank rectangle](#)

.Type A .4

Edit Lyrics

- .1 ;Enter text edit mode on an existing syllable
- .2 ;Use standard text editing commands to make changes
- .3 .Continue entering lyrics (see [above](#)); or exit **lyrics mode** by pressing Esc

Adjust position of lyrics

:The top and bottom margins and the line height of *all* lyric lines can be set globally

- .1 ;From the menu, select Style → General... → Page
- .2 Adjust the properties marked "Lyrics top margin," "Lyrics bottom margin" and "Lyrics line height" (see [General: Page](#))
- .3 .([Lyrics Margins](#))

:To adjust the position of a *particular* lyrics line

- .1 Select the lyrics line: i.e. right click on a word in the line, and (from the menu) choose Select → More...; then check the
- ;"relevant options, which should include "Same system"
- .2 .Adjust the Horizontal and Vertical offsets in the Inspector

Copy lyrics to clipboard

:(To copy *all* lyrics to the clipboard (as of version 2.0.3

- .From the menu bar, select Edit → Tools → Copy Lyrics to Clipboard

Paste lyrics from clipboard

:To copy and paste lyrics from a text file (say) into a score

- .1 .Enter the notes in the score to which the lyrics will be attached

- .Set up your lyrics in a text file, with appropriate spaces, hyphens, line-breaks etc .2
- .Copy the lyrics from the text-file into the clipboard .3
- .(Select the start note in MuseScore, and pressCtrl+L (Mac: Cmd+L) (step 3 under [Enter lyrics in a score](#) .4
- Repeatedly applying [paste](#) will enter successive words of the lyrics. You may need to enter melismas and make .5
- .other corrections as you go along

See also

- [Text](#) •
- [Chord symbol](#) •

External links

- [How to insert Lyrics](#)  •
- [How to move lyrics](#)  •
- [How to copy lyrics, or lyrics with rhythm](#)  •
- [How to add a block of text to a score](#)  •
- [Video tutorial: MuseScore in Minutes: Lesson 6 - Text, Lyrics and Chords](#)  •

Rehearsal marks

Rehearsal marks can be used in a number of ways

- .To identify specific points in a score to facilitate rehearsing •
- .As bookmarks in the score to which you can instantly navigate—using the[Find/Search](#) command •
- .To mark the various sections in the score •

Typically, **rehearsal marks** consist of one or more letters and/or numbers, and appear in sequence in the score—e.g. A, B, C..., or 1, 2, 3... etc. Alternatively, they may display measure numbers (usually larger than standard measure numbers, boldface and/or enclosed in boxes). Multi-measure rests are automatically broken before and after rehearsal marks.

Rehearsal marks can be added to the score (i) *automatically*—which ensures that they are named in sequence—or (ii) *manually*, allowing you to name them as you wish

Add a rehearsal mark

Manual Placement

:To create a rehearsal mark manually

- ;Click on a note (or rest) at the desired location .1
- :Select one of the following options .2
 - ;(Press Ctrl+M (Mac: Cmd+M) ◦
- ;From the menu, chose Add → Text → Rehearsal Mark ◦
- .Enter the desired text .3

Automatic placement

Add an alphanumeric rehearsal mark

:Use either of the following options

- .Click on a note (or rest) at the desired location, then double-click the [B1] rehearsal mark icon in the "Text palette" •
- .Drag and drop the rehearsal mark from the "Text" palette onto the score •

Notes: (1) By default, marks are added in the sequence, A, B, C etc. (2) To change the format of subsequently-added marks (to lower case letters, or numbers), edit the previous rehearsal mark accordingly. (3) Marks added between existing rehearsal marks append a number or letter to the previous mark: it is a good idea to apply the [Resequence](#) command afterwards (see below)

Add a measure-number rehearsal mark

Add the first rehearsal mark in the series as an alphabetical one; then [edit](#) it to read the *same* as the number of the .1

.Add subsequent marks as shown [above](#). They will automatically adopt the measure-number format .2 ;measure it is attached to

Automatically resequence rehearsal marks

MuseScore allows the user to automatically re-order a series of rehearsal marks if they have got out of sequence for any :reason. Use the following method

Before making a selection, you can, if desired, establish a new format for the rehearsal marks (lower/upper case, .1 .number, or measure number) by manually altering the first mark in the range accordingly

Select the range of measures you wish to apply the **Resequence** command to (if there is no selection then the .2 .(program assumes you wish to resequence all measures

.From the menu, select Edit → Tools → Resequence Rehearsal Marks .3

MuseScore automatically detects the sequence based on the *first rehearsal mark* in the selection—all rehearsal marks in :the selection are then altered accordingly. The following sequences are possible

.A, B, C etc •

.a, b, c etc •

.Numerical: 1, 2, 3 etc •

Numerical: according to measure numbers. This requires the number of the first mark in the series to be equal to the .number of the measure it is attached to •

Text style

Rehearsal marks are a variety of [system text](#), appearing both on the score and on every [part](#). By default, they are in a large bold font, and enclosed in frames with rounded corners. All aspects of their appearance can be changed globally via .the rehearsal mark [Text style](#)

Search for a rehearsal mark

.(See [Find](#) (Viewing and navigation

See also

[Text properties](#) •

External links

([Rehearsal Letter](#) [↗](#) (Wikipedia article •

Formatting

Layout and formatting

.Layout and formatting options for the score can be accessed mainly from the **Layout** and **Style** menus

Ways to affect layout

This section lists the *main* commands and dialogs affecting score layout. Other formatting options are covered in either .([Layout menu](#) or [Style menu](#) below (for text, see [Text styles and properties](#)

:From the [Layout](#) menu

.[Page Settings](#): Adjust the overall dimensions of your score such as page size, page margins, and scaling •

.[Increase Stretch/Decrease Stretch](#): Adjust the score spacing by stretching or squashing selected measures •

:From the [Style](#) menu

[Score Style](#): Set overall score details, such as music font, display of multi-measure rests, and whether to hide empty • .staves

.[Page Style](#): Adjust staff and system spacing, score and lyric margins etc •

.Measure Style: Set the measure spacing, which affects the number of measures per line •

.Sizes: Set the default size of "small" and grace notes, small staves and small clefs •

:Other commands

.Add/Remove line breaks: Set the number of measures per system •

Breaks and spacers: Apply line, page or section breaks. You can also add extra space between *particular* systems •
:or staves where needed

Layout menu

...Page Settings


.See Page settings

Reset

The **Reset** command restores all *selected* score elements to their default position. It also restores the default directions of
:note stems and beams. To apply

.Select the elements or the region of the score that you wish to reset. Or use **Ctrl+A** to select the whole score .1
:Press **Ctrl+R**; or from the menu select **Layout → Reset** .2

Increase Stretch/Decrease Stretch



:Increase or decrease the horizontal spacing of notes within selected measures. To apply

.Select a range of measures. Or use **Ctrl+A** to select the whole score .1
:Chose one of two options .2

:To **increase stretch** ◦

;(Use the shortcut } (right curly bracket) (Mac: **Ctrl+Alt+9** ■
;Or from the menu bar, select **Layout → Increase Stretch** ■

:To **decrease stretch** ◦

;(Use the shortcut { (left curly bracket) (Mac: **Ctrl+Alt+8** ■
:Or from the menu bar, select **Layout → Decrease Stretch** ■

.See also Measure Properties: Layout stretch. This allows you to set the stretch more precisely

Reset Stretch

:To reset stretch to the default spacing of 1

.Select a range of measures. Or use **Ctrl+A** to select the whole score .1
:From the menu, select **Layout → Reset Stretch** .2

Reset Beam Mode

:To restore beams to the mode defined in the local time signatures

.Select the section of the score you want to reset. If nothing is selected, the operation will apply to the whole score .1
:Select **Layout → Reset Beam Mode** .2

.See also [Beams](#)

Regroup Rhythms

As of version 2.1, this option corrects note [ties](#), durations and [beaming](#) so that they are grouped according to standard music notation practice. For example



Any notes that are tied and are the same length as a dotted note will be changed to the dotted note with two limitations. (i) Only the last note of a group of tied notes will have a single dot. Notes with more than one dot are not produced using this option. (ii) Dotted notes will not span from one group of beamed notes to another unless their duration is the same as all of the beam groups it covers. Any notes with more than one dot will be regrouped according to the above rules

.To apply


.Select the section of the score you want to reset. If nothing is selected, the operation will apply to the whole score .1
.Select Layout → Regroup Rhythms .2


Note: This is an experimental feature and there are known bugs. Articulations and ornaments are deleted and some pitches respelt. Ties across barlines may be lost on UNDO

Style menu

General: Score

.To open the **Score** dialog: from the menu, select Style → General... → Score





This dialog allows you to set global properties, such as the music font, display of multimeasure rests, whether or not to hide empty staves, "swing" playback etc

.Musical symbols font: Choice of display in Emmentaler, Bravura or Gonville fonts •

.Musical text font: Choice of display in Emmentaler, Bravura, Gonville or MuseJazz fonts •

Display in concert pitch: Tick this option to display the score at concert pitch. If unticked the score is displayed at written pitch •

.Create multimeasure rests: Tick to display multimeasure rests •

.Minimum number of empty measures: The default is 2 ◦

.Minimum width of measure: The default width is 4 sp ◦

Hide empty staves: This option saves space by hiding those staves in a system which consist of only empty measures. Used for *condensed scores* •

Don't hide empty staves in first system: Always display staves in first system even if they consist of empty measures •

.Display note values across measure bar: A feature useful for notating early music. See Unbarred notation •

Hide instrument name if there is only one instrument: You don't usually need to display the instrument name in this case •



.Swing setting: The default is off. Choice of swung eighth or sixteenth notes •

.Select swing ratio: The default setting is 60% ◦


See also, Swing

General: Page

.To open the **Page** dialog: from the menu, select Style → General... → Page



This dialog allows you to adjust the space above and below systems, staves, lyrics, and vertical frames; and between the .score and the top/bottom page margins. You can also control the display of key signatures, time signatures and clefs



Distance to page margins

- .Music top margin:** The distance between the top staff line of the first staff on the page and the top page margin •
- Music bottom margin:** The distance between the bottom staff line of the last staff on the page and the bottom page margin •

Distance between staves

- .(Staff distance:** The space between staves which are not part of a grand staff (see below) •
- Grand staff distance:** The space between staves that share the *same* instrument—such as the piano, organ, or those of a guitar staff/tab pair •

.(Note: To alter the space above one particular staff see Extra distance above staff (Staff properties)

Distance between systems

- .Min. system distance:** The minimum distance allowed between one system and the next •
- .Max. system distance:** The maximum distance allowed between one system and the next •

Lyrics Margins

- .(Lyrics top margin:** The height of the margin *above* the *top* lyrics line (in a system) •
- .(Lyrics bottom margin:** The height of the margin *underneath* the *bottom* lyrics line (in a system) •
- Lyrics line height:** The distance between lyrics line (in a system), expressed as a percentage of the line height associated with the lyrics text style •

Vertical frame margins

- .Vertical frame top margin:** The default margin height *above* a vertical frame •
- .Vertical frame bottom margin:** The default margin height *below* a vertical frame •

Last system fill threshold

- .If the last system is longer than this percentage of the page width, it gets stretched to fill that width •**

Clefs and key signatures

- Create clef for all systems:** Untick this box to prevent a clef from *automatically* displaying at the *start* of any system except the first •
- Create key signature for all systems:** Untick this box to prevent a key signature from *automatically* displaying at •


.the *start* of any system except the first


:Ticking the following boxes, allows the display of courtesy elements at the end of systems

- **Create courtesy time signatures**
- **Create courtesy key signatures**
- **Create courtesy clefs**

General: Header, Footer, Numbers

.Open from the menu: Style → General... → Header, Footer, Numbers





You can show the content of a score's meta tags (see [Score information](#)) or show page numbers in a header or footer for your score. To create a header or footer for a score with linked parts, make sure the main score is in the active tab. To create a header or footer for an individual part, that part needs to be the active tab



If you hover with your mouse over the Header or Footer text region, a list of macros will appear, showing their meaning, as well as the existing meta tags and their content

You can create different Headers and Footers for even and odd pages, such as putting page numbers on the right for odd-numbered pages and on the left for even-numbered pages

.You can also edit whether and how often measure numbers appear

General: System

.Open from the menu: Style → General... → System





:This dialog allows you to

- .Set the **distance** between system brackets or braces and the start barlines
- .Set the **width** of system brackets and braces

.See also [Brackets](#)

General: Measure

.Open from the menu: Style → General... → Barlines





- .Control whether to show barlines at the beginning of a staff or multiple staves
- **Scale barlines to staff size** affects "small" staves only. See [Barline adjustment possibilities](#) (external link) for

.details

.Control proportion of thickness and distance within double barlines, including repeat barlines •



General: Notes

.Open from the menu: Style → General... → Notes





This page can also be accessed direct from the score by right-clicking on any note and selecting "Style..." Here you can adjust the distance and thickness of note-related objects (stems, ledger lines, dots, accidentals). Changing these would .be unusual

.Open from the menu:Style → General... → Clefs



.You can choose between Serif and Standard clef for your tablature sheet

.Open from the menu:Style → General... → Arpeggios





:Here you can change the thickness, spacing and hook height of the following arpeggio and strum symbols



.Changes to these properties would be unusual



General: Beams

.Open from the menu: Style → General... → Beams





General: Slurs/Ties

.Open from the menu: Style → General... → Slurs/Ties



General: Sizes



.Open from the menu: Style → General... → Sizes



.Sets the proportional size of "small" and grace notes, as well as small staves and clefs. Changing this would be unusual

General: Hairpins, Volta, Ottava



.Open from the menu: Style → General... → Hairpins, Volta, Ottava



.The  button returns the setting to the original value



General: Pedal, Trill

.Open from the menu: Style → General... → Pedal, Trill



General: Chord Symbols, Fretboard Diagrams

.Open from the menu: Style → General... → Chord Symbols, Fretboard Diagrams



.This section allows you to adjust the format and positioning of chord symbols and Fretboard diagrams

.**Appearance**: Chose a default chord symbol style—Standard, Jazz or Custom

.**Note Spelling**: Chose the spelling convention for chord symbols and whether to use capital or small letters

:Positioning

Default vertical position: The default vertical distance in space units (sp.) between a newly-applied chord symbol •

.and the music staff. Negative values may be used

Distance to fretboard diagram: The distance (in sp. units) from a chord symbol to a fretboard diagram when both are applied to the same location on a staff. This value overrides the above "Default vertical position" setting. The user can choose to place a chord symbol below a fretboard diagram by entering a negative value

Minimum chord spacing: The minimum space to allow between chord symbols

Maximum barline distance: Increases the distance between the final chord symbol in a measure and the following barline. You may wish to adjust this value if there is a recurring problem in the score with overlap between the final chord symbol in one measure and the following chord symbol

Capo: Enter the number of the capo position at which you want to display substitute chords, in brackets, for all chord symbols in the score

Fretboard diagrams

Default vertical position: the distance in sp. units from a newly applied fretboard diagram to a staff. A negative value may be used

Scale: Increase or decrease the size of the fretboard diagram in the score


Fret offset number font size: Increase or decrease the size of a fret number displayed next to a diagram


Position Left/Right: Display fret number to the left or right of the fretboard diagram

Barre line thickness: Make barre lines in fretboard diagrams thicker or thinner

General: Figured Bass

.Open from the menu: Style → General... → Figured Bass







.Options about figured bass font, style and alignment
See also [Figured bass](#)

General: Articulations, Ornaments

.Open from the menu: Style → General... → Articulations, Ornaments







Position of articulation with respect to the notes and staves

General: Accidentals

.Open from the menu: Style → General... → Accidentals







Options about naturals at key signature changes

General: Tuplets

.Open from the menu: Style → General... → Tuplets





Apply and OK buttons

By pressing the Apply button you can see how the changes you have made in the dialogs affect the score without closing the window. Press OK to save your changes to the score and close the window.

Apply to all parts in one go

When in a part tab while changing layout and formatting, you can use the Apply to all Parts button to apply all changes (either in Layout → Page Settings... or Style → General...) to apply the new settings to all parts in just one click.

Save/Load style

It is easy to transfer a complete set of styles (all General Style settings, all text styles, and page settings) from one score to the other using the **Save/Load Style** functions.

To **save** a customized style

...Go to Style → Save Style .1

.Name and save the **style file** (the default folder is set in your Preferences). Styles are stored as *.mss files .2

Note: You can also define a preferred style for scores and parts in the Score section of MuseScore's Preferences

To **load** a customized style

...Go to Style → Load Style .1

.(Navigate to and select the Style file (.mss) and click Open (or double click on the file .2

.All existing styles in the score should update automatically

See also



- To edit spacing between notes •
- Upgrading from MuseScore 1.x, local relayout •

External links

- (Tutorial – How to create large-print stave notation (MSN) ↗ •

- (MuseScore in 10 Easy Steps: Part 10A Layout and Formatting (a video tutorial) [↗](#) •
- (MuseScore in 10 Easy Steps: Part 10B Layout and Formatting (a video tutorial) [↗](#) •

General style: Measure



.Style → General → Measure allows you to adjust the distance between various items within measures

Introduction

If you change a **measure style** property (see image above), MuseScore automatically adjusts the score to maintain the correct spacing between notes and rests according to best music engraving practice. It will also correctly reposition any *.elements* attached to notes or rests, such as fingerings, dynamics, lines etc

All settings related to measure width and note spacing are *minimum* values. Measures are automatically stretched, if

.necessary, to maintain existing [page margins](#)

All the properties listed below use the **staff space** (abbreviated to "sp") as the basic unit of measurement. See [Page settings: Scaling](#) for more details

Options

Minimum measure width •

Sets the minimum horizontal length of measures. In measures containing very little content (e.g., a single whole note or whole measure rest), the measure will only shrink as far as this minimum

(Spacing (1=tight) •

Condenses or expands the space *after* notes or rests. This setting thus affects not only space between notes but also between the last note and the ending barline. For the space between the *beginning* of the measure and the first (note or rest, see **Barline to note distance** (below

Note: Changes to an individual measure's **Stretch** (under Layout → Increase Stretch, Decrease Stretch) are calculated after, and proportional to, the global **Spacing** setting

Barline to note distance •

Sets the distance between the barline which begins a measure and the first note or rest in that measure. For the (initial measures of systems, which start with clefs instead of barlines, use **Clef/key right margin** (below

Barline to grace note distance •

Sets the distance between a barline and a grace note that occurs before the first actual note in a measure ((independently of the "Barline to note distance" setting

Barline to accidental distance •

Sets the distance between a barline and an accidental placed before the first note in a measure (independently of (the "Barline to note distance" setting

Note to barline distance •

(To be added)

Minimum note distance •

Specifies the smallest amount of space MuseScore will allow after each note (depending on other factors, *more* (space may be allowed

Clef left margin •

(Sets the distance between the very beginning of each line and the clef. (This option is rarely needed

Key signature left margin •

.Sets the distance between the key signature and the clef preceding it

Time signature left margin •

.Sets the distance between the time signature and the key signature or clef preceding it

Clef/key right margin •

Sets the distance between the material at the beginning of each line (such as the clef and key signature) and the first note or rest of the first measure on the line. (Note that, although not named in the option, if a time signature is (present, it is the element from which the spacing begins

Clef to barline distance •

.Sets the distance between a barline and a clef change preceding it

Multi-measure rest margin •

.Sets the distance between a [multi-measure rest](#) and the barlines on either side

Staff line thickness •


Sets the thickness of the lines of the staff, which allows you to make the staff thicker and darker, if you need greater visibility on your printouts

Page settings

Page settings allows you to adjust the *overall* dimensions of your score such as [page size](#), [page margins](#), and [scaling](#). It

...is one of the main layout tools in MuseScore—along with the options available from Style → General

....To open the **Page settings** dialog: from the menu, select Layout → Page Settings



Page size

Here you can select the paper format, either by standard name (e.g., Letter or A4), or by specifying the height and width in either mm or inches (use the radio buttons to choose which unit of measurement to use). The initial default page size depends on your localization—in the United States, Letter size paper is standard

You can also choose to format your music in **Landscape** or **Portrait** orientation using the radio buttons. Prior to version 2.1 unchecking **Landscape** enabled **Portrait** format. You can optionally use **Two sided** layout (i.e., book format, with mirrored left and right margins for even and odd pages—see [below](#))

Odd/Even Page Margins

The **Even Page Margins** and **Odd Page Margins** settings allow you to define the printable area of your pages. Aside from changing the margins around the music on the page, other settings, such as the positions of headers and footers, are calculated relative to the margins defined here

If the "Two sided" checkbox under "Page Size" is selected, you can set margins differently for mirroring odd and even pages. Otherwise, only one set of margins can be modified, but will apply to all pages

.To display page margins in your score on screen (though not in print), go to View → Show Page Margins

Scaling

.The **Scaling** property allows you to increase or decrease the size of your score

In MuseScore, the sizes of score elements, such as note heads, note stems, accidentals, clefs etc., are defined in terms of a unit of measurement called a **staff space** (abbreviated to "sp"). One **staff space** is equal to *the space between two lines of a music staff* (or one-quarter the size of the full five-line staff)

As you change the "Staff space" setting (under **Scaling**), *all* score elements follow suit and thus correct proportions are maintained. The exception is Text in which you can set an *absolute* value, independent of "Scaling"

Note: Changing the "Scaling" does not always change the number of systems per page, because system distance can vary between limits set under "Min system distance" and "Max system distance" (see Style → General... → Page

Miscellaneous

Sets the number of the first page of the particular score. Page numbers below 1 won't get printed—e.g., setting the first page number to -1 would result in the first and second page showing no page number, and page number 1 appearing on the third page.

Apply to all Parts

The Apply to all Parts button is available when modifying a **part**, rather than the main score (see [Part extraction](#)). If you change the page settings of one part and want the rest of the parts to have the same settings, this button will apply the change to all parts in one go.

Breaks and spacers

The **Breaks & Spacers palette** in the Advanced [workspace](#) contains the following non-printing symbols



The first three symbols are called breaks; the blue up and down arrows are known as spacers.

Breaks

A **break** can be applied to either a measure or a frame. There are three types

- .**System break** (called a **line break** prior to version 2.2): Forces the next part of the score to start in a new system
- .**Page break**: Forces the next part of the score to start on a new page
- .**Section break**: Divides the score into sections (see below), and forces the next part of the score to start in a new system. It can be combined with a page break if required

Notes: (1) Blue break symbols are visible on the screen, but do not appear on printouts. (2) To add (or remove) system breaks over *all* or *part* of the score, see [Add/Remove system breaks](#). (3) To split a measure, see [Measure operations: Split and join](#).

Add a break to a measure

Breaks can be added using either (1) a keyboard shortcut; or (2) a break symbol from a palette

Using a keyboard shortcut

To add a **System (Line) break** or a **Page break** only

Click on any one of the following elements .1

- Barline
- Measure

- (Measure range (as of version 2.2
- (Notehead (as of version 2.2

(A text element associated with a staff (e.g. lyric syllable, chord symbol, staff text etc.) (as of version 2.2

Chose one of the following options .2

- (**System (Line) break**: Press \leftarrow (toggle
- (**Page break**: Press $\text{Ctrl}+\leftarrow$ (Mac: $\text{Cmd}+\leftarrow$) (toggle

Note: If you select a measure range, the break will be applied before and after the selection

Using a palette symbol

Any break can be added from a workspace palette

Select any one of the following elements .1

- Barline
- Measure

- (Measure range (as of version 2.2

;(Notehead (as of version 2.2 ◦
 ;(A text element associated with a staff (e.g. lyric syllable, chord symbol, staff text etc.) (as of version 2.2 ◦
 .(Double click a break symbol in a palette (toggle .2

Note: If you select a measure range, the break will be applied before and after the selection

.Alternatively, *drag* a break symbol from a palette onto a measure •

Add a break to a frame

:To add a break to a frame, use one of the following options

- .Drag a break from a palette onto a frame
- .Select a frame then double-click a palette break symbol

Move a break

:To reposition a break

- .1 .Enter edit mode for the break in question
- .2 .Use the keyboard arrow buttons as described in Adjust position of text objects

Delete breaks

:Use one of the following options

- .Select one or more breaks and press Del


.See also: Add / Remove system breaks

Section break

A **Section break**, as the name suggests, is used to create separate sections within a score. Like a **system break**, it forces the next measure or frame to begin a new system, and can also be used in association with a **page break** if required. A section break could be used, for example, to divide a piece into separate movements

Each section can have its own measure numbering independent of the rest of the score. By default, the first measure of a section is numbered "1" (see image below), though like the first measure of the score itself, the number is not displayed unless configured in the measure properties dialog. The same dialog can be used to change the numbering according to your preference

If you change Time signature or Key signature at the beginning of the new section, there will be no courtesy signature at the end of the previous section. See example below



When you play back the score, the program adds a short pause between each section. In addition, the *first/next repeat barline* in a section always sends the playback cursor to the beginning of the section, so a *start repeat barline* is optional

:Right click a Section break and select **Section Break Properties...** to specify

- ;Pause length
- ;If the new section's first system shows long instrument names
- .If the new section starts numbering measures at 1

Spacers

A **Spacer** looks like a blue UP or DOWN arrow and is used to add extra space above or below a system (it cannot be applied to a frame)

:Use either of the following options

- .Select a measure, then double-click a palette spacer symbol
- .Drag a spacer symbol from a palette onto a measure

.Blue spacer symbols are visible on the screen, but do not appear on printouts

Note: Spacers are designed for *local* adjustments only. If you wish to adjust the space between staves across the *whole* score, use the settings in Style → General... → Page instead

Adjust a spacer

:To adjust the height of a **spacer**, chose one of these options

- .Double-click the spacer and drag the blue end-handle up and down
- .Double-click the spacer and use the ↑ ↓ keys and/or Ctrl+↑ ↓ to move the end-handle up and down
- .Click (or double-click) on the spacer and adjust the height property in the Inspector

Delete a spacer

- .Click on the spacer and press the Del key

See also

- Add / Remove system breaks

Frames


:A **Frame** is a rectangular container for empty space, text or pictures in the score. It can be one of three types

- Horizontal: Used to create a break in a particular system. Can contain one or more text objects and/or images
- Vertical: Inserted above a system or appended to the last system. Can contain one or more text objects and/or images
- Text: Inserted above a system or appended to the last system. Can contain one text object only

Horizontal frame

:A **horizontal frame** is used to create a break in a system. For example, you can

- .(Create a coda, with an adjustable gap separating it from the rest of the score (as in the example below



- .Create an offset at the beginning of the score, where there is no staff name to perform the same function
- .Create an adjustable right margin at the end of a system
- .(Create space for some text or image(s
- .Create a space between a 'historical incipit' and the beginning of the modern edition

Insert/append horizontal frame

- .(See Create a Frame (below

Adjust width of horizontal frame

:Use one of the following methods

- .Double-click the frame and drag the handle to the right or left
- .Select the frame and adjust "Width" in the Inspector

Notes: (1) "Left Gap" and "Right Gap" are currently unused (version 2.x); (2) It is possible to create a 'Negative-width' horizontal frame, by dragging the edit-handle back over the left border of the frame. However, this is not a standard feature and once editing is finished you cannot reselect the frame

Add text or image to horizontal frame

:To add text

.Right-click on the frame and select Add → Text •

:To add an image

.Right-click on the frame and select Add → Image •

Vertical frame

A **vertical frame** can be inserted above a system or appended to the last system. It can contain one or more text objects and/or images. The height is adjustable and the width equals the system width

:It can be used, for example, to

- .(Create an area at the head of a score for Title/Subtitle/Composer/Lyricist text etc. (see below •
- .(Add single- or multi-column lyric text (at the end of a score •
- .Create a title page •
- .Create subtitles and other annotations between systems •

Insert/append vertical frame

.(See [Create a Frame](#) (below


Adjust height of vertical frame

:Use one of the following methods

- .Double-click the frame and drag the handle up or down •
- .Select the frame and adjust "Height" in the [Inspector](#) •

Edit vertical frame properties

:Selecting the frame allows you to adjust various parameters in the Inspector



.(**Top Gap:** Adjusts distance between frame and element above (negative values not currently supported

.(**Bottom Gap:** Adjusts distance between frame and element below (Negative values can be entered

.**Height:** Adjusts height of the frame

.**Left Margin:** Moves left-aligned text objects to the right

.**Right Margin:** Moves right-aligned text objects to the left

.(**Top margin:** Moves top-aligned text objects downwards (see also [Style](#) → [General...](#) → [Page](#)

.(**Bottom Margin:** Moves bottom-aligned text objects upwards (see also [Style](#) → [General...](#) → [Page](#)

Add text or image to vertical frame

:To add text

.Right-click on the frame and select Add → Text/Title/Subtitle/Composer/Lyricist •

:To add an image

.Right-click on the frame and select Add → Image •

You can create as many objects as you like within a frame. Their positions can be adjusted independently by dragging or, more accurately, by altering the offset values in the Inspector. To format text objects, see [Text editing](#) and [Text styles and properties](#).

Insert horizontal frame in vertical frame

.Right-click on the frame and select Add → Insert Horizontal Frame •

:The [horizontal frame](#) is automatically *left-aligned* and fills the entire vertical frame. To *right-align* it

.Reduce the [width](#) of the horizontal frame .1

.Deselect the frame then drag it to the right. To restore left-alignment, drag the frame to the left .2

Title" frame"

A vertical frame is automatically created at the beginning of a score, showing the title, subtitle, composer, lyricist etc., when you fill in the information fields provided on page 1 of the [New Score Wizard](#)

:If the score does not have a vertical frame at the beginning, you can create one as follows

.Right-click on an empty space in the document window and select Text → Title/Subtitle/Composer/Lyricist •

Text frame

A **Text frame** looks like a [vertical frame](#), but is specialised for text input: *one* text object is allowed per frame. The height automatically expands to fit the content and there is no height adjustment handle

:A text frame can be used, for example, to

.Create lyric text at the end of a score •

.Create subtitles and other annotations between systems •

Insert/ append text frame

.(See [Create a Frame](#) (below

Edit text frame properties

:Selecting the frame allows you to adjust various parameters in the Inspector

.(**Top Gap**: Adjusts distance between frame and element above (negative values not currently supported

.(**Bottom Gap**: Adjusts distance between frame and element below (negative values can be entered

.**Height**: Not applicable to text frames

.**Left Margin**: Moves left-aligned text objects to the right

.**Right Margin**: Moves right-aligned text objects to the left

.**Top margin**: Moves top-aligned text objects downwards

.**Bottom Margin**: Moves bottom-aligned text upwards

Create a frame

Insert a frame into the score

.[Select](#) a measure .1

:Chose one of the following options .2

...From the menu select Add → Frames → Insert ◦

...Right-click on an empty space in the score window and select Frames → Insert ◦

Append a frame to the score

:Chose one of the following options

- ...From the menu select Add → Frames → Append
- ...Right-click on an empty space in the score window and select Frames → Append

Delete a frame

.Select the frame and press Del

Apply a break

:Line, page or section breaks can be applied to frames as well as measures. Use one of two methods

- .(Select a frame and double-click a palette break symbol (for example, in the Breaks & Spacers palette
- .Drag a break symbol from a palette onto a frame

See also

- .Text Properties: to put a visual frame (border) around text
- .Insert measures: to insert measures before a frame

External links

- How to add a block of text to a score
- [Page Formatting in MuseScore 1.1 - 1. Frames, Text & Line Breaks] [video]

Images

You can use **Images** to illustrate scores, or to add symbols that are not included in the standard palettes. MuseScore supports the following formats

- (PNG (*.png)
- (JPEG (*.jpg and *.jpeg)
- (.SVG (*.svg) (MuseScore currently does not support SVG shading, blurring, clipping or masking)

Add image

:Use one of the following options

- .Drag-and-drop an image file (from outside MuseScore) either into a frame or onto a note or rest in the score
- .Right-click on a frame, select Add → Picture, then pick an image from the file selector

Cut/copy and paste image

- 1 .Click on an image in the score
- 2 .Apply any of the standard copy/cut commands
- 3 .Click on a note, rest or frame
- 4 .Apply any of the standard paste commands

Modify image

To modify the width/height of an image, double-click it and drag any of the handles. If you want to adjust width or height separately, untick "Lock aspect ratio" first in the Inspector

.You can adjust the position of an image by simply dragging it

See also

- Image capture
- Custom palettes

- [How to create an ossia with image capture](#) 
- [How to create an ossia with another staff](#) 

Image capture

MuseScore's **image capture** feature allows you to save a snapshot of any part of the score window. PNG, PDF and SVG .formats are supported

Save a snapshot

1.  Click on the **Toggle image capture** button
2. Press Shift + drag, to create a new selection rectangle
3. Fine tune the rectangle position, if required, by dragging it and/or changing the "Position" values in the "Lasso" section of the Inspector
4. Fine tune the rectangle area, if required, by dragging the handles, and/or changing the "Size" values in the Inspector
5. Right-click on the selection rectangle to open the **Image Capture** menu. Select the desired option
 - **Save As (Print Mode)**. This saves an image of the selection area as it would look if printed, e.g




- **Save as (Screenshot Mode)**. This saves a selection of the actual screen, including any line break symbols, invisible elements etc., e.g



.You can save the image in either PNG (default), SVG or PDF format

Image capture menu

:Right-clicking on the selection rectangle opens the **Image Capture** menu



- **Copy image:** Chose this to copy an image before pasting it in the same or another MuseScore file
- **Resolution:** Set the resolution, and hence the size of the saved or copied image. Try 100 dpi to start with, if you are unsure
- **Transparent background:** Turn image transparency on or off
- **Auto re-size to page:** Adjusts the selection rectangle to fit the page
- **(Resize to A/B/C/D:** Chose a customised selection rectangle (as set below
- **Set Standard Size:** Resize the selection rectangle, then chose "Set size A/B/C/D" to store it

See also

[Image](#) •

External links

- [Create an ossia with image capture](#)
- [How to create an ossia with another staff](#)


Align elements

:While dragging an element

- .Press Ctrl to constrain movement to the horizontal only
- .Press Shift to constrain movement to the vertical only

Snap to grid

.**Snap to grid** is a feature which allows you to *drag* an element in precise steps—useful for exact positioning



To enable snap to grid, select an element and click one or both of the snap to grid buttons, located to the right of the horizontal and vertical offset fields in the [Inspector](#). You can then *drag* the element in steps equal to the **grid spacing**. The default value is 0.5 sp

:To change the **grid spacing**

1. Right-click on any of the snap to grid buttons in the Inspector, and select Configure Grid
2. Set values for the horizontal and vertical grid spacing as required. Note that this is a fractional setting

Advanced topics

Accessibility

Introduction

This document is written for blind and visually impaired users of MuseScore 2.x. It is not intended to provide a full description of all of the features of MuseScore; you should read this in conjunction with the regular MuseScore [documentation](#)

MuseScore comes with support for the free and open source [NVDA screen reader](#) for Windows. The features in this document have been tested on Windows with NVDA. There is no support at the moment for other screen readers such as [Jaws](#) for Windows, or [VoiceOver](#) for macOS, which may work differently, or not at all

At this point in time, MuseScore 2.x is mostly accessible as a score reader, not so much as a score editor. This document will focus on the score reading features, with only a brief description of score editing

Initial setup

When you run MuseScore for the first time, you may want to permanently disable the Start Center window. To do so, go close the Start Center window first, then the Edit menu (Alt+E), choose Preferences, and in there, uncheck Show Start Center. Save and close the preferences window

The user interface in MuseScore works much like other notation programs, or other document-oriented programs in general. It has a single main document window in which you can work with a score. MuseScore supports multiple document tabs within this window. It also supports a split-screen view to let you work with two documents at once, and you can have multiple tabs in each window.

In addition to the score window, MuseScore has a menu bar that you can access via the shortcuts for the individual menus:

- File: Alt+F •
- Edit: Alt+E •
- View: Alt+V •
- Add: Alt+A •
- Notes: Alt+N •
- Layout: Alt+L •
- Style: Alt+S •
- Plugins: Alt+P •
- Help: Alt+H •

Of these, only the File menu is of much interest when using MuseScore as a score reader. Once opening a menu, it may take several presses of the Up or Down keys before everything is read properly.

There are also a number of toolbars, palettes, and subwindows within MuseScore, and you can cycle through the controls in these using Tab (or Shift+Tab to move backwards through this same cycle). When you first start MuseScore, or load a score, focus should be in the main score window. Pressing Tab takes you to a toolbar containing a series of buttons for operations like New, Open, Play, and so forth. Tab will skip any buttons that aren't currently active. The names and shortcuts (where applicable) for these buttons should be read by your screen reader.

Once you have cycled through the buttons on the toolbar, the next window Tab will visit is the Palette. This would be used to add various elements to a score, but it is not currently accessible except for two buttons that are visited by Tab: a drop-down to select between different workspaces (a saved arrangement of palettes), and a button to create a new workspace.

If you have opened one of the optional windows, such as the Inspector, or the Selection Filter, the Tab key will also visit these. You can close windows you do not need by going to the View menu and making sure none of the first set of checkboxes are selected (the windows that appear before the Zoom settings). By default, only the Start Center, Palettes and Inspector should be selected. See [Initial Setup](#) for instructions for disabling the Start Center. F9 can be used to toggle the Palettes while F8 will toggle the Inspector.

To return focus to the score window after visiting the toolbar, or a subwindow, press Esc. This also clears any selection you may have made in the score window.

The score window

When you first start MuseScore 2.x, an empty example score entitled “My First Score” is loaded by default. If you wish to experiment with editing features, this would be a good place to begin. Otherwise, you will probably want to start by loading a score. MuseScore uses the standard shortcuts to access system commands like Ctrl+O (Mac: Cmd+O) to open a file, Ctrl+S (Mac: Cmd+S) to save, Ctrl+W (Mac: Cmd+W) to close, etc.

If you press Ctrl+O (Mac: Cmd+O) to load a score, you are presented with a fairly standard file dialog. MuseScore can open scores in its own format (MSCZ or MSCX) as well as import scores in the standard MusicXML format, in MIDI format, or from a few other programs such as Guitar Pro, Capella, and Band-in-a-Box. Once you have loaded a score, it is displayed in a new tab within the score window. You can move between the tabs in the score window using Ctrl+Tab (does not apply for Mac).

There are a few interesting things you can do with a loaded score besides reading it note by note. You can press Space to have MuseScore play the score for you. You can use File / Export to convert to another format, including PDF, PNG, WAV, MP3, MIDI, MusicXML, etc. And of course, you can print it via File / Print or Ctrl+P (Mac: Cmd+P).

If a score contains multiple instruments, it may already have linked parts generated. Linked parts are presented as part tabs within score tabs, but currently, there is no way to navigate these part tabs using the keyboard. The parts would not normally contain information different from the score; they would just be displayed differently (each part on its own page).

If a score does not already have parts generated, you can do so through File / Parts, and that dialog is accessible. If you wish to print the parts, you can work around the inability of accessing part tabs individually by using the File / Export Parts dialog, which automatically exports PDF's (or other formats) for all parts in one step.

When you first load a score, the score window has the keyboard focus, but there will be nothing selected. The first step to reading a score is to select something, and the most natural place to begin is with the first element of the score. `Ctrl+Home` (Mac: `Cmd+Home`) will do this. You will probably also want to use this, should you ever clear your selection by pressing `.Esc`.

As you navigate between elements, your screen reader should give the name of the selected element (most likely the clef at the beginning of the top staff of your score). You will hear it read the name of the element (for example, “Treble clef”) and also give position information (for example, “Measure 1; Beat 1; Staff 1”). The amount of information read is not currently customizable, but we tried to place the most important first so you can quickly move on to the next element before it has finished reading, or just ignore the rest of what is read. Pressing `Shift` currently interrupts the reading, which might also be useful.

Most navigation in MuseScore is centered around notes and rests only – it will skip clefs, key signatures, time signatures, barlines, and other elements. So if you just use the standard `Right` and `Left` keys to move through your score, you will only hear about notes and rests (and the elements attached to them). However, there are two special navigation commands that you will find useful to gain a more complete summarization of the score:

- (Next element: `Ctrl+Alt+Shift+Right` (Mac: `Cmd+Option+Shift+Right` •
- Previous element: `Ctrl+Alt+Shift+Left` (Mac: `Cmd+Option+Shift+Left` •

These commands include clefs and other elements that the other navigation commands skip, and also navigate through all voices within the current staff, whereas other navigation commands such as `Right` and `Left` only navigate through the currently selected voice until you explicitly change voices. For instance, if you are on a quarter note on beat 1 of measure 1, and there are two voices in that measure, then pressing `Right` will move on to the next note of voice 1—which will be on beat 2—whereas pressing `Ctrl+Alt+Shift+Right` (Mac: `Cmd+Option+Shift+Right`) will stay on beat 1 but move to the note on voice 2. Only once you have moved through all notes on the current beat on the current staff will the shortcut move you on to the next beat. The intent is that this shortcut should be useful for navigating through a score if you don’t already know what the contents are.

When you navigate to an element, your screen reader should read information about it. For notes and rests, it will also read information about elements attached to them, such as lyrics, articulations, chord symbols, etc. For the time being, there is no way to navigate directly to these elements.

One important note: `Up` and `Down` by themselves, with `Shift`, or with `Ctrl / Cmd` are not useful shortcuts for navigation! Instead, they change the pitch of the currently selected note or notes. Be careful not to inadvertently edit a score you are trying to read. `Up` and `Down` should only be used with `Alt/Option` if your intent is navigation only. See the list of navigation shortcuts below.

Moving forwards or backwards in time

The following shortcuts are useful for moving “horizontally” through a score:

- Next element: `Ctrl+Alt+Shift+Right` •
- Previous element: `Ctrl+Alt+Shift+Left` •
- Next chord or rest: `Right` •
- Previous chord or rest: `Left` •
- Next measure: `Ctrl+Right` •
- Previous measure: `Ctrl+Left` •
- Go to measure: `Ctrl+F` •
- First element: `Ctrl+Home` •
- Last element: `Ctrl+End` •

Moving between notes at a given point in time

The following shortcuts are useful for moving “vertically” through a score:

- Next element: `Ctrl+Alt+Shift+Right` •
- Previous element: `Ctrl+Alt+Shift+Left` •
- Next higher note in voice, previous voice, or staff above: `Alt+Up` •
- Next lower note in voice, next voice, or staff below: `Alt+Down` •
- Top note in chord: `Ctrl+Alt+Up` •
- Bottom note in chord: `Ctrl+Alt+Down` •

The Alt+Up and Alt+Down commands are similar to the Ctrl+Alt+Shift+Right and Ctrl+Alt+Shift+Left commands in that they are designed to help you discover the content of a score. You do not need to know how many notes are in a chord, how many voices are in a staff, or how many staves are in a score in order to move vertically through the score using these commands.

Filtering score reading

Excluding certain elements like lyrics, or chord names while reading the score is possible by using the Selection filter (6). Uncheck those elements you don't want to read.

Score playback

The Space bar serves both to start and stop playback. Playback will start with the currently selected note if one is selected; where playback was last stopped if no note is selected; or at the beginning of the score on first playback.

MuseScore supports looped playback so you can repeat a section of a piece for practice purposes. To set the "in" and "out" points for the loop playback via the Play Panel (F11)

- 1 First select the note in the score window where the loop should start.
- 2 Go to the Play Panel and press the Set loop In position toggle button.
- 3 Back to the score window, navigate to the note where you want the loop to end.
- 4 Switch again to Play Panel, and press the Set loop Out position toggle button.
- 5 To enable or disable the loop, press the Loop Playback toggle button.

You can also control the loop playback and control other playback parameters, such as overriding the basic tempo of a score, using the View / Play Panel (F11).

Score editing

Score editing is currently not very accessible – too many score elements require intervention of the mouse in order to place objects onto a score. Additionally, visual reference and manual adjustment of the position of various elements is sometimes necessary due to MuseScore's limited support for conflict avoidance of elements.

In contrast, MuseScore does often provide ample default, and a platform to experiment with the basics of note input. To enter note input mode, first navigate to the measure in which you would like to enter notes, then press "N". Almost everything about note input is designed to be keyboard accessible, and the standard documentation should be good to help you through the process. Bear in mind that MuseScore can either be in note input or normal mode, and it won't always be clear which mode of these you are in. When in doubt, press Esc. If you were in note input mode, this will take you out. If you were in normal mode, you will stay there, although you will also lose your selection.

Customization

You can customize the keyboard shortcuts using Edit / Preferences / Shortcuts. At some point, we may provide a set of special accessibility-optimized shortcuts and/or a way of saving and loading sets of shortcut definitions.


External links

- [Creating a New Score in MuseScore with NVDA](#)
- [Inputting notes in MuseScore with NVDA](#)
- [Creating Modified Stave Notation in MuseScore](#)

Albums

The Album Manager allows you to prepare a list of multiple scores and save the list as an album file ("*.album"), print all the scores as one long print job with consistent page numbers, or even join the scores into a single new MSCZ score. This is ideal for preparing an exercise book or combining multiple movements of an orchestration.

...To open the Album Manager, go to File → Album



Create album

- .To create a new album, click the **New** button. Fill in a title in the "Album Name:" box at the top .1
- To add scores to the album, click **Add Score**. A file selection dialog will appear and let you choose one or multiple .2
- .scores from your file system. Click **OK**
- The scores you add will appear in a list in the Album Manager. You can rearrange their order by selecting a score .3
- .and clicking the **Up** or **Down** button

Load album

If you have previously created an album, you can open it through the Album Manager by clicking the **Load** button. A file selection dialog will appear to let you load the .album file from your file system

Print album

To print an album as if it were a single document, click **Print Album**. The scores loaded into the Album Manager are printed in the order they are listed in with the correct page numbers, ignoring the page number offset values in **Layout → Page Settings...** → **First page number for all but the first score**. As the album is printed in one print job, double-sided printing (duplex printing) also works as expected

Join scores

To combine multiple scores into a single .mscz file, click **Join Scores**. The scores are combined in the selected order into one single score. If not already present, line- and section breaks are added to the last measure or frame of each score in the combined file

.All style settings are taken from the first score, different style settings from subsequent score are ignored

All the scores should have the same number of parts and staves for this to work correctly, ideally with the same instruments in the same order. If the scores have the same total *number* of instruments but not the same ones, or not in the same order, then the instrument names from the first score will overwrite ones from subsequent scores. If some of the scores have fewer instruments than the first score, then empty staves will be created for those sections. **Any part or staff that is not present in the first score will be lost in the joined score**

Save album

Upon clicking the **Close** button, you will be prompted to save your album as a .album file. This file is not the same as a joined score; it simply consists of the list of scores. Album files can be loaded into the Album Manager as described above

Cross-staff notation

In piano scores, it is common to write a musical phrase extending across both staves—bass and treble. This can be entered in MuseScore as follows

:Enter all notes in one staff .1



:(↑+Ctrl+Shift+↓ moves the selected note, or chord to the next staff (Mac:⌘+Shift ↓ .2



Note : this moves the whole chord, not just a single note from a multi note chord. If you need notes in the old staff at the same place, use voices

To adjust the beam, double-click it to show the handles. Use the keyboard arrows or drag the handles to change the .3
:beam angle and position



See also

.Connect barlines: How to extend barlines over multiple staves •

External links

("How to span a chord or stem over two staves" (MuseScore "Howto •

Early music features


MuseScore 2 offers several specialized functions to create engravings of early music (particularly medieval and .renaissance) akin to commercial editions from the 20th century onwards

Unbarred (or unmetred) notation

In MuseScore, notes lasting longer than the duration of a measure are normally tied across barlines. However MuseScore has a special feature which allows it to display the note values intact, without splitting and tying them in this way. This :enables you to notate music which is unbarred (i.e. not divided into measures), such as that of the **renaissance**

.1 From the menu bar, select Style → General... → Score


".2 Tick the box labelled "Display note values across measure bar



.Click "OK" or "Apply." The existing score is immediately updated .3

Example


The example below shows an excerpt from the original score of "De Profundis Clamavi" for 4 voices by Nicolas .1
:Champion



:The same excerpt displayed in MuseScore .2



".And after activating "Display note values across measure bar .3



To get rid of the barlines, just untick the "Show barlines" box in the Staff properties dialog. See also [Mensurstrich](#) .4
.(below

Note: The feature is still in development and may contain bugs. The longest supported note value is the longa (a dotted .(longa is still broken up and tied over

Mensurstrich

Since a complete lack of barlines could make performing the music more difficult for current musicians, many modern .engravers settled on a compromise called *Mensurstrich*, where barlines are drawn between, but not across, staves



:To place barlines between staves

- .1 ;Enter edit mode by double-clicking a barline in a staff above where you want the *Mensurstriche*
- .2 ;Hold Shift and drag the lower handle of the barline *down* until it meets the top of the staff below
- .3 ;Hold Shift and drag the upper handle of the barline *down* until it meets the bottom of the current staff
- .4 .Exit edit mode by pressing Esc or clicking on a blank area of the document window

:Alternatively, you can use the Inspector

- .1 ;In the staff below the proposed *Mensurstriche*, uncheck "Show barlines" in the Staff properties dialog
- .2 In the staff above where you want the *Mensurstriche*, right-click on one barline and chose Select → All Similar Elements in
;Same Staff
- .3 In the Inspector, under "Barline," make the following settings: "Spanned staves" = 2; "Spanned from" = 8; "Spanned
".to = "0

Note: To reset barlines, select the relevant barlines and make the following settings: "Spanned staves" = 1; "Spanned
".from" = 0; "Spanned to" = "8

Ambitus

Before there was the concept of an absolute pitch, performers were required to transpose vocal music to a singable range for their ensemble "on the fly." To aid them, an **ambitus** was sometimes included, marking the entire range of a voice at the beginning of the piece

:To apply an ambitus, use one of the following methods

- .Drag the ambitus symbol (from the Lines palette of the Advanced workspace) onto a clef
- .(Select a clef, then double-click the ambitus symbol (in the Lines palette of the Advanced workspace



When applied, the ambitus automatically displays the note range of the score: if there is a section break then *only* the note range of the section is displayed. Beyond the section break a new ambitus may be applied

The note range of the ambitus can be adjusted manually by selecting it and changing the "Top note" and "Bottom note" values in the Inspector. For automatic adjustment click the Update Range button in the inspector

Mensural time signatures

In the mensural notation system, time signatures did not define the length of a measure, but the length of breves and semibreves. MuseScore supports mensural time symbols as a display method in the Time signature properties dialog rather than as symbols, but they are just for show, as the proportion of e.g. half notes per whole notes cannot be modified. One way to make use of these symbols is to replicate when composers of the renaissance had multiple voices in different time signatures simultaneously without using tuplets. Edit the time signature on a per-staff basis, as long as the beginning and end of a measure in all staves match up. If they do not, then consider increasing the size of the measures to the lowest common denominator.



De Profundis Clamavi for 5 voices by Josquin Des Prez

See also

[Measure Operations: Split and join](#) •

Figured bass

Adding a new figured bass indication

1. Select the note to which the figured bass applies.
2. (Press the Figured Bass shortcut (default **Ctrl+G**; can be changed in Preferences).
3. (Enter the text in the editor 'blue box' as required (see below).
4. Press **Space** to move to the next note ready for another figured bass indication (or click outside the editor box to exit). (it



With **Space**, the editor advances to the next note, or rest of the staff to which figured bass is being added. To move to a point in between, or to extend a figured bass group for a longer duration, see below *Group Duration*.

Tab advances the editing box to the beginning of the next measure.

Shift+Space moves the editing box to the previous staff note or rest.

Shift+Tab moves the editing box to the beginning of the previous measure.

Text format

Digits

Digits are entered directly. Groups of several digits stacked one above the other are also entered directly in a single text, :stacking them with **Enter**.



Accidentals

:Accidentals can be entered using regular keys


:type **:To enter**

- bb double flat
- b flat
- h natural
- # sharp
- ## double sharp

These characters will automatically turn into the proper signs when you leave the editor. Accidentals can be entered before, or after a digit (and of course, in place of a digit, for altered thirds), according to the required style; both styles are properly aligned, with the accidental 'hanging' at the left, or the right

Combined shapes

Slashed digits or digits with a cross can be entered by adding , / or + after the digit (combining suffixes); the proper combined shape will be substituted when leaving the editor



:The built-in font can manage combination equivalence, favoring the more common substitution

(1+ 2+ 3+ 4+ result in 1+ 2+ 3+ 4+ (or +4 , +3 , +2 , +1

(5 6 7 8 9 and 5\, 6\, 7\, 8\, 9\ result in 5 6 7 8 9 (or

.Please remember that / can only be combined with 5; any other 'slashed' figure is rendered with a question mark

.(can also be used before a digit; in this case it is not combined, but it is properly aligned ('+' hanging at the left side +

Parentheses

Open and closed parentheses, both round: '(', ')' and square: '[', ']', can be inserted before and after accidentals, before and after a digit, before and after a continuation line; added parentheses will not disturb the proper alignment of the main character


:Notes

.The editor does not check that parentheses, open and closed, round or square, are properly balanced •

- Several parentheses in a row are non-syntactical and prevent proper recognition of the entered text
- A parenthesis between a digit and a combining suffix ('+', '\', '/') is accepted, but prevents shape combination

Continuation lines

Continuation lines are input by adding an '_' (underscore) at the end of the line. Each digit of a group can have its own continuation line



Continuation lines are drawn for the whole duration of the figured bass group

Extended' continuation lines'

Occasionally, a continuation line has to connect with the continuation line of a following group, when a chord degree has to be kept across two groups. Examples (both from J. Boismortier, *Pièces de viole*, op. 31, Paris 1730



In the first case, each group has its own continuation line; in the second, the continuation line of the first group is carried 'into' the second

This can be obtained by entering several (two or more) underscores "___" at the end of the text line of the first group

Duration

Each figured bass group has a duration, which is indicated by a light gray line above it (of course, this line is for information only and it is not printed or exported to PDF

Initially, a group has the same duration of the note to which it is attached. A different duration may be required to fit several groups under a single note or to extend a group to span several notes

To achieve this, each key combination of the list below can be used

- to advance the editing box by the indicated duration
- AND

- to set the duration of the previous group up to the new editing box position

Pressing several of them in sequence without entering any figured bass text repeatedly extends the previous group

:to get **:Type**

1/64 Ctrl+1

1/32 Ctrl+2

1/16 Ctrl+3

(quaver) 1/8 Ctrl+4

(crochet) 1/4 Ctrl+5

(half note (minim) Ctrl+6

whole note Ctrl+7

((semibreve

(whole notes (breve 2 Ctrl+8

(The digits are the same as are used to set the note durations)

Setting the exact figured bass group duration is only mandatory in two cases

(When several groups are fit under a single staff note (there is no other way .1

.When continuation lines are used, as line length depends on the group duration .2

.However, it is a good practice to always set the duration to the intended value for the purposes of plugins and MusicXML

Editing existing figured basses

:To edit a figured bass indication already entered


- Select it, or the note it belongs to and press the same *Figured Bass* shortcut used to create a new one
- or
- Double-click it


The usual text editor box will open with the text converted back to plain characters ('b', '#' and 'h' for accidentals, separate
.combining suffixes, underscores, etc.) for simpler editing

Once done, press Space to move to a next note, or click outside the editor box to exit it, as for newly created figured
.basses


Style

.To configure how figured bass is rendered: from the menu, select *Style* → *General...* → *Figured Bass*







- **Font:** The dropdown list contains all the fonts which have been configured for figured bass. A standard installation contains only one font, "MuseScore Figured Bass," which is also the default font
 - **Size:** Select a font-size in points. *Note:* This value is also modified by any change made to **Scaling** (Layout → Page → "Settings..."), or **Scale** ("Staff properties")
 - **Vertical Position:** The distance (in *spatia*) from the top of the staff to the top margin of the figured bass text. Negative values go up (figured bass above the staff) and positive values go down (figured bass below the staff: a value greater than 4 is needed to step over the staff itself)
 - **Line Height:** The distance between the base line of each figured bass line, as a percentage of font size
- The following picture visualizes each numeric parameter



- **Alignment:** Select the vertical alignment: with *Top*, the top line of each group is aligned with the main vertical position and the group 'hangs' from it (this is normally used with figured bass notation and is the default); with *Bottom*, the bottom line is aligned with the main vertical position and the group 'sits' on it (this is sometimes used in some kinds of harmonic analysis notations)



- **Style:** Chose between "Modern" or "Historic." The difference between the two styles is shown below



Proper syntax

For the relevant substitutions and shape combinations to take effect and for proper alignment, the figured bass mechanism expects input texts to follow some rules (which are in any case, the rules for a syntactical figured bass : (indication

- ;There can be only one accidental (before or after), or only one combining suffix per figure
- ;There cannot be both an accidental **and** a combining suffix
- .There can be an accidental without a digit (altered third), but not a combining suffix without a digit
- .Any other character not listed above is not expected

If a text entered does not follow these rules, it will not be processed: it will be stored and displayed as it is, without any .layout

Summary of keys

:to get	:Type
.Adds a new figured bass group to the selected note	Ctrl+G
.Advances the editing box to the next note	Space
.Moves the editing box to the previous note	Shift+Space
.Advances the editing box to the next measure	Tab
.Moves the editing box to the previous measure	Shift+Tab
.Advances the editing box by 1/64, setting the duration of the previous group	Ctrl+1
.Advances the editing box by 1/32, setting the duration of the previous group	Ctrl+2
.Advances the editing box by 1/16, setting the duration of the previous group	Ctrl+3
.Advances the editing box by 1/8 (<i>quaver</i>), setting the duration of the previous group	Ctrl+4
.Advances the editing box by 1/4 (<i>crochet</i>), setting the duration of the previous group	Ctrl+5
.Advances the editing box by a half note (<i>minim</i>), setting the duration of the previous group	Ctrl+6
.Advances the editing box by a whole note (<i>semibreve</i>), setting the duration of the previous group	Ctrl+7
.Advances the editing box by two whole notes (<i>breve</i>), setting the duration of the previous group	Ctrl+8
.(Enters an actual space; useful when figure appears "on the second line" (e.g., 5 4 -> 3	Ctrl+Space
.Enters a double flat	BB
.Enters a flat	B
.Enters a natural	H
.Enters a sharp	#
.Enters a double sharp	##
.Enters a continuation line	_
.Enters an extended continuation line	__

File formats

MuseScore can import and export a wide variety of file formats, allowing you to share and publish scores in the format that .best meets your needs

MuseScore native format

:MuseScore saves files in the following native formats

- .MSCZ: The default MuseScore file format. Being compressed it takes up relatively little disk space.*
- .MSCX: An uncompressed MuseScore file format.*
- MSCZ_ / *.MSCX_: These are backup files. Notice the point (full stop) added before the file name, and the comma.*

.added to the file extension

A note about fonts: *MuseScore does not embed text fonts in saved or exported native format files. If you want your MuseScore file to be viewed by other MuseScore users, make sure you are using the built-in FreeSerif or FreeSans font families for your text, or a font that the other parties have installed too. If a system does not have the fonts specified in your original file, MuseScore will use a fallback option, which may cause your score to appear differently*

(MuseScore format (*.mscz

MSCZ is the standard MuseScore file format and recommended for most uses. A score saved in this format takes up very little disk space, but preserves all the necessary information. The format is a ZIP-compressed version of .mscx files and includes any images

(Uncompressed MuseScore format (*.mscx

MSCX is the uncompressed version of the MuseScore file format. A score saved in this format will retain all information, except images. It can be opened with a text editor, allowing the user access to the file's source code

(MuseScore backup file (*.mscz,) or (*.mscx

Backup files are created automatically and saved in the same folder as your normal MuseScore file. The backup copy contains the previously saved version of the MuseScore file and can be important if your normal copy becomes corrupted, or for looking at an older version of the score

The backup file adds a period to the beginning of the file name (.) and a comma (,) to the end (e.g. if your normal file is called "untitled.mscz", the backup copy will be ".untitled.mscz,"), and the period and comma need to be removed from the name in order to open the backup file in MuseScore. As it is stored in the same folder as your normal MuseScore file, you ("may also need to give it a unique name (e.g. changing ".untitled.mscz," to "untitled-backup1.mscz

Note: In order to see the MuseScore backup files, you may need to change your system settings to "Show hidden files".
↑See also [How to recover a backup copy of a score \(MuseScore 2.x\)](#) ↗

(Graphic files (export only

.MuseScore can export a score as a graphic file in either PDF, PNG or SVG format

(PDF (*.pdf

PDF (Portable Document Format) files are ideal for sharing your sheet music with others who do not need to edit the content. This is a very widely-used format and most users will have a PDF viewer of some kind on their computers

:To set the resolution of exported PDFs

;From the menu bar, chose Edit → Preferences... (Mac: MuseScore → Preferences...), and select the "Export" tab .1
.Set the resolution in the "PDF" section .2

(PNG (*.png

PNG (Portable Network Graphics) files are based on a bitmap image format, widely supported by software on Windows, Mac OS, and Linux, and very popular on the web. MuseScore creates PNG images as they would appear if printed, one image per page

:To set the resolution of exported PNG images

;From the menu bar, chose Edit → Preferences... (Mac: MuseScore → Preferences...), and select the "Export" tab .1
.Set the resolution and transparency in the PNG/SVG section .2

Note: If you want to create images that show only parts of the score (with or without screen-only items such as frame boxes, invisible notes, and out-of-range note colors), use Image capture instead

(SVG (*.svg

SVG ↗ (Scalable Vector Graphics) files can be opened by most web browsers (except Internet Explorer before version 9) and most vector graphics software. However, most SVG software does not support embedded fonts, so the appropriate

MuseScore fonts must be installed to view these files correctly. SVG is the format used on MuseScore.com for all scores [\(saved online since May 2017 \(coinciding with the release of MuseScore 2.1: before this the format was PNG](#)

To set resolution and transparency of exported SVG files, see the instructions under [PNG \(above\)](#). Note that MuseScore [\(does not \(yet\) support gradients on export \(although it does for images in a score](#)

(Audio files (export only

MuseScore can create *normalised*, stereo audio of the score in any of the following formats [WAV](#), [MP3](#), [OGG VORBIS](#), [FLAC](#). To export an audio file

1. From the menu, select File → Export
2. Chose the desired format from the dropdown menu, then press Save

You can adjust the **sample rate** of all audio formats as follows

1. From the menu bar, select Edit → Preferences... (Mac: MuseScore → Preferences...), and click on the [Export](#) tab
2. Set "Sample rate" in the "Audio" section

(WAV audio (*.wav

WAV (Waveform Audio Format) is an *uncompressed* sound format. This was developed by Microsoft and IBM, and is widely supported by software for Windows, OS X, and Linux. It is an ideal format for use when creating CDs, as full sound quality is preserved. For sharing via email or the internet, use a compressed alternative such as [MP3](#)

(MP3 (*.mp3

MP3 is a very widely-used compressed audio format. MP3 files are ideal for sharing and downloading over the internet due to their relatively small size

For **Windows** and **Mac** users with an older version of MuseScore (Windows: prior to 2.2, Mac prior to 2.3.2), an additional library, `lame_enc.dll` (Windows) or `libmp3lame.dylib` (Mac), must be installed to create MP3 files (for **Linux**, it is up to the distribution maintainer whether or not to include this). MuseScore will prompt you for its location on the first attempt of an [MP3 export](#). You can get it at <http://lame.buanzo.org>

Some Mac users may find MuseScore encounters an error loading the MP3 library, possibly due to that library being a 32-bit library. A 64-bit build that will work with MuseScore is available from <http://thaliectrum.com/en/products/lame> (note that it is necessary to rename the file to `libmp3lame.dylib` for MuseScore to recognize it). Homebrew users just need to `run brew install lame`

As of version 2.1 you can set the MP3 bitrate

1. From the menu bar, chose Edit → Preferences... (Mac: MuseScore → Preferences...), and select the "Export" tab
2. Set the MP3 bitrate in the "Audio" section

(FLAC audio (*.flac

[Free Lossless Audio Codec](#) (FLAC) is compressed audio format. FLAC files are approximately half the size of uncompressed audio and just as good quality. Windows and OS X do not have built-in support for FLAC, but software such as the free and open source [VLC media player](#) can play FLAC files on any operating system

(Ogg Vorbis (*.ogg

[Ogg Vorbis](#) is intended as a patent-free replacement for the popular MP3 audio format (which MuseScore also supports —see above). Like MP3, Ogg Vorbis files are relatively small (often a tenth of uncompressed audio), but some sound quality is lost. Windows and OS X do not have built-in support for Ogg Vorbis. However, software such as [VLC media player](#) and [Firefox](#) can play Ogg files on any operating system

Share with other music software

MuseScore can [import](#) and [export MusicXML](#) and [MIDI](#) files; it is also able to import a variety of native format files from other music notation programs

(MusicXML (*.xml, *.musicxml

[MusicXML](#) [↗](#) is the universal standard for sheet music. It is the recommended format for sharing sheet music between different scorewriters, including MuseScore, Sibelius, Finale, and more than 100 others. As of version 2.2, MuseScore exports as .musicxml, and imports both, *.xml and *.musicxml

(Compressed MusicXML (*.mxl

Compressed MusicXML creates smaller files than regular MusicXML. This is a newer standard and isn't as widely supported by older scorewriters, but MuseScore has full import and export support

(MIDI (*.mid, *.midi, *.kar

MIDI (Musical Instrument Digital Interface) is a format widely supported by sequencers and music notation software. For details of the protocol see the [MIDI Association](#) [↗](#) website

MIDI files are very useful for playback purposes but contain little in the way of score layout information (formatting, pitch spelling, voicing, ornaments, articulations, repeats, key signatures etc.). To share files between *different* music notation software, [MusicXML](#) is recommended instead

.For details about how to import MIDI files see [MIDI import](#)

(MuseData (*.md) (import only

[MuseData](#) [↗](#) is a format developed by Walter B. Hewlett beginning in 1983 as an early means of sharing music notation between software. It has since been eclipsed by MusicXML, but several thousand scores in this format are still available online

(Capella (*.cap, *.capx) (import only

CAP and CAPX files are created by the score writer, [Capella](#) [↗](#). MuseScore imports version 2000 (3.0) or later fairly accurately (2.x doesn't work, while the *.all format from 1.x versions is not supported at all

(Bagpipe Music Writer (*.bww) (import only

.BWW files are created by the niche score writer, [Bagpipe Music Writer](#) [↗](#)

(BB (*.mgu, *.sgu) (import only

.BB files are created by the music arranging software, [Band-in-a-Box](#) [↗](#). MuseScore's support is currently experimental

(Overture (*.ove) (import only

OVE files are created by the score writer [Overture](#) [↗](#). This format is mainly popular in Chinese-language environments, such as Mainland China, Hong Kong, and Taiwan. MuseScore's support is currently experimental

(Guitar Pro (*.gtp, *.gp3, *.gp4, *.gp5, *.gpx) (import only

.GP files are created by [Guitar Pro](#) [↗](#)

See also


- [Open/Save/Export/Print](#) •
- [Recovered files](#) •

External links

- [How to recover a backup copy of a score](#) [↗](#) •

Fretboard diagrams

A range of **fretboard** (or **chord**) **diagrams** for the guitar are pre-provided in the Fretboard Diagrams palette in the .(Advanced Workspace (versions prior to 2.0.3 feature only one diagram



You can create a chord diagram for *any* fretted, stringed instrument by editing an existing one. It can be saved to a custom palette for future use if required

Add a fretboard diagram

:To add a fretboard diagram to the score, use one of the following methods


- .Select a note in voice 1 and double-click a fretboard diagram from a palette
- .Drag and drop a fretboard diagram from a palette to the desired position in the score

Edit fretboard diagram


1.Right-click on a diagram in the score and select Fretboard Diagram Properties
2. .Adjust the **number of instrument strings**, using the "**Strings**" spin box at the bottom left of the window
3. .Adjust the **fret position number** using the scroll bar on the right-hand side
4. .Adjust how many frets to display (height-wise) using the "**Frets**" spin-box at the bottom right of the window
5. .To place a dot on a string fret, click on that fret. To remove the dot, click on the fret again
6. .Click just above the diagram to toggle a string between
 - o (Open)
 - o (Mute/unplayed)
 - o (No indication)
7. :To create a **barre** or **partial barre**
 - i. ;(i. Make sure the desired fret position is clear of black dots (click on a dot to remove it
 - ii. .Hold shift and click on the fret where you want the barre to begin. **Note**: Only one barre can be applied per diagram
 - iii. .To delete a barre, click on the black dot where the barre begins

:For example, to create a full-barre **F#** chord, from a **C** chord


1.Place the C fretboard diagram on the score, right-click on it and select Fretboard Diagram Properties
2. .Click on the relevant fret positions to establish the fingering dots
3. :Set "Frets" to "4" and fret number (right-hand scroll bar) to "2." The diagram should now look like this



Create the barre by holding Shift and clicking on the second fret of the 6th string. Click "OK" to exit and you should get this



The same principle applies if you want a partial barré. For example, the partial barré in an A7 chord is created by pressing Shift, then clicking on the 4th string, second fret



Adjust position, size, color

The size ("Scale"), color and position of a fretboard diagram can be changed by clicking on it and altering the relevant values in the [Inspector](#).

The position of the fretboard diagram can also be adjusted in [Edit mode](#):

- 1. (Double-click on the diagram (or click on it and press **Ctrl+E** (Mac: **Cmd+E**); or right-click on it and select **Edit element**).
- 2. Press the arrow keys for fine positioning (0.1 **sp.** at a time); or press **Ctrl+Arrow** (Mac: **Cmd+Arrow**) for larger adjustments (1 **sp.** at a time).

Fretboard diagram style

Some default properties of fretboard diagrams (barre thickness, vertical position, size etc.) can be adjusted from the menu: select **Style** → **General...** → [Chord Symbols, Fretboard Diagrams](#). Any changes made here affect all existing diagrams, as well as those applied subsequently.


MIDI import

MuseScore can import [MIDI](#) files (.mid/.midi/.kar) and convert them into music notation. To import, use the standard [Open](#) command.

Initially, the program renders the MIDI to notation using certain default settings. **AMIDI Import Panel** appears at the bottom of the screen, showing a list of tracks (only tracks with note events are shown) and the operations available for each track. You can change these settings on a track-by-track basis and then reimport the data: The "Apply" button (at the top) submits any changes with immediate effect. The "Cancel" button immediately cancels any unsaved changes. The final result should be a better quality score reproduction of the file.

Use **Shift+Wheel** or **Ctrl+Wheel** to scroll track options horizontally; scroll tracks vertically without those modifiers.

If there are multiple tracks, then one more track is added at the top of the list to select all tracks at once.



In the MIDI Import Panel, you can choose which tracks to import and reorder them. Some information about each track is displayed: sound, staff name, and lyrics, if any. The presence of the lyric column is an indication that the file contains a lyric track—assignable to different tracks through the drop-down menu.

The MIDI import panel updates the relevant information of whatever file is in view, if the user has several open. If the MIDI import panel is no longer required, it can be closed by clicking the close button in the top-left corner. The panel will reappear after clicking on the button "Show MIDI import panel" which appears right after the panel is closed.

After saving the score, the MIDI Import Panel will not be available, because MuseScore is no longer importing a MIDI file.

Available operations

MuseScore instrument

Assign a MuseScore instrument (listed in instruments.xml or in specified custom xml file in Preferences) that defines
.staff name, clef, transposition, articulations, etc
Quantization

:Quantize MIDI notes by some regular grid. The grid MAX resolution can be set via the drop-down menu

Value from preferences (default) - quantization value is taken from the main Preferences dialog of MuseScore •
((in the "Import" tab
Quarter, Eighth, 16th, 32nd, 64th, 128th - user-defined values •

However, the actual quantization grid size is adaptive and reduces when the note length is small, so for each note
the quantization value is different. But there is an upper limit for the quantization value, and that value can be set by
.the user as "max. quantization

For example, if some note is long - say, half note, and the max. quantization is set to 8th, then the note will be
.quantized with the 8th-note grid, not the half- or quarter-note grid as it supposed to be by the algorithm
.Such quantization scheme allows to quantize all notes in the score (with different lengths!) adequately

Max. voices

.Sets maximum count of allowed musical voices

Search tuplets

When enabled, this option attempts to detect tuplets and applies the corresponding quantization grid to the tuplet
.chords

Is human performance

If enabled, this option reduces the accuracy of MIDI-to-score conversion in favor of readability. It is useful for
unaligned MIDI files, when no regular quantization grid is provided. For such files the automatic beat tracking
.algorithm is used which tries to detect the bar positions throughout the piece

2x less measure count

The option is active for unaligned MIDI files (when "Is human performance" is checked by default). It halves measure
count obtained in the internal beat tracking operation. It may be convenient when the beat tracking gives 2x more
.frequent bar subdivision than necessary

Time signature

The option is active for unaligned MIDI files. The user can choose an appropriate time signature for the whole piece
if the default detected value is wrong. The option is useful because it handles imported tuplets correctly unlike the
.direct time signature setting from the palette

Split staff

This option is suited mainly for piano tracks - to assign notes to the left or right hand of the performer. It uses
constant pitch separation (the user may choose the pitch via sub-options) or floating pitch separation (depending on
(the hand width - sort of a guess from the program point of view

For drum tracks ("Percussion" sound in the track list) it splits the staff into multiple staves, each of which gets only
one drum pitch (i.e. drum sound). There is also a sub-option to allow/disallow the application of the square bracket
.for the newly created set of drum tracks

Clef changes

Small clefs can be inserted within a staff to keep chords closer to the 5 staff lines. Clef changes depend on the
average pitch of the chord. Tied groups of notes are not broken by the clef insertion (if it occurs, one can report a
.bug for algorithm in importmidi_clef.cpp). This option is available for non-drum tracks only

Simplify durations

Reduces number of rests to form more "simple" note durations. For drum tracks this option can remove rests and
.lengthen notes as well

Show staccato

.Option to show/hide staccato markings in the score

Dotted notes

.Controls whether MuseScore will use dotted notes or ties

Show tempo text

.Shows/hides tempo text markings in the score

Show chord names

.Shows/hides chord names in the score, if any, for XF MIDI file format

Recognize pickup measure

When enabled, this option doesn't change the time signature of the first bar that is shorter than the second bar. It is
.also called anacrusis. This option is only available for all tracks at once

Detect swing


MuseScore tries to detect swing, and automatically replace a pattern of 4th + 8th notes in triplets (for the most
common swing feel, 2:1), or a dotted 8th + 16th pattern (for shuffle, 3:1), with two straight 8ths and a "Swing" or
. "Shuffle" text at the beginning

Master palette

The **Master Palette** is a repository of symbols used to populate the workspaces (Basic, Advanced, and Custom). It is also used to create new Time Signatures and Key Signatures

:To open, use either of the following options

- (Press Shift+F9 (Mac: fn+Shift+F9
- From the menu, select View → Master Palette



The Master palette is divided into sections based on symbol type. Hovering the mouse over an item shows **atool tip** (a short definition in black on yellow background)


:To transfer a Master palette item to a custom palette

- Drag the symbol from the Master Palette window into a custom palette

Note: Except for the Symbols section (below), it is not usual to add items directly to the score from the Master palette: use the workspace palettes instead. However, if desired, items can be added directly using either (i) drag-and-drop or (ii) by selecting one or more notes/rests and double-clicking the item

Symbols

The **Symbols** section of the Master Palette is a large repository of hundreds of musical symbols in addition to those found in the preset workspaces. You can open it from the Master Palette, or directly from the score by using the shortcut



Find a symbol

The symbols are listed under their respective musical font types: use the **font menu** on the bottom right of the box to specify Emmentaler, Gonville or Bravura. You can search for a particular symbol by entering a keyword in the **search box**

Apply a symbol

To add an item to the score from the Symbols section, use any of the following options

- Drag and drop a symbol onto a staff
- Select a note or rest and double-click a symbol

The position of the symbol can be adjusted by dragging or by changing the horizontal / vertical offsets in the **Inspector**. Color and visibility can also be adjusted in the Inspector

Note: Elements from the Symbols section do not follow any positioning rules (in many cases unlike identical elements from other sections of the Master Palette), nor do they affect score playback

Connect symbols

Elements from the Symbols section can be connected to each other on the score page, so that they can be moved as one unit


1. Apply first symbol to the score. Adjust position as required
 2. Double click, or drag-and-drop, a second element onto the first symbol. Adjust position as required
- Drag the first element and the attached element will follow

See also

- [Palettes and workspaces](#)
- [\(Symbols and special characters\)](#) (add musical symbols to text objects)

Note input modes

From version 2.1, you can enter notation using one of several **new note input** modes—in addition to the pre-existing **Step-time** and **Re-pitch** modes. These are accessed by clicking a small dropdown arrow next to the note entry button on the note input toolbar



Step-time

This is the method of note entry that MuseScore has had from the beginning. You enter notes in Step-time mode by choosing a duration using the mouse or keyboard, and then choosing a pitch using the mouse, keyboard, MIDI keyboard or virtual piano.

.For details see [Basic note entry](#)

Re-pitch

Re-pitch mode allows you to correct the pitches of a sequence of notes while leaving their durations unchanged (not to be confused with [Accidental: Respell pitches](#))

.1 Select a note as your starting point

If you are using a pre-2.1 version of the program press **N** to enter note-input mode. This step is optional from 2.1 onwards

.3 Select the **Re-Pitch** option from the **Note input** drop-down menu (or, for pre-2.1 versions, from the note input (toolbar); or use the keyboard shortcut, **Ctrl+Shift+I** (Mac: **Cmd+Shift+I**)

.4 .Now enter pitches using the keyboard, MIDI keyboard or virtual piano keyboard

You can also use the **Re-pitch** function to create a new passage from an existing one of the same sequence of durations —by copying and pasting the latter, then applying Re-pitch

Rhythm

Rhythm mode allows you to enter durations with a single keypress. Combining Rhythm and Re-pitch modes makes for a very efficient method of note entry

.1 .Select your starting point in the score and enter Rhythm mode

.2 Select a duration from the note input toolbar, or press a duration shortcut (numbers 1-9) on your computer keyboard.

A note will be added to the score with the selected duration. In contrast to [Basic note entry](#), pressing the **.** key will toggle dotting or not dotting all subsequent durations. All following rhythms will be dotted until the **.** key is pressed again. Unlike [Basic note entry](#), the dot is to be pressed prior to entering the rhythm

.3 Entering rests is similar to adding dotted notes. Press the **0** key to toggle entering rests. All rhythms entered will be rests until the **0** key is pressed again. This can be used concurrently with dotted notes

.4 .Continue pressing duration keys to enter notes with the chosen durations

.5 .Now use [Re-pitch mode](#) to set the pitches of the notes you just added

(Real-time (automatic

The Real-time modes basically allow you to perform the piece on a MIDI keyboard (or MuseScore's [virtual piano keyboard](#)) and have the notation added for you. However, you should be aware of the following limitations which currently apply

- It is not possible to use a computer keyboard for Real-time input
- You cannot enter tuplets or notes shorter than the selected duration
- You cannot enter notes into more than one voice at a time

However, these restrictions mean that MuseScore has very little guessing to do when working out how your input should

.be notated, which helps to keep the Real-time modes accurate

In the automatic version of Real-time input, you play at a fixed tempo indicated by a metronome click. You can adjust the tempo by changing the delay between clicks from the menu: Edit → Preferences... → Note Input (Mac: MuseScore → Preferences... → Note Input

- .1 .Select your starting position in the score and enter Real-time (automatic) mode
- .2 .Select a duration from the note input toolbar
- .3 .(Press and hold a MIDI key or virtual piano key (a note will be added to the score
- .4 .Listen for the metronome clicks. With each click the note grows by the selected duration
- .5 .Release the key when the note has reached the desired length

The score stops advancing as soon as you release the key. If you want the score to continue advancing (e.g. to allow you to enter rests) then you can use the [Real-time Advance shortcut](#) to start the metronome

(Real-time (manual

In the manual version of Real-time input, you have to indicate your input tempo by tapping on a key or pedal, but you can play at any speed you like and it doesn't have to be constant. The default key for setting the tempo (called "Real-time Advance") is Enter on the numeric keypad (Mac: fn+Return), but it is highly recommended that you change this to a MIDI key (or MIDI pedal (see [below](#)

- .1 .Select your starting position in the score and enter Real-time (manual) mode
- .2 .Select a duration from the note input toolbar
- .3 .(Press and hold a MIDI key or virtual piano key (a note will be added to the score
- .4 .Press the Real-time Advance key. With each press the note grows by the selected duration
- .5 .Release the note when it has reached the desired length

Real-time Advance shortcut

The Real-time Advance shortcut is used to tap beats in manual Real-time mode, or to start the metronome clicks in automatic Real-time mode. It is called "Real-time Advance" because it causes the input position to move forward, or "advance", through the score

The default key for Real-time Advance is Enter on the numeric keypad (Mac: fn+Return), but it is highly recommended that you assign this to a MIDI key or MIDI pedal via MuseScore's MIDI remote control. The MIDI remote control is available (from the menu: Edit → Preferences... → Note Input (Mac: MuseScore → Preferences... → Note Input

Alternatively, if you have a USB footswitch or computer pedal which can simulate keyboard keys, you could set it to simulate Enter on the numeric keypad

See also

- [Note input](#) •
- [Copy and paste](#) •

External links

- [\(Video: Semi-Realtime MIDI Demo Part 1: New note entry modes](#) [↗](#) (available as of MuseScore 2.1 •
- [\(Introduction to the new Repitch Mode](#) [↗](#) (YouTube •

Noteheads

A range of alternative noteheads – in addition to the "normal" – can be found in the **Note Heads** palette of the [Advanced](#) ([workspace](#) and via the [Inspector](#) (see [Change notehead group](#), below

Note: The design of the notehead may vary depending on the music font selected (Emmentaler, Gonville or Bravura). Those in the palette are displayed as half notes in Bravura font

Notehead groups

:MuseScore supports a number of notehead styles

- Normal:** A standard notehead •

- **Crosshead** (Ghost note): Used in percussion notation to represent cymbals. It also indicates muted and/or percussive effects in stringed instruments such as the guitar
- **Diamond**: Used to indicate harmonic notes in instruments such as the guitar, violin etc
- **Slash**: Used to notate rhythmic values
- **Triangle**: Used in percussion notation
- **Shape notes**: Do, Re, Mi, Fa, Sol, La, Ti
- **Circle cross**: Used in percussion notation
- **Alternative Brevis**: Used in early music notation
- **(Brackets (Parentheses))**: When applied, these go around the existing note (or accidental

Change notehead group

:To change the *shape* of one or more noteheads in the score, use one of the following

- Select one or more notes and double click a notehead in a palette
- Drag a notehead from a palette onto a note in the score
- Select one or more notes and change the notehead in the Inspector, using the drop-down list under **Note** → **Head** → **(group)** (not supported for drum staves)

Change notehead type

Occasionally you may need to change the *apparent* duration of a notehead—i.e. *notehead type*—without altering its *actual*, underlying duration

- Select one or more notes .1
- Chose one of the following options from the Inspector under **Note** → **Head type** .2
 - **Auto**: Automatic, i.e, apparent duration = actual duration
 - **Whole**: Whole notehead, regardless of actual duration
 - **Half**: Half notehead, regardless of actual duration
 - **Quarter**: Quarter notehead, regardless of actual duration
 - **Breve**: Breve notehead, regardless of actual duration

Shared noteheads

:When two notes in *different voices*, but of the same written pitch, fall on the same beat, one of two things may happen

- The notes may *share* the same notehead
- The notes may be *offset*: i.e. arranged side by side

:MuseScore follows standard music notation practice as follows

- Notes with stems in the same direction do not share noteheads
- Dotted notes do not share noteheads with undotted notes
- Black notes do not share noteheads with white notes
- Whole notes never share noteheads

Note: If two unison notes occur in the *same* voice they are always offset

Change offset noteheads to shared

:Offset noteheads can be turned into shared noteheads in one of two ways


- Make the smaller-value notehead invisible by selecting it and using the keyboard shortcut `v` (or unchecking the ("Visible" option in the Inspector)
- Alter the notehead type of the shorter-duration note to match the longer one by switching "Head type" in the "Note" section of the Inspector

Examples of notehead sharing

In the first example below, the notes of voices 1 and 2 share noteheads by default, because they are all black, .1
:undotted notes



:By contrast, in the next example, white notes cannot share noteheads with black notes, so are offset to the right .2



To create a shared notehead, make the black eighth note invisible or change its head type to match that of the white note (as explained above)



Remove duplicate fret marks

In certain cases, a shared notehead, when pasted to atablature staff, may result in two separate fret marks on adjacent strings. To correct this, make any extraneous tablature notes invisible by selecting them and using the keyboard shortcut .(v (or by unchecking the "visible" option in the Inspector

External links

- [Shape notes](#) ↗ at Wikipedia •
- [Ghost notes](#) ↗ at Wikipedia •

Parts

.MuseScore not only allows you to create and print the full score but also the individual instrumenparts


Note: In the current version of MuseScore, *only one part can be generated per single staff* (or grand staff or staff/TAB .system). If you want to create a part for a particular voice, you need to ensure that it has its own staff as well

Set up all parts at once

This is the most straightforward method. Parts are generated on a one-to-one basis from the corresponding Instruments in .the score

;.From the menu, select File → Parts .1

Click the New All button (parts are named with the instrument name, and a number added to differentiate parts that .2 ;(have the same label in the main score



.Click OK .3


.The parts can now be accessed by clicking on tabs above the document window

Define specific parts


This method allows you to generate *specific* parts (rather than all-at-once), or to alter a previous parts set-up. It also allows you to specify multi-instrument parts, and define part names differently from the corresponding instruments, if needed.

.The following instructions use a string quartet as an example, but the same principles apply for any other ensemble

;...From the menu, select File → Parts .1




";In the Parts window click New to create a "part definition" .2




In the right pane, type the words you want to use for the "Part title" (this also serves for the corresponding part of the .3
;filename when exporting

Pick the instrument that you want to appear in your part by marking the relevant box in the right-hand pane. Usually, .4
you only want one instrument per part, but sometimes you might need a part that includes more than one instrument
;(such as multiple percussion staves). MuseScore allows you to mark as many instruments per part as you need



;Repeat steps two through four (above) for each part as needed .5



.Once you're done, click OK to dismiss the Parts window .6

You have now finished setting up the parts. You do not need to do this again, unless you add or remove an instrument from your full score

Delete a Part

- ;(...Open the Parts dialog (File → Parts .1
- ;Select the relevant Part in the "Select Part" section .2
- .Press Delete .3

Export the parts

- ...From the menu, select File → Export Parts .1
- ;(Navigate to the place you want them to be exported to and select the file format (PDF is the default .2
- ;(For filename just enter whatever prefix is useful for all parts, or leave the default (the filename of your score .3
- .Click OK .4

This will generate files with the names "<title>" + "-" + "<part name>.<extension>". In addition, when exporting as PDF, this will also generate "<title>" + "-Score_And_Parts.pdf"

Save the parts

Parts and score are "linked", which means that any change to the content in one will affect the other, but changes to the layout will not. When you have the parts created, they are saved along with the score (if you open the score you have (tabs for the score and every part you created

:However, if you wish to save a part individually

- ;Make sure the part is "active." Select its tab if not .1
- ...From the menu, select File → Save As .2

Print a part

- ;Make sure the part is "active." Select its tab if not .1
- .From the menu, select File → Print to open the print dialog .2

Plugins

Overview

Plugins are small pieces of code that add a particular feature to MuseScore. By enabling a plugin, a new menu option will be appended to the Plugins menu in MuseScore to accomplish a given action on the score or a part of it.

Some plugins come pre-installed with MuseScore—see [below](#). You can find many more plugins in the [plugin repository](#). Some plugins there work with MuseScore 2; others will only work with older versions of MuseScore, some work with either. To tell one from the other: for MuseScore 2.x the plugin code files have an extension of .qml, for older versions, it is .js.

Installation

Note that some plugins may require the installation of other components (fonts, e.g.) to work. Check the plugin's documentation for more information.

Most plugins are provided as ZIP archives, so download the plugin's .zip file and uncompress it to one of the directories mentioned below. If a plugin is provided directly as an (unzipped) .qml file, simply download and place into one of these directories.

Once a plugin is installed, it needs to be enabled in the Plugin Manager in order to use it—see [below](#).

Windows

MuseScore looks for pre-installed plugins in %ProgramFiles%\MuseScore 2\Plugins (or %ProgramFiles(x86)%\MuseScore 2\Plugins for the 64-bit versions) and in %LOCALAPPDATA%\MuseScore\MuseScore 2\plugins on Vista, Seven and 10 or C:\Documents and Settings\USERNAME\Local Settings\Application Data\MuseScore\MuseScore 2\plugins (adjusted to your language version) on XP.

To install new plugins, the above folders should **not** be used or modified. Instead you can add other plugins to %HOMEPATH%\Documents\MuseScore2\Plugins, or specify a different folder to look for plugins in MuseScore's [Preferences](#).

macOS

On macOS, MuseScore looks for pre-installed plugins in the MuseScore bundle in Applications/MuseScore 2.app/Contents/Resources/plugins (to reveal files in the app bundle, right click on MuseScore 2.app and choose "Show package contents") and in ~/Library/Application Support/MuseScore/MuseScore 2/plugins.

To install new plugins, the above folders should *not* be used or modified. Instead you can add other plugins to ~/Documents/MuseScore2/Plugins, or specify a different folder to look for plugins in MuseScore's [Preferences](#).


Linux

In Linux, MuseScore looks for plugins in /usr/share/mscore-2.0/plugins and in ~/.local/share/data/MuseScore/MuseScore 2/plugins.

To install new plugins, the above folders should *not* be used or modified. Instead you can add other plugins to ~/Documents/MuseScore2/Plugins, or specify a different folder to look for plugins in MuseScore's [Preferences](#).


Enable/disable plugins


To be able to access the installed plugins from the Plugins menu, they need to be enabled in the Plugin Manager.



Create/edit/run plugins

:It is possible to create new or edit existing plugins and run them via the Plugin Creator





Here also the documentation of all available elements can be found

Plugins installed by default

.Some plugins come pre-installed with MuseScore, but they are not enabled by default. See [above](#) to enable plugins

ABC Import

This plugin imports [ABC](#) text from a file or the clipboard. Internet connection is required, because it uses [an external web-service](#) for the conversion, which uses [abc2xml](#) and gets send the ABC data, returns MusicXML and imports that .into MuseScore

Break Every X Measures

This plugin enters line breaks in the interval you select on the selected measures or, if no measures are selected, the entire score. It is no longer being distributed and has been replaced by Edit → [Tools](#) → [Add/Remove Line Breaks](#). If you ever .used an early beta version of MuseScore 2, though, you may still see the plugin left over

Notes → Color Notes

This demo plugin colors notes in the selected range (or the entire score), depending on their pitch. It colors the note head of all notes in all staves and voices according to the Boomwhackers convention. Each pitch has a different color. C and C# .have a different color. C# and Db have the same color

To color all the notes in black, just run that plugin again (on the same selection). You could also use the '[Remove Notes Color](#)' plugin for this

Create Score

This demo plugin creates a new score. It creates a new piano score with 4 quarters C D E F. It's a good start to learn how .to make a new score and add notes from a plugin

helloQml

.This demo plugin shows some basic tasks

Notes → Note Names

This plugin names notes in the selected range or the entire score. It displays the names of the notes (as `staff text`) as per MuseScore's [language settings](#), for voices 1 and 3 above the staff, for voices 2 and 4 below the staff, and for chords in a comma separated list, starting with the top note

Panel

.This demo plugin creates a GUI panel

random

.Creates a random score

random2

Creates a random score too

run

.This demo plugin runs an external command. Probably this will only work on Linux

scorelist

.This test plugin iterates through the score list

ScoreView

Demo plugin to demonstrate the use of a ScoreView

Walk

This test plugin walks through all elements in a score

See also

[Tools](#) •

Preferences

(...You can customize many of MuseScore's default behaviors via the menu `Edit → Preferences...` (Mac: `MuseScore → Preferences`


:The Preferences dialog has multiple tabs



.Reset All Preferences to Default will reset all preferences to the ones MuseScore had when you installed it

.Cancel will close the dialog without applying changes


General



:Here you can define

- Program Start:** Tick the boxes as appropriate to specify which **score** and what **panels** (Play Panel, Navigator, Start Center) you want to see when MuseScore opens
- Folders:** Specify the default folders for score files, style files, custom score templates, plugins, additional SoundFonts and images
- Language:** Chose the language used by the program. Translations may be updated from here too. Note that language translation updates can also be done via the menu: Help → Resource Manager
- Theme / Style** (prior to version 2.1): Specify a dark or light theme and the size of icons
- Auto Save:** How frequently the program autosaves
- OSC Remote Control**


Canvas



Use Canvas to set your preferred color and wallpaper for the score background and paper. The default "Background" is .grey (RGB 221, 221, 221; Alpha 221) and the default "Paper," white

- Background:** Use this to set the color or background of the score pages. Select "Color" then click on the bar to the right and make a choice from the color picker; or select "Wallpaper," click on the file icon and set a background image.
- Paper:** Sets the color or background of the score pages. Controls identical to "Background" (above).
- Scroll Pages:** This defines the way that the pages are laid out in the score. Choose "Horizontally" for a row layout, or "Vertically" for a column layout.
- Miscellaneous:** "Draw antialiased" (the default option) makes diagonal lines and edges of shapes look smoother. "Proximity for selecting elements" controls the distance the mouse may be from an object and still act on it. Smaller numbers require more precision, making it harder to click on small objects. Larger numbers are less precise, making it harder not to click on nearby objects unintentionally. Choose a comfortable working value.

Note input



:On this tab there are note input and MIDI remote control preferences. Here the following can be set

Note Input

- Enable MIDI Input:** Leave checked to allow MIDI input of notes.
- Color notes outside of usable pitch range:** For details, see [Coloring of notes outside an instrument's range](#) and [Usable pitch range](#) (Staff properties: all staves).
- Delay between notes in automatic real-time mode** (as of version 2.1): See [Real-time \(automatic\)](#).
- Play notes when editing:** When ticked, MuseScore *sounds* the note when it is entered or selected. Tick "Play whole chord when adding note," if you want to hear *all* the notes of a chord when it is added to. You can also edit the "Default duration".

MIDI Remote Control

Midi Remote Control allows you to use certain keys on your MIDI keyboard to enter notes and rests and to select note durations, without involving the computer mouse or (computer) keyboard. The default setting is off.

To assign a command to a MIDI key


- Ensure that "MIDI Remote Control" is checked (your MIDI keyboard should be connected before opening the program).
- Click the red button next to the option you wish to assign a MIDI key to: the red button now lights up.
- Press a MIDI keyboard key. The red button becomes unlit and the green button lights up instead. The MIDI key has now been assigned to the desired option.
- Repeat "2" and "3" to assign other keys.

Once you have defined your key settings you can use the MIDI keyboard to control note input operations. You can verify your key settings by observing the MuseScore [Note Input toolbar](#) while pressing the MIDI keys.

To temporarily deactivate Midi Remote Control: uncheck "Midi Remote Control": all MIDI input key action buttons are now greyed out. *Note:* Your key assignments are always saved between MuseScore sessions and are not affected by .deactivation

Notes: (1) The "Clear" option turns off all the green buttons for the *current* MuseScore session but all the user-recorded MIDI key settings are retained and will be reloaded on the next session. (2) A MIDI key setting that is activated cannot afterwards be turned off, and the green button will always remain lit: however it can be overwritten with a different MIDI key by using the red button again. (3) If the same MIDI key is accidentally assigned to more than one option, then all the ."(associated green buttons remain lit although only one will work. To fix, see "(2


Score



Score preferences include

- (Default instrument list files (two may be selected
- Default style for score and parts
- Default zoom

I/O



This enables you to set the audio interface (API) and specify the device to be used for audio playback: e.g. built-in .speakers/headphones, USB headset, wireless, etc

MIDI Input/Output/Output Latency


When an external MIDI input device is connected, its identifier appears in **MIDI Input**. As of MuseScore 2.2, when the device is connected *for the first time*, you also need to select the correct **MIDI Output** option in order to enable note input and correct audio playback (e.g. in Windows, this might be "MMS<device name>"): then close and reopen the program to .confirm the changes

Versions of MuseScore prior to 2.2 only have the "MIDI Input" option. The correct MIDI output is automatically specified as .long as the MIDI input device is connected correctly

Jack Audio Server

.Check these options as required if using the [JACK](#)  Audio Connection Kit


Import



:These settings determine how files from other sources are imported

- Using either the built in MuseScore style or a style you choose •
- Guitar Pro and Overture character sets •
- MusicXML layout options •
- Shortest note in MIDI files •


Export



:These settings determine how MuseScore files are exported

- PNG/SVG image resolution (in DPI) and whether to use transparent background
- Whether to expand repeats in exported MIDI files
- Digital audio sample rate
- (MP3 bitrate (as of MuseScore 2.1
- Whether to export the layout and how to export system and page breaks to MusicXML

Shortcuts




Every action possible with MuseScore is listed, with the associated shortcut if it exists. To define a new shortcut, select an existing entry in the list and click Define... (or just double click the entry), then enter the new shortcut using up to four keys. You can also reset any shortcut in the list to its default value, or clear a shortcut you select. Shortcuts listed in preferences appear next to their associated commands in the menus

Note: Some shortcuts, including default ones, may not work with some keyboards

The list of shortcuts can be printed out or exported to other media (pdf etc.) using the Print button in the bottom right of the

.window

Update



.This sets whether MuseScore will check for updates at startup


.Updates may be checked manually in Help → Check for updates

See also

- [Keyboard shortcuts](#)
- [Language settings and translation updates](#)
- [Update checking](#)

Recovered files

If MuseScore or your computer should crash, or if power is lost, a pop-up message upon restarting MuseScore will ask if you wish to restore the previous session



If you click No, any work from your previous session will be lost. If you click Yes, MuseScore will attempt to recover the files that were open

Behavior of saving after session recovery

When MuseScore recovers files after a crash, it renames them with the full path name added in front of the original file name. This very long name will appear in the tab(s) above the active score window. On some operating systems, when a user saves any of these recovered files, it will be saved in the folder in which the program itself is running. **This is not necessarily the same directory in which the scores were saved when they were created. You may not be able to locate the revised file in the usual folder**

To avoid this, **do not use "Save"** the first time you save a recovered file. Use the **"Save As..."** menu item **before** making any revisions to the score, to save each recovered file under either its original name or a new name. This will open a window to allow you to navigate to the correct folder and directory. **This is important in order to ensure that the file is saved to the folder in which you expect to find it later**

Finding recovered files

In the event that "Save" is used instead of "Save As..." with a recovered file, you will have to find the files in your computer. The actual location of those files will vary, depending on your operating system, and in which directory MuseScore is installed.

For Windows 7, with a default installation of MuseScore to the x86 program files directory, recovered files are auto-saved
(to C:\Program Files (x86)\MuseScore 2\bin (actually %ProgramFiles(x86)%\MuseScore 2\bin

For Windows 10, look in C:\Users\[User Name]\AppData\Local\VirtualStore\Program Files (x86)\MuseScore 2\bin
(actually%LOCALAPPDATA%\VirtualStore%\ProgramFiles(x86):-3%\MuseScore 2\bin

You may need to run a system-wide search in order to find files saved directly after a session recovery. Use keywords from the original file name as well as wildcards, and specify the date modified

See also

[Save/Export/Print](#)

External links

[How to recover a backup copy of a score](#)

Score properties


The **Score Properties** dialog contains the document meta tags such as "workTitle," "Composer," "Copyright" etc. To view the dialog

- .1 ;Make sure that the applicable score or instrument part is the active tab
- .2 (From the menu, select File → Score Properties (File → Info... in versions earlier than 2.0.3


Several meta tags are generated automatically when you create a score using the [New Score Wizard](#), and others may be added later. Meta tags can also be incorporated into a header or footer if required—see [below](#)

Edit meta tags

- .1 ;Make sure that the applicable score or instrument part is the active tab
- .2 (From the menu, select File → Score Properties (File → Info... in versions earlier than 2.0.3



;Edit the text of the various meta tags as required .3
 ;To add another meta tag, click on the New button. Fill in the "New tag name" field and pressOK .4



Preexisting meta tags

Every score has the following fields available in Score Properties. Some are automatically filled in on score creation, while others will be empty unless specifically changed. The first four items in the following list are not user-modifiable, and cannot be used in the header or footer (they are not really meta tags)

- **File Path:** The score file's location on your Computer (2.0.3 and later)
- **MuseScore Version:** The version of MuseScore the score was last saved with
- **Revision:** The revision of MuseScore the score was last saved with
- **API-Level:** The file format version
- **arranger:** (empty)
- **composer:** As entered in the New Score Wizard (which is also used to fill the composer text in the top vertical frame—**be aware that later changes to one are not reflected in the other**)
- **copyright:** As entered in the New Score Wizard. Copyright info appears as seemingly uneditable text at the bottom of every page of a score, but it can be edited or removed by changing the value here
- **creationDate:** Date of the score creation. This could be empty, if the score was saved in test mode (see Command line options)
- **lyricist:** As entered in the New Score Wizard (which is also used to fill the corresponding lyricist text in the top vertical frame—**be aware that later changes to one are not reflected in the other**)
- **movementNumber:** (empty)
- **movementTitle:** (empty)
- **originalFormat:** This tag exists only if the score got imported and then contains the format the score got imported from (see file formats)
- **platform:** The platform the score was created on: "Microsoft Windows", "Apple Macintosh", "Linux" or "Unknown". This might be empty if the score was saved in test mode
- **poet:** (empty)
- **source:** May contain a URL if the score was downloaded from saved to MuseScore.com
- **translator:** (empty)
- **workNumber:** (empty)
- **workTitle:** As entered in the New Score Wizard (which is also used to fill the corresponding title text in the top vertical frame—**be aware that later changes to one are not reflected in the other**)

When working on multiple scores that belong to one larger work, the nomenclature is like this: **workNumber** and **workTitle** are the number and title of the larger work (e.g. opus 8, “Le quattro stagioni” (The four seasons) by Antonio Vivaldi), **movementNumber** is the number of the movement you’re working on (e.g. 3 for Autumn) and **movementTitle** is its title (“L’autunno”). It is customary, when using the New Score Wizard, to create a work with the **movementTitle** as title (even though it ends up in **workTitle** then) and, directly after creating the score, fixing up this information in the Score Properties dialogue. This ensures that the title frame of the printed score contains the information you expect but the .metadata is also correct

:Every *part* additionally has the following meta tag, generated and filled on part creation


partName: Name of the part as given on part creation (which is also used to fill the corresponding part name text in **Header/Footer** .(the top vertical frame—**be aware that later changes to one are not reflected in the other**

Header/Footer

:To show the content of one or more meta tags in a header or footer for your score/part

;Make sure that the correct score or instrument part is the active tab .1

;From the menu, select Style → General... → Header, Footer, Numbers .2



If you hover with your mouse over the Header or Footer text region, a list of macros will appear, showing their .meaning, as well as the existing meta tags and their content

Special symbols in header/footer	
\$p	- page number, except on first page
\$N	- page number, if there is more than one page
\$P	- page number, on all pages
\$n	- number of pages
\$f	- file name
\$F	- file path+name
\$d	- current date
\$D	- creation date
\$m	- last modification time
\$M	- last modification date
\$C	- copyright, on first page only
\$c	- copyright, on all pages
\$S	- the \$ sign itself
\$tag:	- meta data tag, see below
Available meta data tags and their current values:	
arranger	-
composer	-
copyright	-
creationDate	- 2016-05-02
lyricist	-
movementNumber	-
movementTitle	-
platform	- Microsoft Windows
poet	-
source	-
translator	-
workNumber	-
workTitle	- Test

;Add tags (e.g. \$:workTitle:) and macros (e.g. \$M) to the appropriate boxes, as required .3

;Click Apply to see how the header or footer looks in the score. Make corrections to the dialog if required .4

;If an instrument part is in the active tab, clickApply to all parts, if you want to apply these settings to all the score parts .5

.Click OK to assign the header or footer and exit the dialog .6


See also

- [Layout and formatting: Header and footer](#) •
- [Command line options: Test mode](#) •

Staff properties

The **Staff Properties** dialog allows you to make changes to the display of **astaff**, adjust its tuning and transposition, :change instrument etc. To open

-Right-click on a staff and select Staff Properties •



.Staff Properties dialog, as of version 2.1

:For practical purposes, there are four different types of staff

.1a. **Standard staff I.** A pitched staff used for most instruments except fretted, plucked-string ones

1b. **Standard staff II.** A pitched staff containing a *fretted, plucked-string instrument*, with options to set the number of instrument strings and tuning

Tablature staff. A staff containing a *fretted, plucked-string instrument*, which displays music as a series of fret-marks on .2 strings. Also contains options to set the number of instrument strings and tuning

Percussion staff. A pitched staff for percussion instruments .3

It is possible to change one type of staff into another using the [Instruments](#) dialog, as long as the original staff is loaded with the right instrument. For example, in order to change a standard staff to tablature, it must contain a plucked-string instrument. Similarly, to change a standard staff to a percussion staff you need to ensure that it has an appropriate percussion instrument loaded and so on

Most options in the Staff properties dialog are common to all staves, but each type also has one or two specific options of its own

Staff Properties: all staves

:The following Staff Properties options are common to *all* staves

Lines

.The number of lines making up the staff

Line Distance

The distance between two staff lines, measured in *spaces* (abbr.: *sp*). If you set this to a higher value, the lines are spaced more widely apart; a lower value and they are closer together. It is *not* recommended to change this value for the **standard** group, for which the default distance is 1.0 (instead, change the actual size of the *sp* unit in [Page settings](#)); (other groups may have different default values (for instance, tablature usually has a line distance of 1.5 *sp*

Extra distance above staff

Increases or decreases the distance between the selected staff and the one above *in all systems*. However, it does not apply to the top staff of a system, which is controlled by the minimum/maximum system distance (see [Layout and formatting: Style → General... → Page](#)

:Alternatively, you can alter the "**Extra distance above staff**" directly from the score page

.Press and hold the Shift key .1

.Click on an empty space in a staff and drag it up or down with the mouse .2

Note: To alter the spacing above just *one* staff line in a particular system, see [Breaks and spacers](#)

Scale

Changes the size of the *selected* staff and all associated elements, as a percentage (to adjust the *overall* score size, use [Scaling](#) from the Layout → Page Settings... menu

Never Hide

Never hide this staff. This overrules any "Hide empty staves" setting in [Layout and Formatting: Style → General... → Score](#)

Show clef

.Whether the staff clef will be shown

Show time signature

.Whether the staff time signature(s) will be shown or not

Show barlines

.Whether the staff barlines will be shown

Hide system barline

.Show/hide barline at left-hand edge of the staff

Do not hide if system is empty

Never hide this staff, even if the entire system is empty. This overrules any "Hide empty staves" setting in [Layout and](#)

Small staff

Create a reduced-size staff. You can set the default from the menu in [Layout and Formatting: Style → General... → Sizes](#)

Invisible staff lines

.Make staff lines invisible

Staff line color

.Use a color picker to change the color of the staff lines

Part name

.(The name of the part. This is also displayed in the [Mixer](#) and the [Instruments](#) dialog (I

Instrument

The instrument loaded in the **Instruments** (I) or [Select Instrument](#) dialog. The sound associated with this instrument can .be changed, if desired, in the [Mixer](#)

Long instrument name

Name displayed to the left of the staff in the first system of the score. The long instrument name may also be edited .*directly as a text object* (as of version 2.1): see [Text editing](#)

Short instrument name

Name displayed to the left of the staff in subsequent systems of the score. The short instrument name may also be edited .*directly as a text object* (as of version 2.1): see [Text editing](#). Editing affects *all* occurrences in the score

Usable pitch range

- **.Amateur:** Notes outside this range will be colored olive green/dark yellow in the score
- **.Professional:** Notes outside this range will be colored red in the score

To disable out-of-range coloration of notes: From the menu, select [Edit → Preferences...](#) (Mac: [MuseScore → Preferences...](#)), ".click on the "Note Input" tab, and uncheck "Color notes outside of usable pitch range

.See also, [Coloring of notes outside an instrument's range](#)

Transpose written pitches (as of version 2.1) / Play transposition

This option ensures that the staves of transposing instruments display music at the correct written pitch. Set the transpose in term of a musical interval (plus octave if required) up or down. For plucked-string instruments such as the guitar, this .property can be used to create the effect of applying a capo

(Navigation arrows (as of version 2.1

.Use the ↑ and ↓ buttons, at the bottom left of the Staff Properties window, to navigate to the previous or next staff

Staff Properties: plucked strings only

,Staves of fretted, plucked-string instruments have a few extra options in addition to those listed [above](#)

Number of strings

.Displays the number of instrument strings

...Edit String Data

.This button opens a dialog box which allows you to set the number and tuning of strings. See [Change string tuning](#)

Advanced Style Properties

Clicking the [Advanced Style Properties...](#) button opens a window giving access to advanced display options for the staff. These .will vary depending on the [staff type](#) chosen: see the relevant sections below for details

Change staff type

At the bottom of the [Advanced Style Properties](#) dialog there are a number of buttons which allow you to easily change the :following

- *.The number of lines displayed by a percussion staff*

The staff type of a plucked-string instrument For example, you can change from standard staff to tablature and vice •

.versa, or select from a number of tablature options

;"Make a selection from the drop-down list labelled "Template .1

;Press < Reset to Template .2

.(Press OK to accept the changes and exit the dialog (orCancel to cancel the operation .3

Standard and Percussion staff options

Show key signature

.Whether the staff key signature will be shown

Show ledger lines

.Whether the staff ledger lines will be shown

Stemless

.If checked, staff notes will have no stem, hook or beam

Tablature staff options

Upside down

If not checked, the top tablature line will refer to the highest string and the bottom tablature line will refer to the lowest string (most common case). If checked, the top tablature line will refer to the lowest string and the bottom tablature line .(will refer to the highest line (used in Italian style lute tablatures

Tablature staff options: Fret Marks

Fret marks are the numbers or letters used to indicate the location of notes on the fingerboard. The following group of :properties define the appearance of fret marks

Font

The font used to draw fret marks. As of version 2.1, 8 fonts are provided supporting all the necessary symbols in 8 different styles (modern Serif, modern Sans, Renaissance, Phalèse, Bonneuil-de Visée, Bonneuil-Gaultier, Dowland, Lute .(Didactic

Size

.Font size of fret marks in typographic points. Built-in fonts usually look good at a size of 9-10pt

Vertical offset

MuseScore tries to place symbols in a sensible way and you do not usually need to alter this value (set to 0) for built-in fonts. If the font has symbols not aligned on the base line (or in some other way MuseScore does not expect), this property allows you to move fret-marks up (negative offsets) or down (positive offsets) for better vertical positioning. .Values are in *sp*

Numbers / Letters


Whether to use numbers ('1', '2'...) or letters ('a', 'b'...) as fret marks. When letters are used, 'j' is skipped and 'k' is used .for the 9th fret

On lines / Above lines

.Whether marks should be placed **on** the string lines or **above** them

Continuous / Broken


.Whether string lines should pass 'through' fret marks or should stop at them :Example of numbers on broken lines



:Example of letters above continuous lines



:(Example of 'upside down' tablature (same contents as number example above



Show back-tied fret marks

.If unticked, only the first note in a series of tied notes is displayed. If ticked, all notes in the tied series are displayed

Show fingerings

.From version 2.1, tick to allow the display of fingering symbols applied from a palette

Tablature staff options: Note Values

.This group of properties defines the appearance of the symbols indicating note values

Font

The font used to draw the value symbols. Currently 5 fonts are provided supporting all the necessary symbols in 5 different styles (modern, Italian tablature, French tablature, French baroque (headless), French baroque). Used only with the *Note symbols* option

Size

.Font size, in typographic points. Built-in fonts usually look good at a size of 15pt. Used only with the *Note symbols* option


Vertical offset

Applies only when *Note symbols* is selected (see below). Use negative offset values to raise the note value symbols, positive values to lower them

:Shown as

(None: No note value will be drawn (as in the examples above) •

Note symbols: Symbols in the shape of notes will be drawn above the staff. When this option is selected, symbols are drawn **only** when the note value changes, without being repeated (by default) for a sequence of notes all of the same value. E.g



Stems and beams: Note stems and beams (or hooks) will be drawn. Values are indicated for each note, using the same typographic devices as for a regular staff; all commands of the standard Beam Palette can be applied to these beams too. E.g



:Repeat

.If several notes in sequence have the same duration, you can specify if and where to repeat the same note symbol. i.e

- Never •
- At new system •
- At new measure •

Always •

.(Note: This option is only available if "Shown as: Note symbols" is selected (see above

:Stem style

.Beside staff: Stems are drawn as fixed height lines above/below the staff •

.Through staff: Stems run through the staff to reach the fret marks •

.(Note: This option is only available when "Shown as: Stems and Beams" is selected (see above

:Stem position

.Above: Stems and beams are drawn above the staff •

.Below: Stems and beams are drawn below the staff •

Note: This option is only available when "Shown as: Stems and Beams" and "Stem style: Beside staff" is selected (see
.(above

:Half notes

None •

As short stems •

As slashed stems •

Note: This option is only available when "Shown as: Stems and Beams" and "Stem style: Beside staff" is selected (see
.(above

Show rests

Whether note symbols should be used to indicate also the rests; when used for rests, note symbols are drawn at a slightly
.lower position. Used only with the *Note symbols* option

Preview

.Displays a short score in tablature format with all the current parameters applied

Change instrument

You can change any instrument in a score to a different instrument at any time. The following method updates instrument
.sound, staff name, and staff transposition all at once

...Right-click on an empty part of any measure OR on the instrument name and choose Staff Properties .1

;"Click on Change Instrument... (under "Part Properties .2

;Choose your new instrument and click OK to return to the Staff Properties dialog .3

.Click OK again to return to the score .4

.Not to be confused with Mid-staff instrument change

External links

.[How to turn a staff into an ossia](#)  •

Tools


.A number of useful commands can be found in the Edit → Tools submenu

Add / Remove system/line breaks

:This tool adds or removes system breaks (**Line breaks** prior to version 2.2) over *all* or *part* of the score

.Select a range of measures: if no selection is made, the command is applied to the whole score .1

.Chose Edit → Tools → Add/Remove System (Line) Breaks.... The following dialog appears .2



.Chose one of the following options .3

- .Break systems/lines every X (select number) measures ◦
- .Add system/line breaks at the end of each system ◦
- .Remove current system/line breaks ◦
- .Press OK .4

Explode

The **explode** command allows you to select a passage of music *in a single staff* and split (explode) the chords into their constituent notes. The top note of each chord is retained on this "source staff" while lower notes are moved to subsequent staves. *Explode only affects notes in voice 1*

Note: If the desired passage also contains notes in other voices apart from voice 1, you should, instead, cut and paste each voice to a separate staff with the help of the selection filter

.To explode a section of the score

- .Make sure all notes to be exploded are in voice 1 .1
- Ensure that there are enough staves underneath the "source staff" to receive the exploded notes. Create extra staves if necessary in the Instruments dialog .2
- .Chose one of two options .3
- Select a range of measures in the "source staff": this allows all notes to be exploded if there are enough staves available ◦
- Select a range of measures that includes both the source staff and also extends downwards to include one or more destination staves: This limits the number of exploded notes to the number of selected staves ◦
- .Chose Edit → Tools → Explode .4

Notes: (1) MuseScore will discard the lowest note(s) of any chord that contains more notes than the number of staves in the selection. (2) If a given chord has fewer notes than the number of destination staves, then notes will be duplicated as needed so that every staff receives a note. (3) Any existing music in the destination staves is overwritten. (4) If you select a partial measure, the explode command will automatically expand it to a full measure

Implode

:"The **Implode** command works in the opposite way to "explode

- .If *several staves are selected*, all voice 1 notes in underlying staves are copied to the top staff •
- .If *just one staff is selected*, all notes in voices 1–4 are combined into voice 1 •

Note: Implode works best if the rhythms of selected underlying staves are similar to that of the top staff—the latter providing the rhythmic template for the operation

Apply implode to multiple staves

- Select a range of measures in a staff and extend this selection downwards to include the other staves to be imploded .1
- .Chose Edit → Tools → Implode .2

.The voice 1 notes of underlying staves are copied to the top staff in the selection

Apply implode to a single staff

- .Select a range of measures in the desired staff .1
- .Chose Edit → Tools → Implode .2

.All selected notes in the staff are now displayed in voice 1

Fill with slashes

:This command fills the selection with slashes, one per beat

;(Select one or more measures .1

.From the menu, select Edit → Tools → Fill With Slashes .2

:If a measure is empty the slashes are added to voice 1, full-sized and centered on the middle line of the staff



Notes: (1) If there are already notes in a measure in the selection, the command will put the slashes into the *first available empty voice*. (2) Voice 2 slashes are full-sized and centered on the middle line of the staff; voices 3 slashes appear *small* and *above* the staff; voice 4 slashes are *small* and *below* the staff. (3) If a measure contains notes in all 4 voices, voice 1 will be overwritten. (4) All slashes are set to not transpose or playback

Toggle rhythmic slash notation

:This command toggles selected notes between normal notes and rhythmic slash notation

;(Select a range of notes or measures (Note: use the [selection filter](#) if you need to exclude certain voices .1

.From the menu, select Edit → Tools → Toggle Rhythmic Slash Notation .2

.The selected noteheads are changed to *slash noteheads* which do not transpose or playback



Slash-notehead notes in *voices one or two* are fixed to the middle staff line; those in *voices three or four* are small ("accent" notation) and fixed above or below the staff



In *percussion staves*, notes in voices 3 and 4 are not converted to small slashes but to small notes above or below the staff



Resequence rehearsal marks

The **Resequence Rehearsal Marks** command allows you to re-order the numbering/lettering of [rehearsal marks](#) if, for any reason, they have got out of sequence. For details see [Automatically resequence rehearsal marks](#)

Copy lyrics to clipboard

:This command, available in MuseScore 2.0.3 and above, copies *all* the lyrics of the score to the clipboard

.From the menu, select Edit → Tools → Copy Lyrics to Clipboard •

See also

- [Breaks and spacers](#) •
- [Rehearsal marks](#) •

New features in MuseScore 2

For an overview about the new features, see [What's New in MuseScore 2](#), [Release notes for MuseScore 2.0](#), [Release notes for MuseScore 2.0.1](#), [Release notes for MuseScore 2.0.2](#), [MuseScore 2.0.2 is released](#), [Release notes for MuseScore 2.0.3](#), [MuseScore 2.0.3 is released](#), [Release notes for MuseScore 2.1](#), [MuseScore 2.1 is released](#), [Release notes for MuseScore 2.2](#), [MuseScore 2.2\(.1\) is released](#), [Release notes for MuseScore 2.2.1](#), [Release notes for MuseScore 2.3](#), [MuseScore 2.3\(.1\) is released](#), [Release notes for MuseScore 2.3.1](#), [MuseScore 2.3.2 is released](#), [Release notes for MuseScore 2.3.2](#) and [Changes for MuseScore 2.0](#)

Documentation of new features are available in the chapter they belong to logically (except the one that is referring to upgrading from 1.x) , but for users coming from 1.x here's a collection of links to be able to see at a glance what can be ..done now

See also

- (Album (→ [Advanced topics](#) •
- (View modes: [Continuous view](#) and [Navigator](#) (→ [Basics](#) •
- (Copy and paste: [Selection filter](#) (→ [Basics](#) •
- (Custom palettes (→ [Advanced topics](#) •
- (Early music features (→ [Advanced topics](#) •
- (Figured bass (→ [Advanced topics](#) •
- (Grid-based movement of symbols and staff text (→ [Text](#) •
- (Image capture (→ [Formatting](#) •
- (Inspector and object properties (→ [Advanced topics](#) •
- (Measure operations: [Split and join](#) (→ [Basics](#) •
- (MIDI import (→ [Sound and playback](#) •
- (Mid-staff instrument change (→ [Sound and playback](#) •
- (Part extraction (new options available) (→ [Advanced Topic](#) •
- (Rehearsal marks: [Automatic next rehearsal mark](#) and [Search for a rehearsal mark](#) (→ [Text](#) •
- (Save/Export (→ [Basics](#) •
- (Staff type properties (→ [Advanced topics](#) •
- (Swing (→ [Sound and playback](#) •
- (Tablature (→ [Advanced topics](#) •
- (Workspace (→ [Basics](#) •
- (Master palette (→ [Advanced topics](#) •
- (Layout and formatting (some options have changed, and there is a new "apply to all parts" feature) (→ [Formatting](#) •
- (Break and spacer: [Section break](#) (→ [Formatting](#) •
- (Selection modes: [Select all similar new options \(same subtype\)](#)(→ [Basics](#) •
- (Create a new score: [start center](#) (→ [Basics](#) •
- (Languages settings and translation updates (→ [Basics](#) •
- (Helping and improve translation (→ [Support](#) •
- (Accidentals: [Respell pitches](#) (→ [Notation](#) •
- (Re-pitch mode (→ [Advanced topics](#) •
- (Tools (→ [Advanced topics](#) •
- (Score Information (→ [Advanced topics](#) •

Upgrade from MuseScore 1.x

How to upgrade MuseScore

Download and install the latest version from the [download](#) page as described at [Installation](#). If you want to remove 1.x, check the [installation](#) page of the 1.x handbook

Installing MuseScore 2 won't uninstall 1.x—both versions can coexist peacefully and can even be used in parallel. So this isn't really an upgrade but an installation of a new and different program

Opening 1.x scores in MuseScore 2

MuseScore 2 significantly improved the typesetting quality to make scores attractive and easier to read. Improvements cover many items such as beam slope, stem height, layout of accidentals in chords and general note spacing. However, this means that sheet music made with MuseScore 1.x looks slightly different from sheet music made with 2.x

.It also means that scores saved with 2.x won't open with 1.x

:To prevent you from accidentally overwriting your 1.x scores, 2.x treats them as an import, which means

- The score gets marked as being modified, even if you haven't change anything
- (On exiting MuseScore you're asked to save the score (as a result from the above
- MuseScore uses the "Save As" dialog to save it, not the "Save" dialog
- MuseScore uses the score's title to create a default filename rather than taking the old filename

Relayout

If you did not manually adjust the layout of a 1.x score, then MuseScore uses the 2.x typesetting engine to layout the score. If you *did* touch the layout of the 1.x score, the individual adjustments you may have made should remain after opening it in MuseScore 2.x, but due to slight changes in the surrounding layout they may still not appear correct in context. If you wish to reset even manual adjustments to use the 2.x typesetting engine throughout, select the complete .(score with the shortcut Ctrl+A (Mac: Cmd+A) and reset the layout with Ctrl+R (Mac: Cmd+R

Getting the sound from MuseScore 1.x

While the sound in 2.x has been much improved, you may still prefer the sound from MuseScore 1.x. In that case, you can :get the 1.x sound in 2.x by downloading the 1.3 SoundFont and add it in 2.x. You can do this in two steps

1. [Download the 1.3 SoundFont named TimGM6mb](#)
2. [Install and use the TimGM6mb SoundFont in 2.0](#)

Support

This chapter describes how to find help using MuseScore: the best places to look, the best way to ask a question on the .forums, and tips for reporting a bug

Helping improve translations

You can help translate the MuseScore software and documentation into your own language, as mentioned in .[Development / Translating](#)

Software translation

1. Ask in the [forum to improve translation](#)
2. Connect to Transifex/MuseScore <http://translate.musescore.org>, which will redirect you to <https://www.transifex.com/projects/p/musescore>
3. (Select the language and then the section you want to help with (musescore or instruments
4. (...Click on the "translate" button (the button text will depend on your language
5. ("Search for "strings" (informational meaning) you want to translate (you could filter "already translated items

Here is a technical explanation: [Continuous translation for MuseScore 2.0](#)

Website and handbook translation

See [Translation instructions](#)

See also

- [Language Settings and Update Translation](#), [Update Translation](#)

How to ask for support or file bug reports

:Before submitting your support request in the [forum](#), please

- (Look for a solution in the [Handbook](#) (search the [Handbook](#)
- Check the [How Tos](#), [FAQ](#) and [Tutorials](#)
- [Search](#) the forums of the website to see if someone has already encountered the same problem

:(If posting in either the [issue tracker](#) (for established reports), or [forum](#) (for inquiries/discussions

Try to reproduce the issue with [the latest nightly](#). You may also view and [version history](#) to check whether it

.has been fixed/implemented already

:Please include as much of the following information as you know and limit each issue to one report •

Version/revision of MuseScore you are using (e.g. version 2.1, revision [871c8ce](#) ↗). Check Help → About... ◦

.(...(Mac: MuseScore → About MuseScore

(Operating system being used (e.g. Windows 7, macOS 10.12 or Ubuntu 14.04 ◦

If reporting a bug, describe the precise steps that lead to the problem (where do you click, what keys do you ◦

.(.press, what do you see, etc

If you are not able to reproduce the problem with the steps, it is probably not worth reporting it as the developers will not be able to reproduce (and solve) it either. Remember that the goal of a bug report is not

.only to show the problem, but to allow others to reproduce it easily

:Please remember •

attach the score that shows the problem —use the "File attachments" option at the bottom of the page, just ◦

.above the Save and Preview buttons when you're typing your post

External links

[How to write a good bug report: step-by-step instructions](#) ↗ •


Revert to factory settings

Recent versions of MuseScore have the option to revert back to the standard built-in presets or "factory-settings". This can be necessary if your settings are corrupted. **Warning:** Reverting to factory settings removes any changes you have made to the preferences, palettes, or window settings. This is not a commonly needed procedure; consult the forums first, .as there may be a way to solve your problem without resetting everything

MuseScore 2.0.3 and above

.In recent versions it is possible to revert from within MuseScore, providing that MuseScore itself is able to start

.Go to Help → Revert to Factory Settings. A warning dialog will appear



Clicking Yes resets all MuseScore's settings as if the program was installed for the first time, and MuseScore will .immediately restart. No will safely cancel the revert

MuseScore 2.0 through 2.0.2

.In older versions of MuseScore, or in later versions if they do not start, you must run this process via the command line

Instructions for Windows

(If you have MuseScore open, you need to close it first (File → Quit .1

Type Windows key+R to open the Run dialog (The [Windows key](#) ↗ is the one with the logo for Microsoft Windows). .2

.Alternatively select Start using your mouse

...Click Browse .3

Look for MuseScore.exe on your computer. The location may vary depending on your installation, but it is probably .4

something similar to My Computer → Local Disk → Program Files (or Program Files (x86)) → MuseScore 2 → bin

→ MuseScore.exe

Click Open to leave the Browse dialog and return to the Run dialog. The following text (or something similar) should .5

display in the Run dialog

(C:\Program Files\MuseScore 2\bin\MuseScore.exe (actually %ProgramFiles%\MuseScore 2\bin\MuseScore.exe

For 64-bit Windows, the location is

(C:\Program Files (x86)\MuseScore 2\bin\MuseScore.exe (actually %ProgramFiles(x86)%\MuseScore 2\bin\MuseScore.exe

For the Windows Store version (Windows 10), it is pretty well hidden, search for it via Windows Explorer

Click after the quote and add a space followed by a hyphen and a capital F: F .6

Press OK .7

. "After a few seconds, MuseScore should start and all the settings reverted to "factory settings

: For advanced users, the main preference file is located at

Windows Vista or later: C:\Users\<USERNAME>\AppData\Roaming\MuseScore\MuseScore2.ini •

(actually %APPDATA%\MuseScore\MuseScore2.ini)

Windows XP or earlier: C:\Documents and Settings\<USERNAME>\Application Data\MuseScore\MuseScore2.ini •

: The other preferences (palettes, session, shortcuts, workspaces...) are in

\Windows Vista or later: C:\Users\<USERNAME>\AppData\Local\MuseScore\MuseScore2 •

(actually %APPDATA%\MuseScore\MuseScore2)

\Windows XP or earlier: C:\Documents and Settings\<USERNAME>\Local Settings\Application Data\MuseScore\MuseScore2 •

For the Windows Store version (Windows 10), these are pretty well hidden, search for them via Windows Explorer

Instructions for MacOS

(If you have MuseScore open, you need to quit the application first (MuseScore → Quit .1

Open Terminal (in Applications/Utilities, or via Spotlight search) and a session window should appear .2

:(Type (or copy/paste) the following command into your terminal line (include the '/' at the front .3

```
Applications/MuseScore\ 2.app/Contents/MacOS/mscore -F/
```

This resets all MuseScore preferences to factory settings and immediately launches the MuseScore application. Note that you cannot quit the Terminal without quitting MuseScore. You can safely quit MuseScore, quit the Terminal, and then .reopen MuseScore in the normal fashion, ready to continue using

. For advanced users, the main MuseScore preference file is located at ~/Library/Preferences/org.musescore.MuseScore2.plist

./The other preferences (palettes, session, shortcuts, workspaces...) are in ~/Library/Application\ Support/MuseScore/MuseScore2

Instructions for Linux

.The following is true for Ubuntu, and most likely all other Linux distributions and UNIX-style operating systems

(If you have MuseScore open, you need to quit the application first (File → Quit .1

From the Ubuntu main menu, choose Applications → Accessories → Terminal. A Terminal session window should appear .2

:(Type, (or copy/paste) the following command into your terminal line (Ctrl+Shift+V to paste in Terminal .3

```
mscore -F
```

Or, if you are using the Applmage version, you must first use the `cd` command to change directory to wherever you :saved the Applmage. For example, if you saved it to your Desktop

```
cd ~/Desktop  
MuseScore*.Applmage -F/.
```

This resets all MuseScore preferences to factory settings and immediately launches the MuseScore application. You can .now quit Terminal, and continue using MuseScore

.For advanced users, the main MuseScore preference file is located at ~/.config/MuseScore/MuseScore2.ini

.The other preferences (palettes, session, shortcuts, workspaces...) are in ~/.local/share/data/MuseScore/MuseScore2

See also

[Command line options](#) •

Known incompatibilities

Hardware incompatibilities

.The following software is known to crash MuseScore on startup

- Samson USB Microphone, driver name "Samson ASIO Driver", samsonasiodriver.dll. [More info](#) ↗ •
- Digidesign MME Refresh Service. [More info](#) ↗ •
- Windows XP SP3 + Realtek Azalia Audio Driver. [More info](#) ↗ •
- Wacom tablet. [More info](#) ↗ and [QTBUG-6127](#) ↗ •

Software incompatibilities

- .Maple virtual cable is [known to prevent MuseScore](#) ↗ from closing properly •
- KDE (Linux) window settings can cause the whole window to move when dragging a note. [Changing the window settings of the operating system](#) avoids the problem •
- Nitro PDF Creator may [prevent MuseScore 2 from starting](#) ↗ on Windows 10, if being used as the default printer. •
- .Same for Amyuni/Quickbooks PDF Printer, see [here](#) ↗ and also some cloud printing services, see [here](#) ↗ •
- .Creative Sound Blaster Z Series ASIO driver may [prevent MuseScore 2 from starting](#) ↗ on Windows 10 •
- Untrusted Font Blocking policy [prevents MuseScore 2 from starting](#) ↗ (except in debug mode, i.e. using the -d option) on Windows 10. (Solution in [the links provided here](#) ↗ •

AVG Internet Security hangs MuseScore

MuseScore requires access to your internet connection with AVG. MuseScore doesn't need an internet connection to function, but if AVG blocks it, MuseScore hangs

".If AVG prompts you, **Allow** MuseScore and check "Save my answer as a permanent rule and do not ask me next time

,If it doesn't prompt you anymore

- Open the AVG user interface (right-click on the AVG icon, close to your clock -> Open AVG User Interface.1
- Click on *Firewall* .2
- Click *Advanced Settings* .3
- Click *Applications* .4
- Find MSCORE.EXE in the list and double click it .5
- Change *Application Action* to **Allow for All** .6

Font problem on macOS

.MuseScore is known to display notes as square when some fonts are damaged on macOS
:To troubleshoot this issue

- Go to Applications -> Font Book .1
- Select a font and press ⌘+A to select them all .2
- Go to File -> Validate Fonts .3
- If any font is reported as damaged or with minor problems, select it and delete it .4
- Restart MuseScore if necessary .5

In [Bug in noteheads](#) ↗, a user believes to have found the font "Adobe Jenson Pro (ajenson)" to be the culprit, regardless of not being reported as broken, or problematic as per the above validation, and solved the problem by deleting that font, so this is worth checking too

Font problem on Linux

.If the default desktop environment application font is set to bold, MuseScore will not display the notes properly
:(To troubleshoot this issue (gnome 2.*/MATE users

- Right-click on your desktop and select Change Desktop background .1
- Click on Fonts tab .2
- Set Regular style for Application font .3
- Restart MuseScore if necessary .4

For GNOME 3/SHELL users

- "Open the shell and open "Advanced Settings .1
- Click on the Fonts option in the list .2
- Set the default font to something non-bold .3
- Restart MuseScore if necessary .4

Save As dialog empty on Linux

.Some users reported that the Save As dialog is empty on Debian 6.0 and Lubuntu 10.10
:To troubleshoot this issue

Type the following in a terminal .1

which mscore

The command will answer with the path of mscore. Edit it with your preferred text editor and add the following line at .2
the beginning

```
export QT_NO_GLIB=1
```

.Launch MuseScore and the problem should be solved

Appendix

Keyboard shortcuts

Most keyboard shortcuts can be customized via the menu: select Edit → Preferences... → Shortcuts (Mac: MuseScore → Preferences... → Shortcuts). Below is a list of some of the initial shortcut settings

Navigation

(←+Beginning of score: Home (Mac: Fn

(→+Last page of score: End (Mac: Fn

(Find (measure number, rehearsal mark, or pXX when XX is a page number):Ctrl+F (Mac: Cmd+F

Next score: Ctrl+Tab

Previous score: Shift+Ctrl+Tab

Zoom in: Ctrl++ (doesn't work on some systems) (Mac: Cmd++); or Ctrl (Mac: Cmd) + scroll up

Zoom out: Ctrl+- (Mac: Cmd+-); or Ctrl (Mac: Cmd) + scroll down

(↓+Next page: Pg Dn; or Shift + scroll down (Mac: Fn

(↑+Previous page: Pg Up; or Shift + scroll up (Mac: Fn

(→+Next measure: Ctrl+→ (Mac: Cmd

(←+Previous measure: Ctrl+← (Mac: Cmd

→ :Next note

← :Previous note

↓+Note below (within a chord or on lower staff):Alt

↑+Note above (within a chord or on higher staff): Alt

(Top note in chord: Ctrl+Alt+↑ (Ubuntu uses this shortcut for Workspaces instead
(Bottom note in chord: Ctrl+Alt+↓ (Ubuntu uses this shortcut for Workspaces instead

Note input

Begin note input mode:N

Leave note input mode: N or Esc

Duration

.selects a duration. See also Note input 9 ... 1

Half duration of previous note:Q

Double duration of previous note:W

Decrease duration by one dot: (as of version 2.1) Shift+Q (e.g. a dotted quarter note becomes a quarter note; a quarter note becomes a dotted eighth note)

Increase duration by one dot : (as of version 2.1) Shift+W (e.g. an eighth note becomes a dotted eighth note; a dotted eighth note becomes a quarter note)

Voices

.To select a voice in note input mode

(Voice 1: Ctrl+Alt+1 (Mac: Cmd+Option+1

(Voice 2: Ctrl+Alt+2 (Mac: Cmd+Option+2

(Voice 3: Ctrl+Alt+3 (Mac: Cmd+Option+3

(Voice 4: Ctrl+Alt+4 (Mac: Cmd+Option+4

Pitch

.Pitches can be entered by their letter name (A-G), or via MIDI keyboard. See Note input for full details

(Repeat previous note or chord:R (the repeat can be of a different note value by selecting duration beforehand

(Repeat selection: R (The selection will be repeated from the first note position after the end of the selection

(↑+Raise pitch by octave: Ctrl+↑ (Mac: Cmd

(↓+Lower pitch by octave: Ctrl+↓ (Mac: Cmd

↑:(Raise pitch by semi-tone (prefer sharp

↓:(Lower pitch by semi-tone (prefer flat

↑+Raise pitch diatonically: Alt+Shift

↓+Lower pitch diatonically: Alt+Shift

Change enharmonic spelling in *both* written *and* concert pitch views:J

(Change enharmonic spelling in *current* view only: Ctrl+J (Mac: Cmd+J

(Rest: 0 (zero

Interval

[Add interval above current note: Alt+[Number

Layout

Flip direction (stem, slur, tie, tuplet bracket, etc.):X

Mirror note head: Shift+X

{:(Increase stretch of measure(s

Line break on selected barline: Return

(Page break on selected barline: Ctrl+Return (Mac: Cmd+Return

Adjust space above a staff (except the top staff) for the whole score: Press Shift, click on the staff and drag

Articulations

Staccato: Shift+S

Tenuto: Shift+N

Sforzato (accent): Shift+V

Marcato: Shift+O

/:(Grace note (acciaccatura

> :Crescendo
< :Decrescendo

Text entry

(Staff text: Ctrl+T (Mac:Cmd+T)
(System text: Ctrl+Shift+T (Mac: Cmd+Shift+T)
Tempo text: Alt+T
(Rehearsal Mark: Ctrl+M (Mac: Cmd+M)

Lyrics entry

(Enter lyrics on a note: Ctrl+L (Mac: Cmd+L)
Previous lyric syllable: Shift+Space
Next lyric syllable: if the current and the next syllables are separated by a '-': -, else Space
← :Move lyric syllable left by 0.1sp
→ :Move lyric syllable right by 0.1sp
(←+Move lyric syllable left by 1sp: Ctrl+← (Mac: Cmd
(→+Move lyric syllable right by 1sp: Ctrl+→ (Mac: Cmd
←+Move lyric syllable left by 0.01sp: Alt
→+Move lyric syllable right by 0.01sp: Alt

(↑+Up to previous stanza: Ctrl+↑ (Mac: Cmd
(↓+Down to next stanza: Ctrl+↓ (Mac: Cmd

.For more lyric shortcuts, see [Lyrics](#)

Display

(Navigator: F12 (Mac: fn+F12)
(Play Panel: F11 (Mac: fn+F11)
(Mixer: F10 (Mac: fn+F10)
(Palette: F9 (Mac: fn+F9)
(Inspector: F8 (Mac: fn+F8)
Piano Keyboard: P
Selection filter: F6
Display full screen: Ctrl+U

Miscellaneous

Toggle visibility on selected element(s): V
Show Instruments dialog: I
Toggle multi-measure rests on or off: M

See also

[Preferences: Shortcuts](#) •

Known limitations of MuseScore 2.x

While all members of the development team did their best to make the software easy to use and bug-free, there are some .known issues and limitations in MuseScore 2.x

Local time signatures

The local time signature feature, which allows you to have different time signatures in different staves at the same time, is very limited. You can only add a local time signature to measures that are empty, and only if there are no linked parts. When adding notes to measures with local time signatures, you can enter notes normally via note input mode, but copy and paste does not work correctly and may lead to corruption or even crashes. The join and split commands are disabled .for measures with local time signatures

Regroup Rhythms

The Regroup Rhythms command found under the Layout menu may have unintended side effects, including changing the spelling of pitches and deleting some elements like articulations, glissandos, tremolos, grace notes and, esp. on undo, ties. Use this tool with caution on limited selections, so that you can tell if any unwanted changes are made

Tablature staff linked with standard staff

When entering multiple-note chords on a standard staff in a linked staff/tablature system, the notes should be entered in order from the top (first) string to the bottom string to ensure correct fret assignment

This limitation does not apply if entering notes directly onto a tablature staff, or when using an unlinked staff/tablature system

Mixer

Changing settings in the mixer other than the sound doesn't mark the score 'dirty'. That means if you close a score you may not get the warning "Save changes to the score before closing?". Changing mixer values are also not undoable

Header & footer

There is no way to edit Header and Footer in a WYSIWYG manner. The fields in Style → General → Header, Footer, Numbers are plain text. They can contain "HTML like" syntax, but the text style, layout, etc. can't be edited with a WYSIWYG editor

Command line options

You can launch MuseScore from the command line by typing

- (mscore [options] [filename]) (Mac and Linux •
- (MuseScore.exe [options] [filename]) (Windows •

[options] and [filename] are optional. For this to work the MuseScore executable must be in %PATH% (Windows) resp. \$PATH (Mac and Linux). If it is not, see [Revert to factory settings](#) for detailed instructions on how and where to find and execute the MuseScore executable from the command line on the various supported platforms

The following options are available

- h, --help- ,?- (Display help (doesn't work on Windows
- v, --version- Displays MuseScore's current version in the command line without starting the graphical interface (doesn't work on Windows
- long-version-- Displays MuseScore's current version and revision in the command line without starting the graphical interface ((doesn't work on Windows
- d, --debug- Starts MuseScore in debug mode
- L, --layout-debug- Starts MuseScore in layout debug mode
- s, --no-synthesizer- Disables the integrated software synthesizer
- m, --no-midi- Disables MIDI input
- <a, --use-audio <driver- Use audio driver: jack, alsa, pulse, portaudio
- n, --new-score- Starts with the new score wizard regardless of preference setting for start mode
- l, --dump-midi-in- Displays all MIDI input on the console
- O, --dump-midi-out- Displays all MIDI output on the console
- <o, --export-to <filename-

Exports the currently opened file to the specified <filename>. The file type depends on the filename extension. This option switches to the "converter" mode and avoids any graphical interface. You can also add a filename before the -

"o if you want to import and export files from the command line. For example: `mscore -o "My Score.pdf" "My Score.mscz`
`<r, --image-resolution <dpi>`

Determines the output resolution for the output to PNG images in the converter mode. The default resolution is
taken from [Preferences, Export, PNG/SVG](#)

`<T, --trim-image <margin>`
Trims exported PNG and SVG images to remove surrounding whitespace around the score. The specified number
of pixels of whitespace will be added as a margin; use 0 for a tightly cropped image. For SVG, this option works only
with single-page scores

`<x, --gui-scaling <factor>`
Scales the score display and other GUI elements by the specified factor, for use with high resolution displays
`<D, --monitor-resolution <dpi>`

(Specify monitor resolution, for use with high resolution displays (as of version 2.1
`<S, --style <style>`

Loads a style file; useful when you convert with the -o option
`<p, --plugin <name>`

Execute the named plugin
`template-mode--`

Save template mode, no page size
`F, --factory-settings-`

Use only the standard built-in presets or "factory-settings" and delete preferences. For details, see [Revert to factory settings](#)

`R, --revert-settings-`
Use only the standard built-in presets or "factory-settings", but do not delete preferences

`i, --load-icons-`
Load icons from the file system. Useful if you want to edit the MuseScore icons and preview the changes

`<j, --job <filename>`
(Process a conversion job (as of version 2.1

`e, --experimental-`
Enable experimental features. See e.g. [Layer \(experimental\)](#)

`<c, --config-folder <pathname>`
Set config path

`t, --test-mode-`
Enable test mode

`<M, --midi-operations <filename>`
Specify MIDI import operations file; See this example file: [midi_import_options.xml](#)

`w, --no-webview-`
No web view in Start Center

`P, --export-score-parts-`
Used with -o <filename>.pdf, export score and parts

`no-fallback-font--`
Don't use Bravura as fallback musical font

`f, --force-`
(Used with -o, ignore warnings reg. score being corrupted or from wrong version (as of version 2.1

`<b, --bitrate <bitrate>`
(Used with -o <filename>.mp3, sets bitrate in kbps (as of version 2.1

`<E, --install-extension <extension file>`
(Install an extension, load soundfont as default unless if -e is passed too (as of version 2.3

Qt Toolkit Options

`<style= <style>`
`<style <style>`

Determines the style of the GUI application. Possible values are "motif", "windows" and "platinum". Depending on
the platform other styles may be available

`<stylesheet= <stylesheet>`
`<stylesheet <stylesheet>`

Sets the application stylesheet. The value of "stylesheet" is a path to a file that contains the stylesheet
`<[platform <platformname>]:options-`

Specifies the Qt Platform Abstraction (QPA) plugin
Example: `MuseScore.exe -platform windows:fontengine=freetype`

See also

External links

- [How to use the "conversion job" command-line option](#) ↗ •
- [\(Layer \(experimental](#) ↗ •
- <http://doc.qt.io/qt-5/qapplication.html#QApplication> ↗ •
- <http://doc.qt.io/qt-5/qguiapplication.html#QGuiApplication> ↗ •

Glossary

.The glossary is a work in progress—please help if you can. You can discuss this page in the [documentation forum](#) ↗

The list below is a glossary of frequently used terms in MuseScore as well as their meaning. The differences between American English and British English are marked with "(AE)" and "(BE)", respectively

Acciaccatura

A short [→ grace note](#) which appears as a small note with a stroke through the stem. It is quickly executed and  technically takes no value from its associated note

[Accidental](#)

A sign appearing in front of a note that raises or lowers its pitch. The most common accidentals are [→ sharps](#), [→ flats](#) or [→ naturals](#), but double sharps and double flats are also used. Also [→ koron](#), and [→ sori](#) and other quarter tone accidentals. Accidentals affect all notes on the same [→ staff](#) position only for the remainder of the measure in which they occur, but they can be canceled by another accidental. In notes tied across a [→ barline](#), the accidental continues across the [→ barline](#) to the tied note, but not to later untied notes on the same [→ staff](#) position in that measure

Anacrusis

.See [→ Pickup measure](#)

Anchor

The point of attachment to the score of objects such as Text and Lines: When the object is dragged, the anchor appears as small brown circle connected to the object by a dotted line. Depending on the object selected, its anchor (may be attached to either (a) a note (e.g. fingering), (b) a staff line (e.g. staff text), or (c) a barline (e.g. repeats

Appoggiatura

A long [→ grace note](#) which takes value from its associated note. Its functions include: passing tone, anticipation, struck suspension, and escape tone

(Bar (BE

.See [→ measure](#)

[Barline](#)

.Vertical line through a [→ staff](#), staves, or a full [→ system](#) that separates [→ measures](#)

[Beam](#)

Notes with a duration of an [→ eighth](#) ↗ or shorter either carry a [→ flag](#) or a beam. Beams are used for grouping notes

BPM

Beats Per Minute is the unit for measuring tempo. See [→ metronome mark](#)

Breve

Brevis

.A **double whole note** or **breve** is a note that has the duration of two whole notes

Cent

.An interval equal to one hundredth of a semitone

Chord

A group of two or more notes sounding together. To select a chord in MuseScore, press **Shift** and click on a note. In (the [Inspector](#), however, the word "Chord" only covers notes in the same voice as the selected note(s

[Clef](#)

.Sign at the beginning of a [→ staff](#), used to tell which are the musical notes **on** the lines and **between** the lines .Clefs are very useful for [→ transposition](#)

[Concert pitch](#)

.(Enables you to switch between concert pitch and transposing pitch (see [Concert pitch](#) and [Transposition](#)

(Crotchet (BE

.See [→ Quarter note](#)

(Demisemiquaver (BE

.A thirty-second note

Duplet

.See → [tuple](#)
[Edit mode](#)
 .The program mode from which you can edit various score elements
 Eighth note
 .(A note whose duration is an eighth of a whole note (semibreve). Same as a **quaver** (BE
 Endings
 .See → [volta](#)
 Enharmonic notes
 .Notes that sound the same pitch but are written differently. Example: G[#] and A^b are enharmonic notes
 Flag
 .See → [beam](#)
 Flat
 .Sign (b) that indicates that the pitch of a note has to be lowered one semitone
[Grace note](#)
 .Grace notes appear as small notes in front of a normal-sized main note. See [-acciaccatura](#) and → [appoggiatura](#)
 (Grand Staff (AE
 (Great Stave (BE
 A system of two or more staves, featuring treble and bass clefs, used to notate music for keyboard instruments and
 .the harp
 Half Note
 .(A note whose duration is half of a whole note (semibreve). Same as a **minim** (BE
 (Hemidemisemiquaver (BE
 .A sixty-fourth note
 Interval
 The difference in pitch between two notes, expressed in terms of the scale degree (e.g. major second, minor third,
 .(perfect fifth etc.). See [Degree \(Music\)](#) ↗ (Wikipedia
[Jump](#)
 .In MuseScore, "jumps" are notations such as "D.S. al Coda", found in the "Repeats & Jumps" palette
[Key Signature](#)
 Set of → [sharps](#) or → [flats](#) at the beginning of the → [staves](#). It gives an idea about the tonality and avoids repeating
 .those signs all along the → [staff](#)
 .A key signature with B flat means F major or D minor tonality
 Koron
 An Iranian → [accidental](#) which lowers the pitch of a note by a quarter tone (in comparison to the [-flat](#) which lowers a
 .note by a semitone). It is possible to use this accidental in a → [key signature](#)
 .See also → [sori](#)
 Longa
 .A **longa** is a **quadruple whole note**
 Ledger Line
 .Line(s) that are added above or below the staff
 (Measure (AE
 A segment of time defined by a given number of beats. Dividing music into bars provides regular reference points to
 .(pinpoint locations within a piece of music. Same as → [bar](#) (BE
 Metronome mark
 Metronome marks are usually given by a note length equaling a certain playback speed in [-BPM](#). In MuseScore,
 .metronome marks are used in [Tempo texts](#)
 (Minim (BE
 .See → [Half note](#)
[Natural](#)
 .A natural (♮) is a sign that cancels a previous alteration on notes of the same pitch
 Normal mode
 The operating mode of MuseScore *outside* [note input mode](#) or [edit mode](#): press Esc to enter it. In **Normal mode** you
 can navigate through the score, [select](#) and move elements, adjust Inspector properties, and alter the pitches of
 .existing notes
[Note input mode](#)
 .The program mode used for entering music notation
 Operating System
 OS
 Underlying set of programs which set up a computer, enabling additional programs (such as MuseScore). Popular
 .OSes are Microsoft Windows, macOS, and GNU/Linux
 .Not to be confused with a sheet music → [system](#)
 Part

Music to be played or sung by one or a group of musicians using the same instrument. In a string quartet, 1st part = Violin 1, 2nd part = Violin 2, 3rd part = Viola, 4th part = Cello, in a choir there might be parts for soprano, alto, tenor (and bass. A part has one or more → [staves](#) (e.g. Piano has 2 staves, Organ can have 2 or 3 staves (Pickup Measure (also known as an Anacrusis or Upbeat

Incomplete first measure of a piece or a section of a piece of music. See [Measure duration](#) and [Create new score: Pickup measure](#). Also [Exclude from measure count](#)

Quadruplet
 .See → [tuplet](#)

Quarter note
 .(A note whose duration is a quarter of a whole note (semibreve). Same as a **crotchet** (BE (Quaver (BE .See → [eighth note](#)

Quintuplet
 .See → [tuplet](#)

Respell Pitches
 .(Tries to guess the right accidentals for the whole score (see [Accidentals](#)

Rest
 .Interval of silence of a specified duration

[Re-pitch mode](#)
 .Allows you to rewrite an existing passage of music by changing the note pitches without altering the rhythm (Semibreve (BE .A **whole note** (AE). It lasts a whole measure in 4/4 time (Semiquaver (BE .A sixteenth note (Semihemidemisemiquaver (Quasihemidemisemiquaver) (BE .An hundred and twenty eighth note

Sextuplet
 .See → [tuplet](#)

SFZ
 A virtual instrument format supported by MuseScore (along with → [SoundFonts](#)). An SFZ library consists of one or more SFZ text files, each defining a particular instrument setup, and many audio sound samples

Sharp
 .Sign (#) that indicates that the pitch of a note has to be raised one semitone

[Slur](#)
 A curved line over or under two or more notes, meaning that the notes will be played smooth and connected .((*legato* .See also → [tie](#)

Sori
 An Iranian → [accidental](#) which raises the pitch of a note by a quarter tone (in comparison to the sharp which raises it .by a semitone). It is possible to use this accidental in a → [key signature](#) .See also → [koron](#)

[SoundFont](#)
 A virtual instrument format supported by MuseScore (along with → [SFZ](#)). A **SoundFont** is a special type of file (extension .sf2, or .sf3 if compressed) containing sound samples of one or more musical instruments. In effect, a virtual synthesizer which acts as a sound source for MIDI files. MuseScore 2.2 comes with the SoundFont ."MuseScore_General.sf3" pre-installed

(Spatium (plural: Spatia
 Space
 Staff Space
 (sp (abbr./unit

The distance between two lines of a normal 5-line staff. In MuseScore this unit influences most size settings. See .also [Page settings](#)

(Staff (AE
 (Stave (BE

Group of one to five horizontal lines used to lay on musical signs. In ancient music notation (before 11th century) the .(staff/stave may have any number of lines (the plural of 'staff' is 'staves', in BE and AE

Step-time input
 .MuseScore's default [note input mode](#), allowing you to enter music notation one note (or rest) at a time

System
 .Set of staves to be read simultaneously in a score .(See also → [Operating System \(OS](#)

[Tie](#)

:A curved line between two or more notes on the same pitch to indicate a single note of combined duration

- Quarter note + Tie + Quarter note = Half note •
- Quarter note + Tie + Eighth note = Dotted Quarter note •
- Quarter note + Tie + Eighth note + Tie + 16th note = Double Dotted Quarter note •

.See also → [slur](#)

Transposition

The act of moving the pitches of one or more notes up or down by a constant interval. There may be several reasons for transposing a piece, for example

- 1 The tune is too low or too high for a singer. In this case the whole orchestra will have to be transposed as well .—easily done using MuseScore
- 2 The part is written for a particular instrument but needs to be played by a different one
- 3 The score is written for an orchestra and you want to hear what the individual instruments sound like. This .requires changing the transposing instrument parts to concert pitch
- 4 A darker or a more brilliant sound is desired

Triplet

.See → [triplet](#)

Tuplet

A tuplet divides its next higher note value by a number of notes other than given by the time signature. For example a → [triplet](#) divides the next higher note value into three parts, rather than two. Tuplets may be: [triplets](#), → [duplets](#), . → [quintuplets](#), and other

Upbeat

.See → [pickup measure](#)

Velocity

The velocity property of a note controls how loudly the note is played. This usage of the term comes from MIDI synthesizers. On a keyboard instrument, it is the speed with which a key is pressed that controls its volume. The .(usual scale for velocity is 0 (silent) to 127 (maximum

Voice

Polyphonic instruments like Keyboards, Violins, or Drums need to write notes or chords of different duration at the same time on the same → [staff](#). To write such things each horizontal succession of notes or chords has to be written on the staff independently. In MuseScore you can have up to 4 voices per staff. Not to be confused with vocalists, .singing voices like soprano, alto, tenor and bass, which are better viewed as instruments

Volta

In a repeated section of music, it is common for the last few measures of the section to differ. Markings called *voltas* are used to indicate how the section is to be ended each time. These markings are often referred to simply as . → [endings](#)

External links

- <http://www.robertcarney.net/musical-terms-definitions.htm> ↗ •
- https://en.wikipedia.org/wiki/List_of_musical_symbols ↗ •

Table of Contents

Getting started

- [Installation](#) •
- [Create new score](#) •
- [Language settings and translation updates](#) •
- [Checking for updates](#) •

Basics

- ([Create new score](#) (→ [Getting started](#) •
- [Note input](#) •
- [Concert pitch](#) •
- [Copy and paste](#) •
- [Edit mode](#) •

- [Measure operations](#) •
- [Palette](#) •
- [Preferences](#) •
- [Save/Export/Print](#) •
- [Selection modes](#) •
- [Undo and redo](#) •
- [View modes](#) •
- [File format](#) •
- [Share scores online](#) •

Notation

- [\(Note input \(→ Basics](#) •
- [\(Palette \(→ Basics](#) •
- [Accidental](#) •
- [Arpeggio and glissando](#) •
- [Bar line](#) •
- [Beam](#) •
- [Bracket](#) •
- [Breath and pause](#) •
- [Clef](#) •
- [Drum notation](#) •
- [Grace note](#) •
- [Hairpin](#) •
- [Key signature](#) •
- [Lines](#) •
- [Measure rest](#) •
- [Repeat](#) •
- [Slur](#) •
- [Tie](#) •
- [Time signature](#) •
- [Transposition](#) •
- [Tremolo](#) •
- [Tuplet](#) •
- [Voices](#) •
- [\(Volta \(1st and 2nd time endings](#) •

Sound and playback

- [MIDI import](#) •
- [Mid-staff instrument change](#) •
- [Play mode](#) •
- [Soundfont](#) •
- [Swing](#) •
- [Tempo](#) •
- [Dynamics](#) •
- [Change and adjust sound](#) •

Text

- [Grid-based movement of symbols and staff text](#) •
- [Rehearsal marks](#) •
- [Text editing](#) •
- [Text style](#) •
- [Chord symbols](#) •
- [Fingering](#) •
- [Lyrics](#) •
- [\(Tempo \(→ Sound and playback](#) •

Formatting

- ([Layout and formatting](#) (overview) •
- [Breaks and spacers](#) •
- [Frame](#) •
- [Image](#) •
- [Image capture](#) •

Advanced topics

- [Accessibility](#) •
- [Album](#) •
- [Cross staff beaming](#) •
- [Custom palette](#) ↗ •
- [Early music features](#) •
- [Figured bass](#) •
- [Fretboard diagram](#) •
- [Inspector and object properties](#) •
- [Master palette](#) •
- [Part extraction](#) •
- [Plugins](#) •
- [Replace pitches without changing rhythms](#) ↗ •
- [Score information](#) •
- [Staff type properties](#) •
- [Tablature](#) •
- [Tools](#) •
- Nonexistant node nid: 39841 •

New features in MuseScore 2.0

- [What's New in MuseScore 2](#) ↗ •
- [MuseScore 2.0 Release Notes](#) ↗ •
- [.Changes for MuseScore 2.0](#) ↗ •
 - ([Album](#) (→ [Advanced topics](#)) •
 - ([View modes: Continuous view](#) and [Navigator](#) (→ [Basics](#)) •
 - ([Copy and paste: Selection filter](#) (→ [Basics](#)) •
 - ([Custom palette](#) ↗ (→ [Advanced topics](#)) •
 - ([Early music features](#) (→ [Advanced topics](#)) •
 - ([Figured bass](#) (→ [Advanced topics](#)) •
 - ([Grid-based movement of symbols and staff text](#) (→ [Text](#)) •
 - ([Image capture](#) (→ [Formatting](#)) •
 - ([Inspector and object properties](#) (→ [Advanced topics](#)) •
 - ([Measure operations: Split and join](#) (→ [Basics](#)) •
 - ([MIDI import](#) (→ [Sound and playback](#)) •
 - ([Mid-staff instrument change](#) (→ [Sound and playback](#)) •
 - ([Part extraction \(new options available\)](#) (→ [Advanced Topic](#)) •
 - ([Rehearsal marks: Automatic next rehearsal mark](#) and [Search for a rehearsal mark](#) (→ [Text](#)) •
 - ([Save/Export](#) (→ [Basics](#)) - [Staff type properties](#) (→ [Advanced topics](#)) •
 - ([Swing](#) (→ [Sound and playback](#)) •
 - ([Tablature](#) (→ [Advanced topics](#)) •
 - ([Nonexistant node nid: 39841](#) (→ [Advanced topics](#)) •
 - ([Master palette](#) (→ [Advanced topics](#)) •
- [Layout and formatting](#) (some options have changed, and there is a new "apply to all parts" feature) •
 - ((→ [Formatting](#)) •
 - ([Breaks and spacers, section break](#) (→ [Formatting](#)) •
 - ([Selection modes, select all similar new options \(same subtype\)](#)(→ [Basics](#)) •
 - ([Create a new score, start center](#)(→ [Basics](#)) •
 - ([Languages settings and translation Updates](#) (→ [Basics](#)) •
 - ([Helping and improve translation](#) (→ [Support](#)) •
 - ([Accidentals, respell pitches](#) (→ [Notation](#)) •
 - ([Replace pitches without changing rhythms](#) ↗ (→ [Advanced topics](#)) •
 - ([Tools](#) (→ [Advanced topics](#)) •

[\(Meta tags \(→ Advanced topics](#) ◦
[Upgrading from MuseScore 1.x](#) ◦

Support

- [Helping and improve translation](#)
- [How to ask for support or file reports](#)
- [Revert to factory settings](#)
- [Known incompatibilities](#)

Appendix

- [Keyboard shortcuts](#)
 - [Known limitations of MuseScore 2.x](#)
 - [Command line options](#)
 - [Glossary](#)
 - [Handbook for MuseScore 1.x](#) ↗
-